

SP	CODE NO.	ITEM	UNIT	100% STATE FUNDING					
				TOTAL QUANTITY	URBAN ROADWAY J000-2A	HIGHWAY LIGHTING Y030-1E	PEDESTRIAN BRIDGE STR NO 082-0394 X932-2A	RETAINING WALL STR NO 082-W228 Y007	RETAINING WALL STR NO 082-W229 Y007
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,396	1,396				
	70400100	TEMPORARY CONCRETE BARRIER	FOOT	1,870	1,870				
*	72000200	SIGN PANEL - TYPE 2	SQ FT	14	14				
*	73000100	WOOD SIGN SUPPORT	FOOT	31	31				
*	73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1	1				
*	73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	4	4				
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7,262	7,262				
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	89	89				
*	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	328	328				
*	78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	114	114				
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	2,531	2,531				
*	80400100	ELECTRIC SERVICE INSTALLATION	EACH	1		1			
*	81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	40		40			
*	81100805	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., PVC COATED GALVANIZED STEEL	FOOT	10		10			
*	81300550	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 12" X 6"	EACH	1		1			
*	81400730	HANDHOLE, COMPOSITE CONCRETE	EACH	1		1			
*	81603000	UNIT DUCT, 600V, 2-1C NO.8, 1/C NO.8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	760		760			
*	81603030	UNIT DUCT, 600V, 2-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	1,090		1,090			
*	81800230	AERIAL CABLE, 2-1/C NO. 6 WITH MESSENGER WIRE	FOOT	480		480			
*	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1,600		1,600			
*	82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	9		9			
*	82500530	LIGHTING CONTROLLER TYPE CB-RCS 100AMP - 240VOLT	EACH	1		1			
*	83057290	LIGHT POLE, WOOD, 50 FOOT, CLASS 4	EACH	2		2			
*	83057355	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH 15FT MAST ARM	EACH	9		9			
*	83600110	LIGHT POLE FOUNDATION (SPECIAL)	EACH	8		8			
*	84100110	REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	10		10			
*	84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	1		1			
*	84200700	LIGHTING FOUNDATION REMOVAL	EACH	9		9			
*	84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	8		8			
*	A2006930	TREE, QUERCUS PALUSTRIS (PIN OAK), 3" CALIPER, BALLED AND BURLAPPED	EACH	3	3				
*	X0321781	MECHANICAL SPLICE	EACH	594			594		
	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	48	48				
*	X0322508	PEDESTRIAN TRUSS SUPERSTRUCTURE	SQ FT	10,127			10,127		
*	X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MD	48			48		
*	X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	1,802			1,802		
*	X0324181	DISCONNECT SIGN LIGHTING AND REMOVE WIRING TO NEAREST SPLICE	EACH	1		1			
*	X0324676	MECHANICAL SANDBLAST FINISH	SQ FT	5,488			5,488		
	X0325702	NIGHTTIME WORKZONE LIGHTING	L SUM	1	1				
*	X0350805	FOLD DOWN BOLLARDS	EACH	3	3				
	X6370015	CONCRETE BARRIER, SPECIAL, 32" HEIGHT	FOOT	70	70				
*	X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	120	120				

\* SPECIALTY ITEM

FILE NAME = DSTR1-76C47-sht-summary-03.dgn	USER NAME = millerde	DESIGNED - DJM	REVISED -						F.A.I. RTE. 64	SECTION 82-1-IHR	COUNTY ST. CLAIR	TOTAL SHEETS 93	SHEET NO. 7	Rev.	
	PLOT SCALE = 50,0000' / IN.	DRAWN - DJM	REVISED -												
	PLOT DATE = 6/16/2009	CHECKED - JL	REVISED -												
		DATE - 05/01/09	REVISED -												
								SCALE: NONE	SHEET NO. 3 OF 4 SHEETS		STA.	TO STA.			
												FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	CONTRACT NO. 76C47