

CURED-IN-PLACE PIPE LINER

SHEET NUMBER	EXISTING PIPE LABEL	STREET NAME	FROM MANHOLE	TO MANHOLE	LENGTH (FEET)	AVERAGE DEPTH (FEET)	PIPE SLOPE (%)	DATE TELEVISED	COMMENTS
CURED-IN-PLACE PIPE LINER, 10"									
8	EX-P 150	1ST STREET	MH 101	MH 102	156	9.6	1.0	3/5/2003	
8	EX-P 151	1ST STREET	MH 100	MH 101	147	9.3	0.6	3/5/2003	
				10" TOTAL	303				
CURED-IN-PLACE PIPE LINER, 18"									
13	EX-P 204	9TH STREET	MH 142	MH 143	315	7.0	0.6	4/22/2003	
14	EX-P 79	ST. CLAIR AVE.	MH 127	MH 125	62	6.3	1.0	3/25/2003	
				18" TOTAL	377				
CURED-IN-PLACE PIPE LINER, 20"									
15	EX-P 83	BAUGH AVE.	MH 138	MH 139	126	14.2	0.3	4/15/2003	ASSUMED SLOPE & AVERAGE DEPTH
				20" TOTAL	126				
CURED-IN-PLACE PIPE LINER, 21"									
9 & 10	EX-P 21	BOWMAN AVE.	MH 103	MH 110	528	14.7	0.0	4/25/2003	INSIDE IDOT BOWMAN MAINTENANCE YARD
				21" TOTAL	528				ASSUMED FLAT SLOPE
CURED-IN-PLACE PIPE LINER, 24"									
11	EX-P 208	ST. CLAIR AVE.	MH 113	MH 114	363	11.2	0.1	4/3/2003	
11	EX-P 212	I-55	MH 111	MH 112	252	7.5	0.2	4/4/2003	
15	EX-P 69	ST. CLAIR AVE.	MH 136	MH 137	89	4.6	0.0	3/24/2003	ASSUMED FLAT SLOPE
15	EX-P 1028	18TH STREET	MH 144	MH 145	144	7.4	0.0	N/A	
				24" TOTAL	848				
CURED-IN-PLACE PIPE LINER, 30"									
13	EX-P 200	ST. CLAIR AVE.	MH 123	MH 124	148	6.9	0.3	4/2/2003	
14	EX-P 78	ST. CLAIR AVE.	MH 126	MH 127	206	6.3	0.3	4/10/2003	
15	EX-P 82A	BAUGH AVE.	MH 140	MH 141	387	10.7	0.0	4/11/2003	ASSUMED DOWNSTREAM FLOWLINE ELEVATION
				30" TOTAL	741				
CURED-IN-PLACE PIPE LINER, 36"									
10	EX-P 16	BOWMAN AVE.	MH 107	MH 105	160	10.3	5.0	3/28/2003	INSIDE IDOT BOWMAN MAINTENANCE YARD
10	EX-P 17	BOWMAN AVE.	MH 105	MH 106	85	6.3	-0.1	3/28/2003	INSIDE IDOT BOWMAN MAINTENANCE YARD
11 & 13	EX-P 207	ST. CLAIR AVE.	MH 119	MH 113	511	11.1	0.0	4/3/2003	
13	EX-P 205	ST. CLAIR AVE.	MH 122	MH 121	80	10.2	0.0	4/3/2003	ASSUMED FLAT SLOPE
13	EX-P 205A	ST. CLAIR AVE.	MH 121	MH 120	280	10.0	0.0	4/3/2003	
13	EX-P 206	ST. CLAIR AVE.	MH 120	MH 119	211	10.1	0.7	4/3/2003	
14	EX-P 75	ST. CLAIR AVE.	MH 130	MH 131	143	13.3	0.0	3/20/2003	ASSUMED SLOPE & AVERAGE DEPTH
14	EX-P 76	ST. CLAIR AVE.	MH 132	MH 133	183	8.4	0.0	3/20/2003	ASSUMED FLAT SLOPE
14	EX-P 76A	ST. CLAIR AVE.	MH 131	MH 132	360	10.7	1.6	3/20/2003	ASSUMED SLOPE & AVERAGE DEPTH
14	EX-P 77	ST. CLAIR AVE.	MH 133	MH 134	288	8.7	0.0	3/20/2003	ASSUMED FLAT SLOPE
14 & 15	EX-P 74	ST. CLAIR AVE.	MH 129	MH 130	349	12.7	0.1	3/20/2003	
15	EX-P 73	ST. CLAIR AVE.	MH 128	MH 129	140	12.5	-0.2	3/24/2003	ASSUMED SLOPE & AVERAGE DEPTH
				36" TOTAL	2790				
CURED-IN-PLACE PIPE LINER, 42"									
9	EX-P 14	EXCHANGE AVE	MH 146	MH 147	373	11.6	0.1	3/31/2003	
9 & 12	EX-P 12	I-55	MH 115	MH 116	158	15.5	0.0	3/31/2003	ASSUMED FLAT SLOPE
12	EX-P 10	EXCHANGE AVE	MH 117	MH 118	409	13.1	0.0	3/31/2003	ASSUMED UPSTREAM FLOWLINE ELEVATION
				42" TOTAL	940				
CURED-IN-PLACE PIPE LINER, 72"									
15	EX-P 80	64/ST. CLAIR AVE	MH 128	MH 135	244	14.2	0.1	3/27/2003	ASSUMED SLOPE & AVERAGE DEPTH
				72" TOTAL	244				

FILE NAME = DBTRI-76C48-8ht-Schedule-85.dgn	USER NAME = IDOT	DESIGNED - TTB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 1:8000 ' / IN.	DRAWN - GDO	REVISED -	64					82-1T	ST. CLAIR	15	5	
PLOT DATE = 6/25/2009	CHECKED - JAH	REVISED -	SCALE: SHEET NO. 1 OF 2 SHEETS STA. TO STA.			FED. ROAD DIST. NO. 8 ILLINOIS FED. AID PROJECT		CONTRACT NO. 76C48				
DATE - 6/25/2009	REVISOR -	REVISED -										