

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL	STRUCTURE	
			QUANTITIES	X031-2A	
50102400	CONCRETE REMOVAL	CU YB	0.5	0.5	
50300255	CONCRETE SUPERSTRUCTURE	CU YB	0.5	0.5	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	25790	25790	
50501110	STRUCTURAL STEEL REMOVAL	POUND	14270	14270	
67100100	MOBILIZATION	L SUM	1	1	
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	LSUM	1	1	
70101220	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411 (SPECIAL)	EACH	1	1	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	262.5	262.5	
Z0003600	BEAM STRAIGHTENING	L SUM	1	1	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1	
Z0073300	TEMPORARY SHORING AND CRIBBING	L SUM	1	1	
Z0073351	TEMPORARY SLAB SUPPORT SYSTEM	L SUM	1	1	

GENERAL NOTES

- THE STANDARDS AND REVISION NUMBERS SHALL APPLY TO THIS PROJECT.
 - THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
 - ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO UTILITIES WITHIN THE PROJECT AREA BEFORE DIGGING BY CALLING J.U.L.I.E. AND BY NOTIFYING NON-J.U.L.I.E. MEMBERS INDIVIDUALLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
 - AMERENIP
 - AMERENUE
 - AT&T ILLINOIS
 - VILLAGE OF CASEYVILLE
 - CHARTER COMMUNICATION, INC.
 - MEDIACOM LLC CENTRAL
- MEMBERS OF J.U.L.I.E (800) 892-0123 ARE INDICATED BY *. NON-MEMBERS MUST BE NOTIFIED INDIVIDUALLY.
- A QUANTITY OF 1288 FEET OF "TEMPORARY PAVEMENT MARKING - LINE 6" WHITE HAS BEEN INCLUDED IN THE PLANS FOR PAINTING THE BOTTOM 6" OF THE TEMPORARY CONCRETE BARRIER.
 - THE CONTRACTOR SHALL FURNISH AND INSTALL WOOD SIGN SUPPORTS IN ACCORDANCE WITH SECTION 730 OF THE STANDARD SPECIFICATIONS, HOWEVER, INSTALLATION BY METHOD "A" (ARTICLE 730.04(A)) SHALL BE THE ONLY METHOD PERMITTED.
 - TWO LANE OF TRAFFIC IN EACH DIRECTION SHALL BE MAINTAINED AT ALL TIMES.
 - "ROAD CONSTRUCTION AHEAD" SIGNS SHALL BE REQUIRED AT INTERSECTING SIDE ROADS THROUGHOUT THE PROJECT. COST TO BE INCLUDED IN BID PRICES FOR TRAFFIC CONTROL AND PROTECTION.
 - THE CONTRACTOR SHALL TAKE ALL PRECAUTIONS NECESSARY TO PREVENT ANY DEBRIS FROM FALLING ONTO LANES OPEN TO TRAFFIC BELOW THE BRIDGE.

COMMITMENTS

NONE

FILE NAME =	USER NAME = gelnh	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES /GENERAL NOTES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\pwork\PWID001\GELINH\0120465\087605-shr-S00.dgn		DRAWN -	REVISED -			270	60-2HB-1-HDF-3	MADISON	8	2	
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 76C95		ILLINOIS FED. AID PROJECT			
PLOT DATE = 6/23/2009		DATE -	REVISED -			SCALE: _____	SHEET NO. ___ OF ___ SHEETS	STA. _____ TO STA. _____			