

SUMMARY OF QUANTITIES						SUMMARY OF QUANTITIES							
CODE NO.	ITEM	CONSTRUCTION TYPE CODE		1000		Y031-1F	CODE NO.	ITEM	CONSTRUCTION TYPE CODE		1000		Y031-1F
		UNIT	URBAN TOTAL QUANTITIES	ROADWAY 90% FEDERAL 10% STATE	TRAFFIC SIGNALS 90% FEDERAL 10% STATE				UNIT	URBAN TOTAL QUANTITIES	ROADWAY 90% FEDERAL 10% STATE	TRAFFIC SIGNALS 90% FEDERAL 10% STATE	
550A0090	STORM SEWER, CLASS A, TYPE 1 18"	FOOT	148	148			* 78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS	SO FT	876	876		
550A0160	STORM SEWER, CLASS A, TYPE 1 36"	FOOT	19	19			* 78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	15257	15257		
550A0180	STORM SEWER, CLASS A, TYPE 1 42"	FOOT	65	65			* 78004250	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 12"	FOOT	793	793		
55034500	STORM SEWER, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 38, RISE 24	FOOT	186	186			* 78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"	FOOT	300	300		
60229200	MANHOLE, SPECIAL, TYPE 3	EACH	1	1			78300100	PAVEMENT MARKING REMOVAL	SO FT	1252	1252		
60243500	INLETS, SPECIAL, TYPE 3, 6'	EACH	2	2			78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	80	80		
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	1	1			80300100	LOCATING UNDERGROUND CABLE	FOOT	129		129	
60500060	REMOVING INLETS	EACH	2	2			80500105	SERVICE INSTALLATION, TYPE A (MODIFIED)	EACH	1		1	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1493	1493			81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	690		690	
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	313	313			81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	108		108	
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	287	287			81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	88		88	
60614600	PAVED DITCH (SPECIAL)	FOOT	294	294			81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	70		70	
60616120	PAVED DITCH, TYPE A-37	FOOT	522	522			81012900	CONDUIT IN TRENCH, 3 1/2" DIA., PVC	FOOT	54		54	
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SO FT	2535	2535			81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	123		123	
60622323	CONCRETE MEDIAN, TYPE SM-4.24 (SPECIAL)	SO FT	2456	2456			81021550	CONDUIT, AUGERED 2" DIA., PVC	FOOT	85		85	
66502300	WOVEN WIRE FENCE REMOVAL	FOOT	1086	1086			* 81021560	CONDUIT, AUGERED 2 1/2" DIA., PVC	FOOT	152		152	
67100100	MOBILIZATION	LSUM	1	1			81021570	CONDUIT, AUGERED 3" DIA., PVC	FOOT	30		30	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4			81021580	CONDUIT, AUGERED 3 1/2" DIA., PVC	FOOT	236		236	
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1			81021590	CONDUIT, AUGERED 4" DIA., PVC	FOOT	169		169	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	47	47			81400100	HANDHOLE	EACH	16		16	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	12			81500100	GULFBOX JUNCTION	EACH	4		4	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2300	2300			81603010	UNIT DUCT, 600V, 2-1C NO. 10, 1/C NO. 10 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	152		152	
70300210	TEMPORARY PAVEMENT MARKING-LETTERS AND SYMBOLS	SO FT	821	821			81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1285		1285	
70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	15484	15484			82104000	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 400 WATT	EACH	4		4	
70300260	TEMPORARY PAVEMENT MARKING-LINE 12"	FOOT	793	793			82500605	LIGHTING CONTROLLER PHOTOCCELL RELAY	EACH	1		1	
70300280	TEMPORARY PAVEMENT MARKING-LINE 24"	FOOT	252	252			81702450	ELECTRIC CABLE IN CONDUIT, 600V(XLP-TYPE USE)- 3-1/C NO. 10	FOOT	1180		1180	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	8046	8046			83600100	LIGHT POLE FOUNDATION	EACH	1		1	
* 72000100	SIGN PANEL - TYPE 1	SO FT	10		10		83800660	BREAKWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	4		4	
* 72400710	RELOCATE SIGN PANEL - TYPE 1	SO FT	28		28		84200700	LIGHTING FOUNDATION REMOVAL	EACH	1		1	

\* Specialty Items

Rev,

FILE NAME =	USER NAME = russellcf	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE. =	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
78053_sht_typical.dgn	DRAWN -	REVISED -	331			SEC. # (IX-1N-1, TS-2)	WILLIAMSON	190	5	
PLOT SCALE = 40.00' / IN.	CHECKED -	REVISED -	CONTRACT NO. 78053							
PLOT DATE = 5/6/2009	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							