

**SEEDING AND EROSION CONTROL SCHEDULE**

LOCATION STATION TO STATION	SEEDING, CLASS 1B	SEEDING, CLASS 7	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH, METHOD 2	EROSION CONTROL BLANKET	TEMP. DITCH CHECKS	INLET AND PIPE PROTECTION	PERIMETER EROSION BARRIER	REMARKS
	ACRE	ACRE	POUND	POUND	POUND	TON	ACRE	SQ YD	EACH	EACH	FOOT	
<b>ILLINOIS 13 (EB LANES)</b>												
763 + 35.00 RT TO 776 + 20.00 RT	1.7	1.7	204	204	204	3.4	6.8					
763 + 35.00 RT TO 770 + 69.00 RT								320				
764+00									1			
764+50									1			
765+00									1			
765+50									1			
766+00									1			
766+50									1			
767+00									1			
767+50									1			
768+00									1			
768+50									1			
769+00									1			
769+50									1			
770+00									1			
771 + 0.00 RT TO 4 + 33.00 RT											705	EB 13 TO WALTON WAY
777 + 40.00 RT TO 779 + 0.00 RT	0.1	0.1	12	12	12	0.2	0.4					
<b>ILLINOIS 13 (WB LANES)</b>												
765 + 0.00 LT TO 766 + 33.00 LT	2.0	2.0	240	240	240	4.0	8.0					
765 + 50.00 LT TO 770 + 33.00 LT								215				
766+00									1			
766+50									1			
767+00									1			
767+50									1			
768+00									1			
768+50									1			
769+00									1			
769+50									1			
770+00									1			
770+60 @ 31.7' RT										1		
770 + 60 RT TO 772 + 26 RT								74				
770 + 70.00 RT TO 772 + 26.00 LT	0.1	0.1	12	12	12	0.2	0.4					MEDIAN
771+00									1			
772+50									1			
774+00									1			
775+50									1			
777 + 40.00 LT TO 783 + 62.00 LT	0.5	0.5	60	60	60	1.0	2.0					
777 + 88.00 LT TO 783 + 62.00 LT								255				
778+09 @ 62.85' LT										1		
780+00 @ 65.71' LT										1		
781 + 22.00 RT TO 782 + 36.00 RT								51				
781 + 22.00 RT TO 783 + 61.00 RT	0.1	0.1	12	12	12	0.2	0.4					MEDIAN
782+36 @ 35.8' RT										1		
<b>WALTON WAY</b>												
1 + 66.00 RT TO 4 + 33.00 RT	0.3	0.3	36	36	36	0.6	1.2					
2 + 20.00 LT TO 779 + 0.00 RT											202	WALTON WAY TO EB 13
<b>WILLIAMSON CO. PARKWAY</b>												
1 + 0.00 LT TO 6 + 69.00 LT	0.4	0.4	48	48	48	0.8	1.6					
<b>TOTALS</b>	<b>5.2</b>	<b>5.2</b>	<b>624</b>	<b>624</b>	<b>624</b>	<b>10.4</b>	<b>20.8</b>	<b>915</b>	<b>26</b>	<b>4</b>	<b>907</b>	