

EARTHWORK SCHEDULE

LOCATION STATION TO STATION	EARTH EXCAVATION	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD
ILLINOIS 13 EB 763+35 TO 779+00	4536	3402	11937	-8535
ILLINOIS 13 WB 776+00 TO 783+62	2435	1826	9907	-8081
WALTON WAY 01+00 TO 4+00 499+40 TO 501+20	181 330	136 248	361 1	-225 +247
WILLIAMSON CO. PARKWAY 00+00 TO 06+70	273	205	1446	-1241
TOTALS	7755	5816	23652	-17835

25% Shrinkage Factor for Earth Excavation

TREE REMOVAL SCHEDULE

LOCATION STATION TO STATION	TREE REMOVAL (6-15 UNITS DIAMETER)	TREE REMOVAL (OVER 15 UNITS DIAMETER)
	UNIT	UNIT
ILLINOIS 13 WB 765+98 LT 766+35 LT 767+05 LT		31 24 24
ILLINOIS 13 EB 764+44 RT 764+47 RT		24 24
WILLIAMSON CO. PARKWAY 04+99 LT TO 05+52 LT	65	34
TOTALS	65	161