



### STAGE 3 FAP 311 (ILLINOIS 13)

**NOTES:**

THE FLAGMEN ON THIS DETAIL ARE SHOWN AT SUGGESTED LOCATIONS. THE ACTUAL NUMBER AND LOCATION SHALL BE AS DIRECTED BY THE ENGINEER.

ADDITIONAL TRAFFIC CONTROL DEVICES MAY BE NECESSARY AS DIRECTED BY THE ENGINEER.

TRAFFIC CONTROL FOR THIS WORK SHALL BE PAID FOR AS TRAFFIC CONTROL AND PROTECTION, SPECIAL CLOSE NEWLY CONSTRUCTED EB OUTSIDE THROUGH LANE AND EB RIGHT TURN LANE ACCORDING TO STD 701101 REMOVE EXISTING PAVEMENT AND SHOULDER, PLACE BINDER COURSE AND HMA SHOULDERS.

CONSTRUCTION OF BOX CULVERT EXTENSION AT SOUTH END SHALL BE COMPLETED PRIOR TO THE BEGINNING OF STAGE 3.

FILE NAME =	USER NAME = russellcf	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>IL 13 STAGE 3 CONSTRUCTION</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
et\pwork\PWIDOT\RUSSELLCF\dms35765\dms_78053.staging.dgn	PLOT SCALE = 30.0000' / IN.	DRAWN -	REVISED -			331	SEC. NO. (1X-1N-1, TS-2)	WILLIAMSON	193	62	
PLOT DATE = 5/6/2009	DATE -	CHECKED -	REVISED -			CONTRACT NO. 78053					
						FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT					

DATE PLOTTED: 5/6/2009 10:58:54 AM