



LEFT TURN SIGNAL

R10-10
24" X 30"
SIGNAL POST MOUNTED

STA 777+92, 20' LT (IL 13 EB) - TO REMAIN IN PLACE
STA 776+19, 20' RT (IL 13 WB) - RELOCATE TO STA 775+75, 20' RT (IL 13 WB)

STA 01+60, 28' RT (WALTON WAY) - NEW SIGN
STA 00+72, 28' RT (WMS. CO. PKWY.) - NEW SIGN



- LEGEND**
- PROPOSED TYPE IV CABINET, TRAFFIC SIGNAL CONTROLLER, HIGHWAY LIGHTING CONTROLLER, AND SERVICE INSTALLATION
 - PROPOSED GULFBOX JUNCTION
 - PROPOSED CONCRETE HANDHOLE
 - EXISTING TRAFFIC SIGNAL CONTROLLER
 - EXISTING SIGNAL HEAD
 - EXISTING LIGHT POLE AND LUMINAIRE
 - PROPOSED STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH TENON FOR LUMINAIRE
 - PROPOSED STEEL COMBINATION MAST ARM ASSEMBLY AND POLE
 - PROPOSED TRAFFIC SIGNAL POST AND SIGNAL HEAD
 - PROPOSED SIGNAL HEAD WITH BACKPLATE, MAST ARM MOUNTED
 - CONDUIT IN TRENCH
 - CONDUIT, AUGERED
 - " PVC SIZE OF CONDUIT

NOTES:

1. THE PAY ITEM 'REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT' SHALL INCLUDE ALL WORK NECESSARY FOR THE REMOVAL OF THE ITEMS LISTED ON SHEET 105 OF 193.
2. EXISTING CABLES AND CONDUIT THAT DO NOT INTERFERE WITH PROPOSED WORK MAY BE ABANDONED IN PLACE.
3. RELOCATE EXISTING STREET NAME SIGNS ONTO NEW MAST ARMS PER STANDARD 720016-01.

FILE NAME =	USER NAME = russellcf	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PROPOSED TRAFFIC SIGNALS AND LIGHTING	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\pw-work\p\dms\russellcf\dms43738\d9-78053-ts-sht.dgn		DRAWN -	REVISED -			331	SEC. NO. (IX-1N-1, T5-2)	WILLIAMSON	190	91
	PLOT SCALE = 30,0000' / IN.	CHECKED -	REVISED -							
	PLOT DATE = 5/5/2009	DATE -	REVISED -							
						SCALE: 1"=30'	SHEET NO.	OF	SHEETS	STA. TO STA.
										FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

Rev.