

CONTRACT NO. 83827				
F.A.I.L. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3570	00-00116-00-BR	DUPAGE	106	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES		UNIT	TOTAL QTY.	CONSTRUCTION TYPE CODE				
CODE NO.	ITEM			80% FED / 20% CITY OF NAPERVILLE		100% CITY OF NAPERVILLE		
				ROADWAY	BRIDGE	LIGHTING	ELECTRIC	LANDSCAPING
				1000-2A	X071-2A	Y030-1E	Y030-1E	Y003
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	556	443				113
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	197	197				
20101000	TEMPORARY FENCE	FOOT	730	450				280
20101100	TREE TRUNK PROTECTION	EACH	43	43				
20200100	EARTH EXCAVATION	CU YD	1750	1750				
20200410	EARTH EXCAVATION (SPECIAL)	CU YD	70			70		
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	750		750			
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	50	50				
20800150	TRENCH BACKFILL	CU YD	713.3	713.3				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	2640	2640				
21101815	COMPOST FURNISH AND PLACE, 4"	SO YD	54					54
25000200	SEEDING CLASS 2	ACRE	0.01	0.01				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	65	50		15		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	65	50		15		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	65	50		15		
25000920	SEEDING CLASS 1A (SPECIAL)	ACRE	0.25			0.25		
25100630	EROSION CONTROL BLANKET	SO YD	14.7	14.7				
25200110	SODDING, SALT TOLERANT	SO YD	2640	2640				
25200200	SUPPLEMENTAL WATERING	UNIT	27	27				
25200700	SODDING, (SPECIAL)	SO YD	200			200		
25400105	PERENNIAL PLANTS	EACH	366	50				316
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	12	12				
28000400	PERIMETER EROSION BARRIER	FOOT	727	727				
28000510	INLET FILTERS	EACH	5	5				
28100107	STONE RIPRAP, CLASS A4	SO YD	23	23				
28100111	STONE RIPRAP, CLASS A6	SO YD	184	184				
28200200	FILTER FABRIC	SO YD	207	207				
31101100	SUB-BASE GRANULAR MATERIAL, TYPE B	CU YD	385	385				
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	292	292				
40600300	AGGREGATE (PRIME COAT)	TON	6	6				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40701851	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 8 1/2"	SO YD	2900	2900				
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SO YD	348	348				
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	270	270				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	4055	4055				
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SO FT	297	297				
42400800	DETECTABLE WARNINGS	SO FT	136	136				
44000100	PAVEMENT REMOVAL	SO YD	3768	3768				
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	134	134				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1560	1560				
44000600	SIDEWALK REMOVAL	SO FT	4765	4765				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	32			32		
44002000	CONCRETE CURB REMOVAL	FOOT	186	186				
44004610	SIDEWALK REMOVAL AND REPLACEMENT (SPECIAL)	SO FT	300			300		
44201000	CLASS B PATCHES TYPE IV 12 INCHES	SO YD	100			100		
44201796	CLASS D PATCHES TYPE IV 12 INCHES	SO YD	100			100		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1			1		
50200100	STRUCTURE EXCAVATION	CU YD	1694		1694			
50300225	CONCRETE STRUCTURES	CU YD	561.5		561.5			

\* SPECIALTY ITEMS

SUMMARY OF QUANTITIES		UNIT	TOTAL QTY.	CONSTRUCTION TYPE CODE				
CODE NO.	ITEM			80% FED / 20% CITY OF NAPERVILLE		100% CITY OF NAPERVILLE		
				ROADWAY	BRIDGE	LIGHTING	ELECTRIC	LANDSCAPING
				1000-2A	X071-2A	Y030-1E	Y030-1E	Y003
50300255	CONCRETE SUPERSTRUCTURE	CU YD	301.6	18.0	283.6			
50300260	BRIDGE DECK GROOVING	SO YD	581		581			
50300280	CONCRETE ENCASEMENT	CU YD	88				88	
50300300	PROTECTIVE COAT	SO YD	1300	317	983			
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1			
50500505	STUD SHEAR CONNECTORS	EACH	4536		4536			
50800105	REINFORCEMENT BARS	POUND	11500		11500			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	181300	1210	180090			
50800515	BAR SPLICERS	EACH	318		318			
50900810	PEDESTRIAN RAIL (SPECIAL)	FOOT	421		421			
50901755	PARAPET RAILING, (SPECIAL)	FOOT	85	85				
51500100	NAME PLATES	EACH	1		1			
51602000	PERMANENT CASING	FOOT	416		416			
51603000	DRILLED SHAFT IN SOIL	CU YD	131.1		131.1			
51604000	DRILLED SHAFT IN ROCK	CU YD	94.1		94.1			
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	18		18			
52100520	ANCHOR BOLTS, 1"	EACH	36		36			
52100540	ANCHOR BOLTS, 1 1/2"	EACH	36		36			
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1				
54216220	REINFORCED CONCRETE PIPE TEE, 36" PIPE WITH 12" RISER	EACH	1	1				
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	1	1				
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	19	19				
550A0240	STORM SEWERS, CLASS A, TYPE 1 78"	FOOT	32	32				
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	192	192				
55039700	STORM SEWERS TO BE CLEANED	FOOT	575	575				
55100500	STORM SEWER REMOVAL 12"	FOOT	83	83				
55101200	STORM SEWER REMOVAL 24"	FOOT	179	179				
55102400	STORM SEWER REMOVAL 78"	FOOT	75	75				
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	243		243			
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	26		26			
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	2		2			
60100905	PIPE DRAINS 4"	FOOT	20		20			
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1				
60226800	DROP MANHOLES, TYPE A1-1, 5' DIAMETER TYPE 1 FRAME CLOSED LID	EACH	1	1				
60228200	MANHOLES, SANITARY, WITH SPECIAL FRAME AND CLOSED LID	EACH	3	3				
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	3	3				
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	2	2				
60247800	JUNCTION CHAMBER	EACH	1	1				
60255500	MANHOLES TO BE ADJUSTED	EACH	3	3				
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	2	2				
60266600	VALVE BOXES TO BE ADJUSTED	EACH	1	1				
60500040	REMOVING MANHOLES	EACH	1	1				
60500060	REMOVING INLETS	EACH	5	5				
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1410	1410				
63200310	GUARDRAIL REMOVAL	FOOT	168	168				
66410300	CHAIN LINK FENCE REMOVAL	FOOT	28	28				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8				

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE
PER DEC & CLIENT	9/13/05
PER IDOT	11/1/05

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
  
JEFFERSON AVENUE OVER  
WEST BRANCH DUPAGE RIVER

SCALE: NO SCALE  
DATE: JULY 10, 2009  
DRAWN BY: HRT  
CHECKED BY: HRT

V:\800\_808 & 809\_822 Jefferson Revisions BPCADD Sheets\SumofQuant.dgn  
 8/17/2005 10:23:21 AM