

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3570	00-00116-00-BR	DUPAGE	106	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES		UNIT	TOTAL QTY.	CONSTRUCTION TYPE CODE				
CODE NO.	ITEM			80% FED / 20% CITY OF NAPERVILLE		100% CITY OF NAPERVILLE		
				ROADWAY	BRIDGE	LIGHTING	ELECTRIC	LANDSCAPING
		I000-2A	X071-2A	Y030-1E	Y030-1E	Y003		
67100100	MOBILIZATION	L SUM	1	0.88			0.12	
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1				1	
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1210	1210				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	290	290				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	150	150				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	15	15				
* 78008210	POLYURA PAVEMENT MARKING, TYPE I - LINE 4"	FOOT	430	430				
* 81702500	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 4/C NO. 6	FOOT	52			52		
* 81900205	TRENCH AND BACKFILL FOR ELECTRICAL WORK (SPECIAL)	FOOT	10			10		
* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	4			4		
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	850			850		
* C2C03424	SHRUB, HYDRANGEA ARBORESCENS ANNABELLE (ANNABELLE SMOOTH HYDRANGEA), 2' HEIGHT CONTAINER	EACH	42	42				
* C2C05824	SHRUB, RHUS AROMATICA GRO-LOW (GRO-LOW FRAGRANT SUMAC), 2' WIDTH, CONTAINER	EACH	45	45				
* C2006148	SHRUB, RHUS TYPHINA LACINIATA (CUTLEAF STAGHORN SUMAC), 4' HEIGHT, BALLED AND BURLAPPED	EACH	12				12	
* C2007218	SHRUB, ROSA KNOCKOUT (KNOCKOUT ROSE), 18" HEIGHT, CONTAINER	EACH	27				27	
* C2012136	SHRUB, VIBURNUM X JUDDII (JUDD VIBURNUM) 3' HEIGHT, BALLED AND BURLAPPED	EACH	3	3				
* C2012760	SHRUB, VIBURNUM PRUNIFOLIUM (BLACKHAW VIBURNUM), 5' HEIGHT, BALLED AND BURLAPPED	EACH	3	3				
* D2002788	EVERGREEN, PINUS NIGRA (AUSTRIAN PINE), 8' HEIGHT, BALLED AND BURLAPPED	EACH	5				5	
* D2003524	EVERGREEN, TAXUS X MEDIA DENSIFORMIS DENSE ANGLO-JAPANESE YEW), 2' WIDTH, BALLED AND BURLAPPED	EACH	5	5				
* K1005481	SHREDDED BARK MULCH, 3"	SQ YD	240	120				120
* K1005875	TREE TRANSPLANT	EACH	4	4				
* X0320591	SANITARY MANHOLES TO BE REMOVED	EACH	1	1				
* X0321158	PARK BENCHES	EACH	1				1	
X0321297	REMOVE EXISTING SIGN POST	EACH	1	1				
X0321309	CONCRETE PAD	SQ YD	4	4				
X0322033	STORM SEWER (WATERMAIN REQUIREMENTS) 12"	FOOT	41	41				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	103	103				
X0322671	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	450	450				
X0322795	REMOVE AND RELOCATE EXISTING MONUMENT	EACH	1	1				
X0322917	PROPOSED STORM SEWER CONNECTION TO EXISTING MANHOLE	EACH	3	3				
X0323080	DRAINAGE SCUPPERS, DS-12	EACH	6					6
X0323350	FURNISHING AND SETTING BRICK PAVERS	SQ FT	550	550				
X0323706	TRASH RECEPTACLE RELOCATION	EACH	1	1				
* X0840000	SANITARY SEWER REMOVAL 8"	FOOT	127	127				
X0974300	SIGN REMOVAL	EACH	1	1				
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	4	4				
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	1	1				
X4023000	TEMPORARY ACCESS (ROAD)	EACH	2	2				

* SPECIALTY ITEMS

SUMMARY OF QUANTITIES		UNIT	TOTAL QTY.	CONSTRUCTION TYPE CODE				
CODE NO.	ITEM			80% FED / 20% CITY OF NAPERVILLE		100% CITY OF NAPERVILLE		
				ROADWAY	BRIDGE	LIGHTING	ELECTRIC	LANDSCAPING
		I000-2A	X071-2A	Y030-1E	Y030-1E	Y003		
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1		1			
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1		1			
X5020503	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 3	EACH	1		1			
X5020504	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 4	EACH	1		1			
X7240600	REMOVE AND RE-ERECT EXISTING SIGN	EACH	3	3				
* X8161000	EXPOSE AND RELOCATE EXISTING UNIT DUCT	FOOT	10	10				
XX000406	BRICK PAVER REMOVAL AND REPLACEMENT	SQ FT	480	480				
XX000504	RESTORATION WORK	L SUM	1			1		
XX003435	PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	102				102	
* K0026030	SHRUB REMOVAL	EACH	28	28				
* XX004809	UNDER BRIDGE CONDUIT SYSTEM	L SUM	1				1	
* XX005581	VIDEO TAPE	UNIT	1				1	
* XX005593	NEW SWITCH GEAR VAULT	EACH	1				1	
XX005594	FA-2 ENCASEMENT	CU YD	45				45	
XX005595	TRENCH BACKFILL CA-6	CU YD	165				165	
* XX005597	ROD AND MANDREL	FOOT	8000				8000	
* XX005598	ADDITIONAL GROUND ROD INSTALLATION	EACH	6				6	
* XX005600	COUNTERPOISE, UNPAVED	FOOT	400				400	
* XX005601	COUNTERPOISE, PAVED	FOOT	800				800	
* XX005602	HAND DIGGING 0FT TO 5FT IN PAVEMENT	CU YD	40				40	
* XX005603	HAND DIGGING 5FT TO 20FT IN PAVEMENT	CU YD	30				30	
* XX005604	HAND DIGGING 0FT TO 5FT IN UNPAVED AREAS	CU YD	40				40	
* XX005605	HAND DIGGING 5FT TO 20FT IN UNPAVED AREAS	CU YD	30				30	
* XX005606	MACHINE AIDED DIGGING 0FT TO 5FT IN PAVEMENT	CU YD	60				60	
* XX005608	MACHINE AIDED DIGGING 0FT TO 5FT IN UNPAVED AREAS	CU YD	60				60	
XX008161	REMOVE AND REINSTALL MODULAR CONCRETE PAVERS	SQ FT	208	208				
XX005896	CONCRETE PAD REMOVAL	SQ FT	36	36				
* XX005987	MACHINE AIDED DIGGING 5FT TO 20FT IN PAVEMENT	CU YD	30				30	
* XX005989	MACHINE AIDED DIGGING 5FT TO 20FT IN UNPAVED AREAS	CU YD	60				60	
* XX008162	MAINTAIN LIGHTING SYSTEM	L SUM	1	1				
XX006947	HOT MIX ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	102				102	
* XX007055	HANDHOLE-DEH6	EACH	1				1	
* XX007138	2 WAY-3" PVC DUCT BANK-1 HIGH BY 2 WIDE	FOOT	30				30	
* XX007141	2 WAY-6" PVC DUCT BANK-1 HIGH BY 2 WIDE	FOOT	90				90	
XX007594	MANHOLE INSTALLATION, TYPE "G"	EACH	2				2	
XX007595	MANHOLE INSTALLATION, TYPE "E"	EACH	1				1	
* XX007596	CONDUIT IN TRENCH TRANSITION AND TRANSPOSING	EACH	2				2	
* XX007625	6 WAY 6-6" PVC DUCT BANK 2 HIGH BY 3 WIDE	FOOT	400				400	
* XX007627	8 WAY 6-6" & 2-3" PVC DUCT BANK 3 HIGH BY 3 WIDE	FOOT	150				150	
* XX007628	8 WAY 8-6" PVC DUCT BANK 3 HIGH BY 3 WIDE	FOOT	10				10	
* XX007629	9 WAY 9-6" PVC DUCT BANK 3 HIGH BY 3 WIDE	FOOT	60				60	
XX007747	PARK BENCH REMOVAL AND RELOCATION	EACH	2	2				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.88				0.12

* SPECIALTY ITEMS

HA095-0328 & 068-032 Jefferson Revisions 09/13/05
 7/15/2009 11:46:53 AM

REVISIONS	
NAME	DATE
PER DEC & CLIENT	9/13/05
PER IDOT	11/1/05

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 JEFFERSON AVENUE OVER
 WEST BRANCH DUPAGE RIVER

SCALE: NO SCALE
 DATE: JULY 10, 2009
 DRAWN BY: HRT
 CHECKED BY: HRT