



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

September 3, 2009

SUBJECT: FAU 2903 (Cemetery Road)  
Project ARA-8003(322)  
Section 00-00047-00-FP (Gurnee)  
Lake County  
Contract No. 83845  
Item 90  
September 18, 2009 Letting  
Addendum (A)

TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

**Proposal – Added special provision, “Temporary Bituminous Pavement”**

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Charles Ingersoll  
Engineer of Design and Environment

A handwritten signature in cursive script, reading 'Ted B. Walschleger', followed by the initials 'AE'.

By: Ted B. Walschleger  
Engineer of Project Development  
and Implementation

Traffic Control and Protection for Temporary Detour – District One 34

**SPECIAL PROVISIONS for Pay Items – LCDOT**

21101625	Topsoil Furnish and Place, 6"	35
21301052	Exploration Trench 52" Depth	36
25000210	Seeding, Class 2A	37
28000400	Perimeter Erosion Barrier	38
40600100	Bituminous Materials (Prime Coat)	41
42400800	Detectable Warnings	42
440001XX	Hot-Mix Asphalt Surface Removal	43
44201XXX	Class D Patches	44
78100100	Raised Reflective Pavement Marker	45
LC200500	Remove Perimeter Erosion Barrier	46
X2800500	Inlet Protection, Special	47
X6013600	Pipe Underdrains 4" (Modified)	48
XX000610	Relocate Existing Mailbox	49
XX004878	Maintenance of Temporary Erosion Control Systems	50
XX006338	Erosion Control Blanket (Special)	52
XX206400	Mailbox Post	53
Z0062400	Sawing Bituminous Concrete Pavement	54

Lake County Division of Transportation Traffic Control Plan 55

Lake County Division of Transportation Traffic Signal Specifications and Special Provision 71

Lake County Stormwater Management Commission Watershed Development Permit 118

U.S. Army Corps of Engineers Permit 124

Storm Water Pollution Prevention Plan and Permit 139

Storm Water Pollution Prevention Plan (BDE 2342)

Contractor Certification Statement (BDE 2342a)

Erosion and Sediment Control Analysis (BDE 2394)

Erosion Control Inspection Report (BC 2259)

151

152

**Environmental Survey Request Forms**

Topsoil/Borrow/Waste/Use Areas (BDE 2289)

154

Temporary Bituminous Pavement

253

Revised 9-3-09

**XX004782 TEMPORARY BITUMINOUS PAVEMENT**

**Description:** This work shall consist of constructing, maintaining, and removing temporary bituminous pavement at the locations shown on the plans or as directed by the Engineer.

**Materials:** The hot-mix asphalt materials shall be according to Section 1030 of the "Standard Specifications".

**General:** Temporary bituminous pavement shall consist of 10" of Hot-Mix Asphalt Binder Course constructed and compacted according to Section 355 of the "Standard Specifications". The temporary bituminous pavement shall be placed and compacted in a minimum of two lifts on a prepared sub-grade.

The bituminous mixture shall be shown on the plans.

Article 355.08 of the "Standard Specifications", shall not apply.

The removal of temporary bituminous pavement shall be according to Section 440 of the "Standard Specifications". The removed pavement shall be disposed of outside the right-of-way according to Article 202.03 of the "Standard Specifications".

**Method of Measurement:** Temporary Bituminous Pavement will be measured for payment in place, and the area computed in square yards.

**Basis of Payment:** This work will be paid for at the contract unit price per square yard for TEMPORARY BITUMINOUS PAVEMENT. The unit price shall include both placement and removal of the hot-mix asphalt material.

*Added 9-3-09*