SCHEDULES

LOCATION	EARTH EXCAVATION (SPECIAL) 20200410* C.Y.	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE 25%	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
SUMMIT AVE. (WEST) - LOC #1 STA. 100+00 TO 103+82	33	25	3	22
SUMMIT AVE. (EAST) - LOC #2 STA. 200+30 TO 203+21	25	19	0	19
MAPLE AVE. (SOUTH) - LOC #3 STA. 300+62 TO 301+72	40	30	0	30
MAPLE AVE. (NORTH) - LOC #4 STA. 400+32 TO 401+60	5	4	12	-8
HIGH AVE. - LOC #5 STA. 500+49 TO 502+30	25	18	0	18
QUEEN AVE. - LOC #7 STA. 700+02 TO 705+14	43	32	17	15
TOTALS	171	128	32	96

TREE REMOVAL (6 TO 15 UNITS DIAMETER)

STATION	UNIT	REMARKS
SUMMIT AVENUE - WEST (LOC. #1)		
102+82 LT 3'	12	
PROJECT TOTAL	12	
20100110		

AGGREGATE SURFACE COURSE, TYPE B

STATION	TON	REMARKS
QUEEN AVENUE (LOC #7)		
PEL 703+71	12	CONTINGENCY ITEM - DRESS AGG. DRIVEWAY
PROJECT TOTAL	12	
40200800		

SEEDING, CLASS 1 (SPECIAL)

STATION	ACRE	REMARKS
SUMMIT AVENUE - WEST (LOC #1)		
100+00 TO 103+82 LT	0.03	
100+00 TO 103+82 RT	0.04	
SUBTOTAL:	0.07	
SUMMIT AVENUE - EAST (LOC #2)		
200+30 TO 203+21 LT	0.01	
200+30 TO 203+21 RT	0.04	
SUBTOTAL:	0.05	
MAPLE AVENUE - SOUTH (LOC #3)		
300+12 TO 301+72 LT	0.03	
300+12 TO 301+72 RT	0.01	
SUBTOTAL:	0.04	
MAPLE AVENUE - NORTH (LOC #4)		
400+32 TO 401+60 LT	0.01	
400+32 TO 401+60 RT	0.01	
SUBTOTAL:	0.02	
HIGH AVENUE - (LOC #5)		
500+49 TO 502+30 LT	0.02	
500+49 TO 502+30 RT	0.01	
SUBTOTAL:	0.03	
QUEEN AVENUE - (LOC #7)		
700+02 TO 705+14 LT	0.02	
700+02 TO 705+14 RT	0.08	
SUBTOTAL:	0.10	
PROJECT TOTAL	0.31	
25000900		

PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH, SPECIAL

STATION	SQ YD	REMARKS
SUMMIT AVENUE - WEST (LOC #1)		
CEL 100+88	32	
PEL 102+32	22	
SUBTOTAL:	54	
SUMMIT AVENUE - EAST (LOC #2)		
PEL 201+50	32	
PEL 202+34	22	
SUBTOTAL:	54	
MAPLE AVENUE - SOUTH (LOC #3)		
PER 301+54	67	
SUBTOTAL:	67	
MAPLE AVENUE - NORTH (LOC #4)		
PEL 401+49	16	
SUBTOTAL:	16	
HIGH AVENUE (LOC #5)		
PEL 501+29	43	
PEL 501+75	38	
SUBTOTAL:	81	
QUEEN AVENUE (LOC #7)		
PEL 702+68	28	
PEL 703+71	5	
SUBTOTAL:	33	
PROJECT TOTAL	305	
42300710		

PLAN: SURVEYED / PLOTTED / ALIGNMENT CHECKED / RT. OF WAY CHECKED / CADD FILE NAME / NOTE BOOK / NO. / BY / DATE

PROFILE: SURVEYED / PLOTTED / GRADES CHECKED / B.M. NOTED / STRUCTURE NOTATNS CHKD / NOTE BOOK / NO. / BY / DATE

S:\Freeport\1105d085stocktonSidewalk\Typical Sections.dgn

WILLETT, HOFMANN & ASSOCIATES, INC.
CONSULTING ENGINEERS
809 East Second Street Dixon, IL 61021
Phone 815.284.3381 Fax 815.284.3386
Design Firm # 184-000918
www.willetthofmann.com

USER NAME =	DESIGNED - M.L.W.	REVISED - 6/3/09	
	DRAWN - K.B.A.	REVISED -	
PLOT SCALE =	CHECKED - J.L.H.	REVISED -	
PLOT DATE =	DATE - 3/18/09	REVISED -	

STOCKTON, IL.
SAFER ROUTES TO SCHOOL PROGRAM

SCHEDULES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	08-00033-00-SW	JO DAVIESS	20	3
STA.	TO STA.	CONTRACT 85459		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		