

SCHEDULES

DATE	
BY	
PLANNED	
CHECKED	
NO. OF WAY CHECKED	
DATE FILE NAME	
PLAN	
NO.	

DATE	
BY	
DESIGNED	
CHECKED	
NO. OF WAY CHECKED	
DATE FILE NAME	
PROFILE	
NO.	

PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH		
STATION	SO FT	REMARKS
SUMMIT AVENUE - WEST (LOC #1)		
99+98 TO 100+00	25	4' W
100+00 TO 100+75.95	304	4' W
101+02.90 TO 102+27.80	512	4' - 5' W
102+39.98 TO 103+00.35	229	4' W
103+03.35 TO 103+17.56	57	4' W
103+50.90 TO 103+82	166	3.8' W
SUBTOTAL	1,293	
SUMMIT AVENUE - EAST (LOC #2)		
200+30 TO 200+36.12	27	4' W
200+54.01 TO 201+41.30	348	4' W
201+59.15 TO 202+28.04	275	4' W
202+11.25 TO 202+17.04	14	4' W
202+40.04 TO 203+21.31	325	4' W
SUBTOTAL	989	
MAPLE AVENUE - SOUTH (LOC #3)		
300+64.66 TO 301+43.92	317	4' W
301+10.42 TO 301+13.37	9	2.8' W
301+63.76 TO 301+72	34	4' W
SUBTOTAL	360	
MAPLE AVENUE - NORTH (LOC #4)		
400+32 TO 400+73.48	168	4' W
400+95.97 TO 401+44.05	188	4' W
401+54.05 TO 401+60	18	4' W
SUBTOTAL	374	
HIGH AVENUE - (LOC #5)		
500+51.96 TO 501+18.12	275	4' W
501+39.12 TO 501+66.19	103	4' W
501+84.19 TO 502+30	182	4' W
SUBTOTAL	560	
QUEEN AVENUE (LOC #7)		
700+01.54 TO 700+09.53	61	4' & VAR W
700+54.56 TO 702+60.11	822	4' W
702+34.22 TO 702+37.22	31	3' W
702+76.11 TO 703+65.67	358	4' W
703+77.41 TO 704+45.00	272	4' W
704+45 TO 704+49.36	51	4' W
704+49.36 TO 704+59.23	40	4' W
704+91.03 TO 705+14	152	4' W
SUBTOTAL	1,787	
PROJECT TOTAL	5,363	

DETECTABLE WARNINGS		
STATION	SO FT	REMARKS
SUMMIT AVENUE - WEST (LOC #1)		
99+98	8	2'X4'
103+16	8	2'X4'
103+53	8	2'X4'
SUBTOTAL	24	
SUMMIT AVENUE - EAST (LOC #2)		
200+34	8	2'X4'
200+55	8	2'X4'
203+19	8	2'X4'
SUBTOTAL	24	
MAPLE AVENUE - SOUTH (LOC #3)		
300+62	8	2'X4'
SUBTOTAL	8	
HIGH AVENUE - (LOC #5)		
500+53	8	2'X4'
SUBTOTAL	8	
QUEEN AVENUE (LOC #7)		
700+08	8	2'X4'
700+56	8	2'X4'
704+47	8	2'X4'
704+58	8	2'X4'
704+93	8	2'X4'
705+01	8	2'X4'
SUBTOTAL	48	
PROJECT TOTAL	112	

COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT		
STATION	FOOT	REMARKS
SUMMIT AVENUE - WEST (LOC #1)		
103+18	8	
103+49	8	
SUBTOTAL	16	
MAPLE AVENUE - SOUTH (LOC #3)		
300+62	11	
SUBTOTAL	11	
HIGH AVENUE - (LOC #5)		
500+53	9	
SUBTOTAL	9	
QUEEN AVENUE (LOC #7)		
700+11	9	
704+61	8	
704+89	8	
SUBTOTAL	25	
PROJECT TOTAL	61	

S:\Fr\report\1105d085\stockton\sidewalk\Typical Schedules.dgn

WILLET, HOFMANN & ASSOCIATES, INC.
CONSULTING ENGINEERS
 809 East Second Street Dixon, IL 61021
 Phone 815-294-3381 Fax 815-294-3388
 Design Firm # 184-00918
 www.willettthofmann.com

USER NAME =	DESIGNED - M.L.W.	REVISED - 6/3/09
PLOT SCALE =	DRAWN - K.B.A.	REVISED -
PLOT DATE =	CHECKED - J.L.H.	REVISED -
	DATE - 3/16/09	REVISED -

STOCKTON, IL.
SAFER ROUTES TO SCHOOL PROGRAM

SCHEDULES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	08-00033-00-SW	JO DAVIESS	20	4
STA.	TO STA.	CONTRACT	85459	
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				