



PAY ITEM #	ITEM DESCRIPTION	ABBREVIATION	UNIT	QUANTITY
20100110	TREE REMOVAL (6-15 UNITS DIAMETER)	TREE REMOV 6-15	UNIT	18
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	TREE REMOV OVER 15	UNIT	30
20200100	EARTH EXCAVATION	EARTH EXCAVATION	CU YD	696
20800150	TRENCH BACKFILL	TRENCH BACKFILL	CU YD	723
21101505	TOPSOIL EXCAVATION AND PLACEMENT	TOPSOIL EXC & PLAC	CU YD	76
25000100	SEEDING, CLASS 1	SEEDING CL 1	ACRE	0.15
25000400	NITROGEN FERTILIZER NUTRIENT	NITROGEN FERT NUTR	POUND	13
25000500	PHOSPHORUS FERTILIZER NUTRIENT	PHOSPHORUS FERT NUTR	POUND	13
25000600	POTASSIUM FERTILIZER NUTRIENT	POTASSIUM FERT NUTR	POUND	13
25100105	MULCH, METHOD 1	MULCH METHOD 1	ACRE	0.15
28000250	TEMPORARY EROSION CONTROL SEEDING	TEMP EROS CONTR SEED	POUND	15
28000500	INLET & PIPE PROTECTION	INLET & PIPE PROTECT	EACH	14
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SUB GRAN MAT A 4	SQ YD	4002
40200100	AGGREGATE SURFACE COURSE, TYPE A	AGG SURF CSE A	TON	44
40201000	AGGREGATE FOR TEMPORARY ACCESS	AGGREGATE-TEMP ACCESS	TON	691
40701881	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH) 10"	HMA PAVT FD 10	SQ YD	13.4
42000211	PCC PAVEMENT, 7 1/2" (JOINTED)	PCC PVT 7 1/2 JOINTED	SQ YD	3455
42000501	PCC PAVEMENT, 10" (JOINTED)	PCC PVT 10 JOINTED	SQ YD	80
42001200	PAVEMENT FABRIC	PAVEMENT FABRIC	SQ YD	80
42001300	PROTECTIVE COAT	PROTECTIVE COAT	SQ YD	1654
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6"	PCC DRIVEWAY PAVT 6	SQ YD	245
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7"	PCC DRIVEWAY PAVT 7	SQ YD	203
42400100	PORTLAND CEMENT CONCRETE SIDEWALK, 4"	PC CONC SIDEWALK 4	SQ FT	6743
42400800	DETECTABLE WARNINGS	DETECTABLE WARNINGS	SQ FT	60
44000100	PAVEMENT REMOVAL	PAVEMENT REM	SQ YD	2755
44000200	DRIVEWAY PAVEMENT REMOVAL	DRIVE PAVEMENT REM	SQ YD	386
44000500	COMBINATION CURB AND GUTTER REMOVAL	COMB CURB GUTTER REM	FOOT	1622
44000600	SIDEWALK REMOVAL	SIDEWALK REM	SQ FT	3584
54248515	** CONCRETE COLLAR	CONCRETE COLLAR	EACH	1
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV, 12"	SS 1 RCP CL 4 12	FOOT	175
55019800	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV, 21"	SS 1 RCP CL 4 21	FOOT	120
55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III, 12"	SS 2 RCP CL 3 12	FOOT	38
55021900	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III, 21"	SS 2 RCP CL 3 21	FOOT	631
55100500	STORM SEWER REMOVAL 12"	STORM SEWER REMOV 12	FOOT	428
55100700	STORM SEWER REMOVAL 15"	STORM SEWER REMOV 15	FOOT	383
56108210	** WATER VALVES TO BE ADJUSTED	WATER VALVE ADJUST	EACH	2
56200200	WATER SERVICE LINE, 3/4"	WATER SERV LINE 3/4	FOOT	533
56400100	FIRE HYDRANTS TO BE MOVED	FIRE HYDNTS TO BE MVD	EACH	1
56500100	DOMESTIC METER VAULTS TO BE MOVED	DOM MET VLTS MOVED	EACH	2
56500200	DOMESTIC WATER SERVICE BOXES TO BE MOVED	DOM WAT SER BOX MOVED	EACH	2
56500300	** DOMESTIC METER VAULTS TO BE ADJUSTED	DOM MET VLTS ADJ	EACH	10
56500600	** DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	DOM WAT SER BOX ADJ	EACH	2
60221000	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	MAN TA 5 DIA T1F OL	EACH	6
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	INLETS TA T3F&G	EACH	1
60236200	INLET, TYPE A, TYPE 8 GRATE	INLETS TA T8G	EACH	1
60242500	** INLETS, SPECIAL NO. 1	INLETS SPL N1	EACH	11
60255500	MANHOLES TO BE ADJUSTED	MAN ADJUST	EACH	2
60500040	REMOVING MANHOLES	REMOV MANHOLES	EACH	3
60500060	REMOVING INLETS	REMOV INLETS	EACH	3
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	COMB CC&G TB6.18	FOOT	1802
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	COMB CC&G TB6.24	FOOT	11
67100100	MOBILIZATION	MOBILIZATION	L SUM	1

PAY ITEM #	ITEM DESCRIPTION	ABBREVIATION	UNIT	QUANTITY
70101700	** TRAFFIC CONTROL & PROTECTION	TRAF CONT & PROT	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	SHORT-TERM PAVT MKING	FOOT	84
70300200	TEMPORARY PAVEMENT MARKING	TEMP PAVT MARKING	FOOT	84
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	WORK ZONE PAVT MK REM	SQ FT	28
78008210	** POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4"	POLYUREA PM T1 LN 4	FOOT	2264
78008230	** POLYUREA PAVEMENT MARKING TYPE 1 - LINE 6"	POLYUREA PM T1 LN 6	FOOT	106
78008240	** POLYUREA PAVEMENT MARKING TYPE 1 - LINE 8"	POLYUREA PM T1 LN 8	FOOT	123
78008250	** POLYUREA PAVEMENT MARKING TYPE 1 - LINE 12"	POLYUREA PM T1 LN 12	FOOT	92
78008270	** POLYUREA PAVEMENT MARKING TYPE 1 - LINE 24"	POLYUREA PM T1 LN 24	FOOT	69
78300100	PAVEMENT MARKING REMOVAL	PAVT MARKING REMOVAL	SQ FT	186
Z0013798	** CONSTRUCTION LAYOUT	CONSTRUCTION LAYOUT	L SUM	1
Z0048665	** RAILROAD PROTECTIVE LIABILITY INSURANCE	RR PROT LIABILITY INS	L SUM	1
Z0076600	** TRAINEES	TRAINEES	HOUR	
XX000731	** CASING PIPE	CASING PIPE	FOOT	220
XX002873	** BRICK SIDEWALK REMOVAL	BRICK SIDEWALK REMOVAL	SQ FT	2480
XX003360	** STORM SEWER PVC (SDR 26) 12"	STORM S PVC SDR 26	FOOT	78
XX004830	** RELOCATE INLET, SPECIAL	RELOCATE INLET SPL	EACH	1
X0300025	WATER SERVICE CONNECTION 3/4"	WAT SER CONN 3/4	EACH	10
X7800500	** POLYUREA PAVEMENT MARKING - LETTERS AND SYMBOLS, SPECIAL	POLYUREA PM LTR-SY SPL	SQ FT	124
	** CONNECT EXISTING HOUSE DRAINS AND FIELD TILES TO PROPOSED STORM SEWERS	CON HSE DR & FLD T SS	EACH	6

- * SPECIALTY ITEMS
- ** SPECIAL PROVISION INCLUDED IN SPECIFICATIONS

PLOTTING SCALE: 1" = 1'
 DRAWN BY: JAH
 CHECKED BY: ECM
 DATE: MARCH 2009

NO.	REVISIONS	DATE
1	REV DRYN & DRYN REM	7/27/09

WARD 8 STREET IMPROVEMENTS - PHASE 2
SUMMARY OF QUANTITIES
 CITY OF MACOMB
 SOUTH WARD ST.
 FILE NAME: \\c066\projects\phase2\ward-st-prj-04\wf-ss\qif FIELD BOOK No. 2257 JOB NUMBER: 03-26-0908
 MACOMB, ILLINOIS