

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6711	09-00178-00-R5	TAZEWELL	11	2
STA.		TO STA.		
FED. ROAD DIST. NO. 4		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 89528				

SUMMARY OF QUANTITIES				CITY OF PEKIN 100% FEDERAL CONSTRUCTION TYPE CODE ROADWAY	
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	1000 (BIT.)	
40800100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,342	2,342	
40800300	AGGREGATE (PRIME COAT)	TON	47	47	
40803335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	2,147	2,147	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	2,135	2,135	
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	23,421	23,421	
80265500	MANHOLES TO BE ADJUSTED	EACH	18	18	
67100100	MOBILIZATION	L.SUM	1	1	
70101700	TRAFFIC CONTROL AND PROTECTION	L.SUM	1	1	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	53	53	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10,480	10,480	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	650	650	
* 78000800	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	420	420	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	108	108	
* 88800100	DETECTOR LOOP, TYPE I	FOOT	304	304	

* SPECIALTY ITEMS

GENERAL NOTES:

PROPERTY OWNER ACCESS REQUIREMENT

Access must be maintained to all existing properties during construction per Article 107.09 unless arrangements are made in writing by the Contractor with the property owners with a copy to the Engineer for short-term closures.

No hot-mix asphalt surface removal can begin between October 1, 2009 and March 1, 2010.

WINTER SHUTDOWN RESTRICTIONS ON COLD MILLED PROJECTS

Prior to winter shutdown the following steps shall be taken:

- All cold milled surfaces shall be overlaid.
- All lanes shall be reopened to traffic.
- Manholes, where applicable, shall be adjusted to the elevation of the binder to ease in plowing snow, and re-adjusted to finished grade in the Spring. The initial manhole adjustment will be paid for at the contract unit price and any re-adjustment, as directed by the Engineer, will be paid for in accordance with Article 109.04.
- Temporary or permanent pavement marking shall be placed as applicable.

AECOM

111 NE Jefferson Ave
Peoria, Illinois 61602
PH: (309) 676-8404
FAX: (309) 676-5445
IL Design Firm Reg. No. 184-001518

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
**CITY OF PELIN
PARKWAY DRIVE
SUMMARY OF QUANTITIES
AND GENERAL NOTES**

SCALE: AS SHOWN
DATE: 04/20/2009

DRAWN BY: KRS
CHECKED BY: KMC