

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6711	09-00178-00-RS	TAZEWELL	11	4
STA.		TO STA.		
FED. ROAD DIST. NO. 4		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 89528				

BITUMINOUS MATERIALS (PRIME COAT)	
LOCATION	GALLON
STA. 3+00 TO STA. 26+70 AND STA. 40+00 TO STA. 60+43	2,342
TOTAL	2,342

AGGREGATE (PRIME COAT)	
LOCATION	TON
STA. 3+00 TO STA. 26+70 AND STA. 40+00 TO STA. 60+43	47
TOTAL	47

HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	
LOCATION	TON
STA. 3+00 TO STA. 26+70 AND STA. 40+00 TO STA. 60+43	2,147
TOTAL	2,147

HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	
LOCATION	SQ YD
STA. 3+00 TO STA. 26+70 AND STA. 40+00 TO STA. 60+43	2,185
TOTAL	2,185

HOT-MIX ASPHALT SURFACE REMOVAL, 3"	
LOCATION	SQ YD
STA. 3+00 TO STA. 26+70 AND STA. 40+00 TO STA. 60+43	23,421
TOTAL	23,421

MANHOLES TO BE ADJUSTED	
LOCATION	EACH
STA. 3+00 TO STA. 26+70 AND STA. 40+00 TO STA. 60+43	18
TOTAL	18

MOBILIZATION	
LOCATION	L SUM
STA. 3+00 TO STA. 26+70 AND STA. 40+00 TO STA. 60+43	1
TOTAL	1

TRAFFIC CONTROL AND PROTECTION	
LOCATION	L SUM
STA. 3+00 TO STA. 60+43	1
TOTAL	1

THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS		
LOCATION	NO.	SQ FT
SOUTHBOUND RT. TURN ARROW AT STA. 4+00±	1	8.8
NORTHBOUND RT. TURN ARROW AT VOGEL DR.	1	8.8
NORTHBOUND LT. TURN ARROWS AT VOGEL DR.	2	17.6
SOUTHBOUND LT. TURN ARROWS AT VOGEL DR.	2	17.6
TOTAL		52.8

THERMOPLASTIC PAVEMENT MARKING - LINE 4"			
LOCATION	FOOT	NO.	FOOT
DOUBLE YELLOW			
STA. 3+00 TO VOGEL DR.	386	2	772
VOGEL DR. TO STADIUM DR.	1,163	1	1,163
VOGEL DR. TO STADIUM DR.	1,418	1	1,418
STADIUM DR. TO STA. 26+70	450	2	900
STA. 40+00 TO STA. 60+43	2,043	2	4,086
SKIP DASH			
SOUTHBOUND STA. 3+00 TO VOGEL DR.	10	11	110
SOUTHBOUND VOGEL DR. TO STADIUM DR.	10	11	110
SOUTHBOUND STADIUM DR. TO STA. 26+70	10	35	350
SOUTHBOUND STA. 26+70 TO STA. 60+43	10	51	510
NORTHBOUND STA. 3+00 TO VOGEL DR.	10	9	90
NORTHBOUND VOGEL DR. TO STADIUM DR.	10	35	350
NORTHBOUND STADIUM DR. TO STA. 26+70	10	11	110
NORTHBOUND STA. 26+70 TO STA. 60+43	10	51	510
TOTAL			10,479

THERMOPLASTIC PAVEMENT MARKING - LINE 8"	
LOCATION	FOOT
EXTENDING EXISTING AT COURT ST.	80
SOUTHBOUND LT. TURN AT VOGEL DR.	100
NORTHBOUND RT. TURN AT VOGEL DR.	50
NORTHBOUND LT. TURN AT VOGEL DR.	100
CROSSWALK AT VOGEL DR.	310
TOTAL	650

THERMOPLASTIC PAVEMENT MARKING - LINE 12"	
LOCATION	FOOT
CROSSWALK FOR PARK ENTRANCE (15 STRIPES X 10 FOOT)	270
MEDIAN STRIPES NORTH OF VOGEL (13 STRIPES - LENGTH VARIES)	150
TOTAL	420

THERMOPLASTIC PAVEMENT MARKING - LINE 24"	
LOCATION	FOOT
SOUTHBOUND STOP BAR AT VOGEL DR.	24
NORTHBOUND STOP BAR AT VOGEL DR.	48
NORTHBOUND STOP BAR AT WILLOW ST.	36
TOTAL	108

DETECTOR LOOP, TYPE I	
LOCATION	FOOT
VOGEL DR.	304
TOTAL	304

**AECOM**

111 NE Jefferson Ave  
Peoria, Illinois 61602  
PH: (309) 676-8464  
FAX: (309) 676-5445  
IL Design Firm Reg. No. 184-001518

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**CITY OF PELIN**  
**PARKWAY DRIVE**  
**SCHEDULE OF QUANTITIES**

SCALE: AS SHOWN  
DATE: 04/20/2009

DRAWN BY: KRS  
CHECKED BY: KMC