

SEEDING SCHEDULE

LOCATION	A	B	C	D	E	F	G
	TEMPORARY EROSION CONTROL SEEDING	SEEDING CLASS 1A	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH, METHOD 2
STATION	POUND	ACRES	POUND	POUND	POUND	POUND	ACRE
RT STA. 14+50.00 TO STA. 17+35.14	8.0	0.08	7.2	7.2	7.2	320	0.08
LT STA. 14+50.00 TO STA. 14+90.59	1.0	0.01	0.9	0.9	0.9	40	0.01
LT STA. 15+07.88 TO STA. 17+23.64	7.0	0.07	6.3	6.3	6.3	280	0.07
LT STA. 17+40.36 TO STA. 26+77.04	24.0	0.24	21.6	21.6	21.6	960	0.24
RT STA. 17+50.86 TO STA. 18+03.61	2.0	0.02	1.8	1.8	1.8	80	0.02
RT STA. 18+23.86 TO STA. 24+69.14	18.0	0.18	16.2	16.2	16.2	720	0.18
RT STA. 24+86.86 TO STA. 30+00.00	14.0	0.14	12.6	12.6	12.6	560	0.14
LT STA. 26+99.01 TO STA. 27+41.02	1.0	0.01	0.9	0.9	0.9	40	0.01
LT STA. 27+79.80 TO STA. 30+00.00	2.0	0.02	1.8	1.8	1.8	80	0.02
TOTALS	77.0	0.77	69.3	69.3	69.3	3,080	0.8
USE	80	0.8	72	72	72	(1.6 Ton)	0.8

SIGN SCHEDULE

LOCATION	PLAN ID	SIGN PANEL	SIGN PANEL	SIGN PANEL	RELOCATE	METAL POST
		TYPE 1	TYPE 2	TYPE 3	SIGN PANEL ASSEMBLY - TYPE A	TYPE A
STATION		SF	SF	SF	EACH	FOOT
SORENTO ROAD						
STA. 12+00.00 24 FT LEFT	4,5,6	2.25	10.5	35		60
STA. 14+50.00 24 FT LEFT	1B				1	
STA. 14+50.00 24 FT RIGHT	1A				1	
STA. 15+00.00 24 FT RIGHT	2A	5				11
STA. 19+50.00 24 FT LEFT	2B	5				11
STA. 30+00.00 24 FT LEFT	3	5				11
STA. 32+00.00 24 FT LEFT	7	9				13
STA. 34+75.00 24 FT LEFT	4,5,6	2.25	10.5	35		60
TOTALS		28.5	21	70	2	166
USE		29	21	70	2	166

EROSION CONTROL SCHEDULE

LOCATION	A	B
	INLET AND PIPE PROTECTION	TEMPORARY DITCH CHECK
STATION	EACH	EACH
LT. STA. 15+50.00		1
RT. STA. 15+68.00	1	
LT. STA. 17+45.00	1	
RT. STA. 17+55.00	1	
RT. STA. 18+26.00	1	
RT. STA. 21+50.00		1
LT. STA. 22+00.00		1
RT. STA. 24+90.00	1	
LT. STA. 27+00.00	1	
LT. STA. 28+70.00		1
RT. STA. 29+00.00		1
TOTAL	6	5

PAVEMENT MARKING SCHEDULE

LOCATION	TYPE	PAINT PAVEMENT MARKING - LINE	
		4" WHITE	4" YELLOW
STATION		FOOT	FOOT
LEFT STA. 14+50.00 TO STA. 30+00.00	SOLID	1550.0	
C (LEFT) STA. 14+50.00 TO STA. 19+50.00	SOLID		500.0
C (RIGHT) STA. 14+50.00 TO STA. 19+50.00	SKIP		130.0
CENTER STA. 19+50.00 TO STA. 30+00.00	SKIP		270.0
RIGHT STA. 14+50.00 TO STA. 30+00.00	SOLID	1550.0	
TOTALS		3100.0	900.0
USE		4000	

HENRY, MEISENHEIMER & GENDE, INC., 1075 LAKE ROAD, PO BOX 70, CARLYLE, IL 62231 PHONE (618) 594-3711 WWW.HMGENGINEERS.COM