

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	*	JACKSON	67	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*112-11B-14D9 BSMART FY 10-1

SUMMARY OF QUANTITIES (CONT.)

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	RURAL-JACKSON COUNTY	
				100% FED.	
				X071-2A SN 039-0014	SFTY-2A SN 039-0050
				QUANTITY	QUANTITY
40603575	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N105	TON	165.7	165.7	
42001300	PROTECTIVE COAT	SQ YD	273.4	273.4	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	54.7	54.7	
44000100	PAVEMENT REMOVAL	SQ YD	1348	1,348	
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	713		713
44004250	PAVED SHOULDER REMOVAL	SQ YD	1274	795	479
48101200	AGGREGATE SHOULDERS, TYPE B	TON	123	123	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	515	515	
44213200	SAW CUTS	FOOT	600	600	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1	
50102400	CONCRETE REMOVAL	CU YD	9.6		9.6
50200100	STRUCTURE EXCAVATION	CU YD	354.8	354.8	
50300225	CONCRETE STRUCTURES	CU YD	261.2	261.2	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	409.7	399.0	10.7
50300260	BRIDGE DECK GROOVING	SQ YD	1732	1,048.0	684
50300280	CONCRETE ENCASEMENT	CU YD	8.4	8.4	
50300300	PROTECTIVE COAT	SQ YD	2012	1,283	729
50300530	FLOOR DRAIN EXTENSION	EACH	26		26
50300100	FLOOR DRAINS	EACH	22	22	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	1	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	1734		1734
50500505	STUD SHEAR CONNECTORS	EACH	4086	4,086	
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	12		12
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	117260	115,810	1450
50800515	BAR SPLICERS	EACH	110	92	18

PLOT DATE = 3/19/2009
 FILE NAME = c:\pawson\pawson\shpapp\dgt\cma43645\98641.dgn
 USER NAME = shpappdgt