

SUMMARY OF QUANTITIES (CONT.)

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	*	JACKSON	67	7
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
*12-1B-1:09 BSMART FY 10-1				

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	RURAL-JACKSON COUNTY	
				100% FED.	
				X071-2A SN 039-0014	SFTY-2A SN 039-0050
				QUANTITY	QUANTITY
51201600	FURNISHING STEEL PILES HP12X53	FOOT	715	715	
51201710	FURNISHING STEEL PILES HP12X84	FOOT	792	792	
51202305	DRIVING PILES	FOOT	1507	1,507	
51203600	TEST PILE STEEL HP12X53	EACH	1	1	
51204650	PILE SHOES	EACH	24	24	
51500100	NAME PLATES	EACH	1	1	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	81		81
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	12		12
52100520	ANCHOR BOLTS, 1"	EACH	72	48	24
542A1063	PIPE CULVERTS, CLASS A, TYPE 2 18"	FOOT	600	600	
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	2	2	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	90	90	
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	147	147	
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	250	250	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2	
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	2	2	
63200310	GUARDRAIL REMOVAL	FOOT	206	206	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	24	21	3
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	2	1	1
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	1		1
70100410	TRAFFIC CONTROL AND PROTECTION, STANDARD 701416	EACH	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	4	2	2
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1	0.5	0.5
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	100		100
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	5450	4,106	1344

* SPECIALTY ITEM

PLOT DATE = 3/18/2009
 FILE NAME = C:\pwworking\PMDDT\SHEPARD00\dmu43646\98641.dgn
 USER NAME = shepardg