CONTRACT NO. 98641

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	*	JACKSON	67	8
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*(12-1)B-1;D9 BSMART FY 10-1

SUMMARY OF QUANTITIES(CONT.)

	CODE NUMBER	ITEM DESCRIPTION	UNIT	RURAL-JACKSON COUNTY 100% FED. TOTAL QUANTITY	X071-2A SN 039-0014 QUANTITY	SFTY-2A SN 039-0050 QUANTITY
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2824	2,342	482
	70400100	TEMPORARY CONCRETE BARRIER	FOOT	1775.5	1,338	437.5
	70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1138	788.0	350
	70500100	TEMPORARY STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	188	188	
	70500665	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1	1	
*	78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	5450	4,106	1344
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	7	5	2
*	78200405	GUARDRAIL MARKERS	EACH	6	6	
*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3	3	
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	831	383	448
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	7	5	2
	X0321468	PLUG EXISTING DECK DRAINS	EACH	28		28
	X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1	1	
	X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1	1	
	X5080600	MECHANICAL SPLICERS	EACH	96	96	
	X7050167	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	1	1	
	XZ191200	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/2''	SQ YD	696		696
	Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2''	SQ YD	696		696
	Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1		1
	Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	1	1
⊙	Z0076600	TRAINEES	HOUR	500	350	150

* SPECIALTY ITEM

⊙ Y080

PLOT DATE = 3/26/2009
FILE NAME = c:\pw_work\pwidot\sheper-dgn\dms43646\d9256008pl.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = sheperdgd