PAVEMENT SCHEDULE

LOCATION STATION TO STATION			LENGTH (FOR INFORMATION ONLY)	HOT-MIX ASPHALT LEVELING BINDER	HOT-MIX ASPHALT BINDER COURSE	HOT-MIX ASPHALT SURFACE COURSE	PRIME COAT BITUMINOUS MATERIALS	PRIME COAT AGGREGATE	PAVEMENT REMOVAL	SAW CUTS	HOT-MIX ASPHALT PAVEMENT REMOVAL BUTT-JOINT	TEMPORARY RAMP
			FEET	TON	TON	TON	GAL	TON	SQ YD	FOOT	SQ YD	SQ YD
FAP RT. 331(IL 13)												
MAINLINE PAVEMENT												
241+57	TO	242+12	55.0	3.2		12.4	19	0.2			111.1	31.1
242+11.5	TO	242+17.5	6.0	0.0		0.0	2	0.0				
242+17.5	TO	242+47.5	30.0	0.0		0.0	10	0.1	110.0			
242+47.5	TO	244+32.5	185.0	0.0		0.0	64	0.7				
244+32.5	TO	244+62.5	30.0	0.0		0.0	10	0.1	110.0			
244+62.5	TO	244+68.5	6.0	0.0		0.0	2	0.0				
244+68.5	TO	245+00	31.5	5.3		7.1	11	0.1				
245+00.0	TO	245+50	50.0	11.6		11.3	17	0.2				
245+50.0	TO	246+00	50.0	13.4		11.3	17	0.2				
246+00.0	TO	246+68	68.0	17.1		15.3	24	0.3				
246+68	TO	247+23	55.0	3.3		12.4	19	0.2			111.1	31.1
DETOUR PAVEMENT												
235+00	TO	238+50	350.0		100.3	16.4	62		192.2	220.0		
238+50	TO	239+75	125.0		117.2	19.7	74		232.8			
239+75	TO	242+53	278.0		80.6	13.1	49		154.4	160.0		
244+26	TO	246+90	264.0		71.3	11.7	44		136.0			
246+90	TO	248+00	110.0		99.9	16.7	63		198.0			
248+00	TO	251+00	300.0		109.5	18.3	69		214.2	220.0		
				54.0	578.7	165.7	557.2	2.3	1347.7	600.0	222.2	62.2

SHOULDER SCHEDULE

LOCATION STATION TO STATION						LENGTH (FOR INFORMATION ONLY)	HOT-MIX ASPHALT SHOULDERS	AGGREGATE SHOULDERS TYPE B	PRIME COAT BITUMINOUS MATERIALS	PAVED SHOULDER REMOVAL	GENERAL COMMENTS
						FEET	TON	TON	GAL	SQ YD	
FAP RT. 331(IL 13)											
RT	239+75	TO	RT	242+53	WESTBOUND	278.0	83.0	21.1	16.7	185.3	REMOVE SHOULDER, PLACE NEW
RT	244+26	TO	RT	246+90	WESTBOUND	264.0	78.9	20.0	15.8	176.0	REMOVE SHOULDER, PLACE NEW
LT	241+57	TO	LT	242+12	EASTBOUND	55.0	5.1	1.4	5.5		
LT	244+32	TO	LT	244+69	EASTBOUND	36.5	4.4	0.9	3.1		
LT	244+69	TO	LT	245+00	EASTBOUND	31.5	12.4	0.8	8.5		
LT	245+00	TO	LT	246+00	EASTBOUND	100.0	37.9	2.5	22.6		
LT	246+00	TO	LT	246+13	EASTBOUND	13.0	4.9	0.3	3.0		
LT	246+13	TO	LT	246+43	EASTBOUND	30.0	14.4	0.8	9.3		
LT	246+43	TO	LT	246+60	EASTBOUND	17.0	6.5	0.4	4.1		
LT	246+60	TO	LT	247+23	EASTBOUND	62.6	5.8	1.6	5.9		
RT	241+57	TO	RT	242+12	EASTBOUND	55.0	3.1	1.4	3.3		
RT	235+00	TO	RT	238+50	EASTBOUND	350.0	104.5	26.6	21.0	233.3	REMOVE SHOULDER, PLACE NEW
RT	244+32	TO	RT	244+69	EASTBOUND	36.5	3.6	2.8	2.6		
RT	244+69	TO	RT	245+00	EASTBOUND	31.5	8.1	2.4	5.5		
RT	245+00	TO	RT	246+00	EASTBOUND	100.0	29.6	7.6	18.6		
RT	246+00	TO	RT	246+13	EASTBOUND	13.0	3.8	1.0	2.4		
RT	246+13	TO	RT	246+43	EASTBOUND	30.0	11.3	2.3	7.5		
RT	246+43	TO	RT	246+60	EASTBOUND	17.0	4.9	1.3	3.2		
RT	246+60	TO	RT	247+23	EASTBOUND	62.6	3.3	4.8	3.3		
RT	248+00	TO	RT	251+00	EASTBOUND	300.0	89.6	22.8	18.0	200.0	REMOVE SHOULDER, PLACE NEW
TOTALS							515	123	180	795	

PLOT DATE = 3/18/2009
FILE NAME = c:\pw_work\PWIDOT\SHEPARDGD\dms43646\d7R05608pl.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = shepardgd