


SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	ONLY QUANTITY	F/S/L QUANTITY	TOTAL QUANTITY	RECORD QUANTITY
AR108108	1/C #8 5KV UG CABLE	LF	-	65	65	
AR110202	2" PVC DUCT, DIRECT BURY	LF	-	20	20	
AR125100	ELEVATED RETROREFLECTIVE MARKER	EACH	-	19	19	
AR125902	REMOVE BASE MOUNTED LIGHT	EACH	-	14	14	
AR125942	ADJUST BASE MOUNTED LIGHT	EACH	-	4	4	
AR150510	ENGINEER'S FIELD OFFICE	LS	-	1	1	
AR152410	UNCLASSIFIED EXCAVATION	CY	6,300	8,550	14,850	
AR152540	SOIL STABILIZATION FABRIC	SY	11,625	10,175	21,800	
AR156510	SILT FENCE	LF	-	700	700	
AR156520	INLET PROTECTION	EACH	-	27	27	
AR162506	CLASS E FENCE 6'	LF	-	300	300	
AR162900	REMOVE CLASS E FENCE	LF	149	326	475	
AR162905	REMOVE GATE	EACH	-	2	2	
AR162908	REMOVE ELECTRIC GATE	EACH	-	1	1	
AR163520	CONSTRUCTION FENCE	LF	-	275	275	
AR201610	BITUMINOUS BASE COURSE	TON	-	230	230	
AR208515	POROUS GRANULAR EMBANKMENT	CY	3,950	3,450	7,400	
AR209606	CRUSHED AGG. BASE COURSE - 6"	SY	11,600	10,100	21,700	
AR401610	BITUMINOUS SURFACE COURSE	TON	-	110	110	
AR401655	BUTT JOINT CONSTRUCTION	SY	-	550	550	
AR401900	REMOVE BITUMINOUS PAVEMENT	SY	5,675	5,907	11,582	
AR401910	REMOVE & REPLACE BIT. PAVEMENT	SY	-	215	215	
AR501510	10" PCC PAVEMENT	SY	11,500	9,965	21,465	
AR501530	PCC TEST BATCH	EACH	-	1	1	
AR501900	REMOVE PCC PAVEMENT	SY	2,990	5,125	8,115	
AR602510	BITUMINOUS PRIME COAT	GAL	-	50	50	
AR603510	BITUMINOUS TACK COAT	GAL	-	360	360	
AR620520	PAVEMENT MARKING - WATERBORNE	SF	-	845	845	
AR620525	PAVEMENT MARKING - BLACK BORDER	SF	-	1,140	1,140	
AR701008	8" PVC STORM SEWER	LF	-	210	210	
AR701512	12" RCP, CLASS IV	LF	-	350	350	
AR701515	15" RCP, CLASS IV	LF	-	1,402	1,402	
AR701518	18" RCP, CLASS IV	LF	-	327	327	
AR701900	REMOVE PIPE	LF	510	885	1,395	
AR751001	TRENCH DRAIN	LF	-	150	150	
AR751540	MANHOLE 4'	EACH	-	18	18	
AR751900	REMOVE INLET	EACH	2	1	3	
AR751903	REMOVE MANHOLE	EACH	1	6	7	
AR751940	ADJUST INLET	EACH	1	-	1	
AR754904	REMOVE COMB CURB & GUTTER	LF	-	210	210	
AR760508	8" DUCTILE IRON WATER MAIN	LF	485	50	535	
AR760724	24" STEEL CASING	LF	80	22	102	
AR760947	ADJUST WATER VALVE	EACH	1	-	1	
AR760965	RELOCATE FIRE HYDRANT	EACH	1	-	1	
AR770510	10" SANITARY SEWER	LF	284	-	284	
AR770704	SANITARY MANHOLE 4'	EACH	2	-	2	
AR800040	BUILDING DEMOLITION - SITE A	LS	1	-	1	
AR800053	SOIL GUARD	SY	-	3,600	3,600	
AR800153	CONCRETE WASHOUT	LS	-	1	1	
AR800154	REMOVE WOODEN TAXI GUIDANCE SIGN	EACH	-	3	3	
AR800181	REMOVE LIGHT POLE AND FIXTURE	EACH	2	2	4	
AR800194	REMOVE ELEVATED RETROREFLECTIVE MARKER	EACH	5	14	19	
AR901510	SEEDING	ACRE	-	3.9	3.9	
AR905520	TOPSOILING (FROM OFF SITE)	CY	-	445.0	445.0	
AR908510	MULCHING	ACRE	-	3.2	3.2	

REVISIONS		
NUMBER	BY	DATE



**CHICAGO EXECUTIVE AIRPORT
 WHEELING/PROSPECT HEIGHTS, ILLINOIS
 CONSTRUCT SOUTHEAST QUADRANT APRON**

SUMMARY OF QUANTITIES

© Copyright GMT, Inc.

DESIGN BY:	MLK
DRAWN BY:	JRO
CHECKED BY:	
APPROVED BY:	
DATE:	07/24/09
JOB No:	09290-04
ILLINOIS PROJECT: PWK-3581 A.I.P. PROJECT: 3-17-0018-B37	
SHEET 2 OF 35 SHEETS	