

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	U.S. 45 / 52 BRIDGE SFTY-2A
20200100	EARTH EXCAVATION	CU YD	176	176
25000210	SEEDING, CLASS 2A	ACRE	0.2	0.2
25100630	EROSION CONTROL BLANKET	SQ YD	660	660
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	314	314
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	26	26
40600300	AGGREGATE (PRIME COAT)	TON	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	22	22
40600990	TEMPORARY RAMP	SQ YD	13	13
40603080	HOT MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	26	26
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	26	26
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	294	294
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	72	72
44000086	HOT-MIX ASPHALT SURFACE REMOVAL COMPLETE	SQ YD	196	196
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	255	255
44000700	APPROACH SLAB REMOVAL	SQ YD	192	192
44004250	PAVED SHOULDER REMOVAL	SQ YD	164	164
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	95	95
50102400	CONCRETE REMOVAL	CU YD	5.9	5.9
50300255	CONCRETE SUPERSTRUCTURE	CU YD	8.3	8.3
50300260	BRIDGE DECK GROOVING	SQ YD	180	180
50300300	PROTECTIVE COAT	SQ YD	217	217
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	348	348
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4,310	4,310
50800515	BAR SPLICERS	EACH	39	39
54200445	PIPE CULVERTS, TYPE 1 RCCP 30"	FOOT	30	30
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2	2
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4
63200310	GUARDRAIL REMOVAL	FOOT	292	292
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4
67100100	MOBILIZATION	L SUM	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	U.S. 45 / 52 BRIDGE SFTY-2A
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	665	665
70400100	TEMPORARY CONCRETE BARRIER	FOOT	313	313
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	313	313
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	760	760
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2	2
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2	2
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	4	4
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	12	12
* 78201000	TERMINAL MARKER-DIRECT APPLIED	EACH	4	4
78300100	PAVEMENT MARKING REMOVAL	SQ FT	230	230
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	3	3
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	1
* 81800300	AERIAL CABLE, 3-1/C NO. 2 WITH MESSENGER WIRE	FOOT	1,350	1,350
* 82103400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 400 WATT	EACH	6	6
* 83057120	LIGHT POLE, WOOD, 25 FOOT, CLASS 4	EACH	2	2
* 83057355	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH 15FT MAST ARM	EACH	6	6
* 84100110	REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	6	6
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	348	348
X0321468	PLUG EXISTING DECK DRAINS	EACH	6	6
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	48	48
* X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	4	4
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	272	272
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	1,780	1,780
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	203	203
* X8900005	TEMPORARY BRIDGE TRAFFIC SIGNAL INSTALLATION	EACH	1	1
* XX006937	GROUND ROD, 5/8" DIA. x 10 FT.	EACH	2	2
* X0325949	ELECTRIC SERVICE DISCONNECT, LIGHTING AND TRAFFIC SIGNAL	EACH	1	1
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 2	EACH	2	2
Z0032700	KEYWAY REPAIR	FOOT	350	350

* SPECIALTY ITEM

FILE NAME = 60D68 summary.dgn
PLOT DATE = 7/18/2008



DESIGNED - S.J.P.
DRAWN - A.Y.
CHECKED - E.J.M.
DATE - JULY 10, 2008

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
U.S. 45 / 52
SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE. 330 SECTION 17 B-1-1-1 COUNTY WILL TOTAL SHEETS 29 SHEET NO. 3 CONTRACT NO. 60D68
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT