

SUMMARY OF QUANTITIES

URBAN

CODE NO.	ITEMS	UNIT	TOTAL QUANTITY	90% FEDERAL - 10% STATE				
				1000-2A	J000-2A	Y031-1F	X271-2A	Y007
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	530		530			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	30		30			
20200100	EARTH EXCAVATION	CU YD	14,467		14,467			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	365		365			
20400800	FURNISHED EXCAVATION	CU YD	13,391		13,391			
20700220	POROUS GRANULAR EMBANKMENT	CU YD	96					96
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	308				308	
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	365		365			
20800150	TRENCH BACKFILL	CU YD	700		700			
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1839		1839			
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	5530	5530				
21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	6391	6391				
21400100	GRADING AND SHAPING DITCHES	FOOT	40		40			
* 25000210	SEEDING, CLASS 2A	ACRE	1.5	1.5				
* 25000300	SEEDING, CLASS 3	ACRE	1.75	1.75				
* 25000310	SEEDING, CLASS 4	ACRE	1	1				
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	342	342				
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	342	342				
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	342	342				
* 25100630	EROSION CONTROL BLANKET	SQ YD	18400	18400				
* 25200110	SODDING, SALT TOLERANT	SQ YD	2638	2638				
* 25200200	SUPPLEMENTAL WATERING	UNIT	70	70				
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	1209		1209			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	483		483			
28000300	TEMPORARY DITCH CHECKS	EACH	31		31			
28000500	INLET AND PIPE PROTECTION	EACH	48		48			
28000510	INLET FILTERS	EACH	48		48			
28000720	MULCH, METHOD 2	ACRE	1		1			
28100101	STONE RIPRAP, CLASS A1	SQ YD	63		63			
28200200	FILTER FABRIC	SQ YD	120		120			
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	517	517				
X0326142	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2"	SQ YD	4159		4159			
35300700	PORTLAND CEMENT CONCRETE BASE COURSE 12"	SQ YD	305	305				
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	623	623				
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1080	1080				
40600300	AGGREGATE (PRIME COAT)	TON	22	22				
40600895	CONSTRUCTING TEST STRIP	EACH	3	3				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	213	213				
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	3966	3966				
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	71	71				

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	*	WILL	303	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
*991821 R-389-1B-1-BR-2		CONTRACT: 62253		

- SPECIALTY ITEM
- 50% OF THE AS-BUILT QUANTITY WILL BE CHARGED TO AQUA ILLINOIS (PRIVATE UTILITY BENEFIT). FUND CODE: Y060 (50% AQUA / 50% STATE)
- † NON-PARTICIPATING ITEM
- †† NON-PARTICIPATING FOR RETROREFLECTIVE SIGN SHEETING ONLY - 100% STATE
- ‡ NON-PARTICIPATING ITEM - 100% MONEE FIRE PROTECTION DISTRICT. FUND CODE: Y031-3D

DESIGN FIRM REGISTRATION No. 184-000450
Clark Dietz
 ENGINEERS
 118 SOUTH CLINTON STREET SUITE 600
 CHICAGO, IL 60661
 PHONE : 312.648.9900 FAX : 312.648.0204

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 I-57 AT MANHATTAN - MONEE ROAD
 SUMMARY OF QUANTITIES
 1 OF 9
 SCALE: VERT. NTS
 HORIZ. NTS
 DATE 8/1/2008
 DRAWN BY KLM
 CHECKED BY TMW

07/23/08 09:01
 6/10/2008

Rev