

SUMMARY OF QUANTITIES

URBAN

CODE NO.	ITEMS	UNIT	TOTAL QUANTITY	90% FEDERAL - 10% STATE				
				I000-2A	J000-2A	Y031-1F	X271-2A	Y007
51100100	SLOPE WALL 4 INCH	SQ YD	797				797	
51201400	FURNISHING STEEL PILES HP10X42	FOOT	4823				4823	
51202305	DRIVING PILES	FOOT	4823				4823	
51203400	TEST PILE STEEL HP10X42	EACH	3				3	
51205200	TEMPORARY SHEET PILING	SO FT	211				211	
51500100	NAME PLATES	EACH	2				1	1
52100520	ANCHOR BOLTS, 1"	EACH	44				44	
52100540	ANCHOR BOLTS, 1/2"	EACH	22				22	
54213465	END SECTIONS 30"	EACH	2		2			
54213471	END SECTIONS 36"	EACH	2		2			
54213477	END SECTIONS 42"	EACH	2		2			
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	8		8			
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	3		3			
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	3		3			
54248510	CONCRETE COLLAR	CU YD	1		1			
55039700	STORM SEWERS TO BE CLEANED	FOOT	553		553			
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	677		677			
550A0060	STORM SEWERS, CLASS A, TYPE 1 14"	FOOT	13		13			
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	20		20			
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	450		450			
550A0180	STORM SEWERS, CLASS A, TYPE 1 42"	FOOT	12		12			
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	846		846			
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	59		59			
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	184		184			
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	80		80			
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	78		78			
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	29		29			
550A0470	STORM SEWERS, CLASS A, TYPE 2 42"	FOOT	38		38			
550A0640	STORM SEWERS, CLASS A, TYPE 3 12"	FOOT	70		70			
55100500	STORM SEWER REMOVAL 12"	FOOT	320		320			
55100700	STORM SEWER REMOVAL 15"	FOOT	90		90			
55100900	STORM SEWER REMOVAL 18"	FOOT	470		470			
55101200	STORM SEWER REMOVAL 24"	FOOT	70		70			
55101400	STORM SEWER REMOVAL 30"	FOOT	240		240			
55101800	STORM SEWER REMOVAL 42"	FOOT	15		15			
552A1100	STORM SEWERS JACKED IN PLACE, CLASS A 30"	FOOT	165		165			
56400100	FIRE HYDRANTS TO BE MOVED	EACH	1		1			
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	205				157	48
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	20		20			

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57		WILL	303	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
9901827 R-389-1HB-1-BR-2		CONTRACT: 62253		

- SPECIALTY ITEM
- 50% OF THE AS-BUILT QUANTITY WILL BE CHARGED TO AQUA ILLINOIS (PRIVATE UTILITY BENEFIT). FUND CODE: Y060 (50% AQUA / 50% STATE)
- † NON-PARTICIPATING ITEM
- †† NON-PARTICIPATING FOR RETROREFLECTIVE SIGN SHEETING ONLY - 100% STATE
- * NON-PARTICIPATING ITEM - 100% MONEE FIRE PROTECTION DISTRICT. FUND CODE: Y031-3D

Clark Dietz
ENGINEERS

DESIGN FIRM REGISTRATION No. 184-000450
118 SOUTH CLINTON STREET SUITE 800 CHICAGO, IL 60661
PHONE : 312.648.9900 FAX : 312.648.0204

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-57 AT MANHATTAN - MONEE ROAD
SUMMARY OF QUANTITIES
3 OF 9

SCALE: VERT. NTS
HORIZ. NTS
DATE 8/1/2008

DRAWN BY KLM
CHECKED BY TMW

02231 0803.
 6/10/2008