

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	*	WILL	303	11A
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
*9901&2 R-3&9-1H&1-BR-2		CONTRACT: 62253		

SUMMARY OF QUANTITIES

URBAN

CODE NO.	ITEMS	UNIT	TOTAL QUANTITY	90% FEDERAL - 10% STATE				
				I000-2A	J000-2A	Y031-1F	X271-2A	Y007
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	18	18				
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1			1		
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	170			170		
X7330105	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	71	71				
X8011000	TELEPHONE SERVICE INSTALLATION	EACH	1			1		
X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	3			3		
X8160395	UNIT DUCT, WITH 3-1/C NO. 2 AND 1/C NO. 4 GROUND, 600V (EPR-TYPE RHW), 1/2" DIA., POLYETHYLENE	FOOT	21247			21247		
X8250085	LIGHTING CONTROLLER, DUPLEX CONSOLE TYPE	EACH	1			1		
X8410113	REMOVE TEMPORARY LIGHTING UNITS AND SALVAGE	EACH	4			4		
X8450100	REMOVE EXISTING LIGHTING CONTROLLER AND SALVAGE	EACH	1			1		
X8620020	UNINTERRUPTABLE POWER SUPPLY	EACH	2			2		
X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	1169			1169		
X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	2532			2532		
X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	1435			1435		
X8730350	ELECTRIC CABLE AERIAL SUSPENDED NO. 20 3/C, TWISTED, SHIELDED	FOOT	215			215		
X8950077	REMOVE AND RELOCATE EXISTING LIGHTING CONTROLLER	EACH	1			1		
XX005656	INLET FILTER CLEANING	EACH	96		96			
XZ191300	AGGREGATE SUBGRADE	CU YD	8237			8237		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1			1		
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	1		1			
Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	12	12				
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	4	4				
Z0050900	REMOVE CONCRETE FOUNDATION	EACH	1		1			
Z0064800	SELECTIVE CLEARING	UNIT	36		36			
Z0065740	SLOTTED DRAIN 12" WITH VARIABLE SLOT	FOOT	46		46			
Z0076600	TRAINEES	HOUR	4000	4000				
40701936	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 12 3/4"	SQ YD	6587	6587				
40702700	FURNISH PROFILEGRAPH	L SUM	1	1				
40901000	BACKFILL PLUGS	CU YD	25		25			
87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.	EACH	2			2		
X0325737	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1			1		

- SPECIALTY ITEM
- 50% OF THE AS-BUILT QUANTITY WILL BE CHARGED TO AQUA ILLINOIS (PRIVATE UTILITY BENEFIT). FUND CODE: Y060 (50% AQUA/50% STATE)
- † NON-PARTICIPATING ITEM
- †† NON-PARTICIPATING FOR RETROREFLECTIVE SIGN SHEETING ONLY - 100% STATE
- ‡ NON-PARTICIPATING ITEM - 100% MONEE FIRE PROTECTION DISTRICT. FUND CODE: Y031-3D
- ⊙ Y080

DESIGN FIRM REGISTRATION
No. 184-000460
Clark Dietz
ENGINEERS
118 SOUTH CLINTON STREET
SUITE 800
CHICAGO, IL 60661
PHONE : 312.648.0900
FAX : 312.648.0204

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-57 AT MANHATTAN - MONEE ROAD
SUMMARY OF QUANTITIES
9 OF 9
SCALE: VERT. NTS
HORIZ. NTS
DATE 8/1/2008
DRAWN BY KLM
CHECKED BY TMW

Rev.

02231
6/10/2008