

F.A.L. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	•	WILL	303	21
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
+991182) R-389-11B-1-BR-2		CONTRACT: 62253		

TREE REMOVAL (6 TO 15 UNITS DIAMETER) UNIT				
LOCATION	STATION	OFFSET (FT)		QUANTITY
MANHATTAN-				
MONEE ROAD				
	14032+73	75.98	LT	10
	14032+82	104.88	LT	12
	14032+88	62.39	LT	12
	14032+91	53.28	LT	10
	14033+03	62.89	LT	10
	14033+06	68.05	LT	12
	14033+44	83.67	LT	10
	14033+50	85.87	LT	10
	14033+60	84.85	LT	10
	14033+74	81.98	LT	10
	14033+83	81.68	LT	10
	14033+84	82.02	LT	15
	14033+90	75.94	LT	10
	14034+10	56.96	LT	10
	14034+59	89.51	RT	10
	14034+94	96.01	LT	10
	14034+95	66.94	LT	10
	14034+98	98.97	LT	10
	14035+05	58.33	LT	10
	14035+15	102.91	LT	10
	14035+65	84.97	RT	10
	14035+73	103.07	LT	10
	14035+74	94.43	LT	10
	14035+95	95.45	LT	10
	14036+00	90.44	LT	10
	14036+26	91.67	LT	10
	14036+28	70.19	LT	10
	14036+34	79.67	LT	10
	14038+64	85.49	RT	10
	14039+10	62.57	LT	10
	14039+15	75.95	LT	10
	14039+20	63.13	LT	10
	14039+23	73.31	LT	10
	14039+41	64.24	LT	10
	14039+49	62.07	LT	10
	14039+53	69.41	LT	10
	14039+72	61.71	LT	10
	14039+87	73.33	LT	10
	14041+31	82.48	RT	10
RAMP B				
	234+83	49.96	LT	10
	235+11	64.56	LT	10
	235+36	64.62	LT	10
	235+49	97.31	LT	10
	235+72	42.08	LT	12
	235+77	83.53	LT	10
	235+77	83.53	LT	10
	235+84	77.39	LT	10
	235+95	44.25	LT	10
	235+95	38.06	LT	7
	236+46	62.81	LT	10
	236+63	58.05	LT	10
	236+65	47.98	LT	10
TOTAL				530

TREE REMOVAL (OVER 15 UNITS DIAMETER) UNIT				
LOCATION	STATION	OFFSET (FT)		QUANTITY
MANHATTAN-				
MONEE ROAD				
	14029+38	56.87	LT	30
TOTAL				30

PAVED SHOULDER REMOVAL SO YD				
LOCATION	STATION	TO	STATION	QUANTITY
MANHATTAN-				
MONEE ROAD				
	14030+00	LT	14031+71	LT 45
	14030+59	RT	14032+08	RT 46
	14032+83	LT	14035+64	LT 72
	14033+17	RT	14036+36	RT 94
	14035+95	LT	14036+36	LT 18
	14038+49	RT	14041+96	RT 281
	14038+51	LT	14041+69	LT 90
RAMP A				
	100+21	RT	101+36	RT 33
	100+85	LT	101+36	LT 19
	101+91	RT	102+42	RT 63
	101+91	LT	102+42	LT 12
RAMP B				
	200+00	RT	225+00	RT 2835
	235+21	LT	237+43	LT 80
	235+21	RT	237+41	RT 105
RAMP C				
	300+01	RT	303+06	RT 283
	300+73	LT	303+06	LT 110
RAMP D				
	415+60	LT	419+05	LT 162
	415+60	RT	419+06	RT 453
I-57				
	1355+30	RT	1360+00	RT 221
TOTAL				5,022

AGGREGATE SHOULDERS, TYPE B 6" SO YD				
LOCATION	STATION	TO	STATION	QUANTITY
MANHATTAN-				
MONEE ROAD				
	14024+24	LT	14029+11	LT 220
	14024+24	RT	14025+72	RT 40
	14026+08	RT	14029+50	RT 189
	14029+50	RT	14030+31	RT 54
RAMP B				
	200+00	RT	215+00	RT 333
	215+00	RT	224+81	RT 218
	225+31	LT	228+79	LT 95
TOTAL				1,149

HOT-MIX ASPHALT SURFACE REMOVAL, 1" SO YD				
LOCATION	STATION	TO	STATION	QUANTITY
MANHATTAN-				
MONEE ROAD				
	14046+65		14050+82	2362
TOTAL				2,362

PAVEMENT REMOVAL SO YD				
LOCATION	STATION	TO	STATION	QUANTITY
MANHATTAN-				
MONEE ROAD				
	14024+23.67		14027+47	646
	14027+47		14036+32	3874
	14038+55		14046+65	3818
RAMP A				
	100+50		102+68	839
RAMP B				
	217+85		225+00	1399
	233+60		237+27	1048
RAMP C				
	300+50		303+06	676
RAMP D				
	415+60		418+90	800
I-57				
	1359+97		1355+37	336
TEMP. PAV'T				4312
TOTAL				17,948

HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4" SO YD				
LOCATION	STATION	TO	STATION	QUANTITY
MANHATTAN-				
MONEE ROAD				
	224+81		228+50	698
	228+50		233+60	943
TOTAL				1,641

COMBINATION CURB AND GUTTER REMOVAL FOOT				
LOCATION	STATION	TO	STATION	QUANTITY
MANHATTAN-				
MONEE ROAD				
	14030+82	LT	14032+25	190
	14043+46	RT	14050+82	772
	14043+61	LT	14045+74	204
	14046+18	LT	14046+89	117
	14047+33	LT	14050+82	402
TOTAL				1,685

HOT-MIX ASPHALT SHOULDERS, 8" SO YD				
LOCATION	STATION	TO	STATION	QUANTITY
MANHATTAN-				
MONEE ROAD				
	14024+24	LT	14029+08	161
	14024+24	RT	14029+50	160
	14029+50	RT	14030+32	35
	14030+55	LT	14032+66	97
	14032+66	RT	14033+05	408
	14038+55	RT	14041+56	307
TOTAL				1,168

HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 12 3/4" SO YD				
LOCATION	STATION	TO	STATION	QUANTITY
MANHATTAN-				
MONEE ROAD				
	1355+00		1385+00	6587
TOTAL				6587

POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90 TON				
LOCATION	STATION	TO	STATION	QUANTITY
MANHATTAN-				
MONEE ROAD				
	14046+65		14050+82	225
RAMP B				
	225+00		233+60	129
TOTAL				354

HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 TON				
LOCATION	STATION	TO	STATION	QUANTITY
MANHATTAN-				
MONEE ROAD				
	14025+89	RT		9
	14025+90	LT		4
	14029+17	LT		25
	14043+83	RT		9
	14043+98	LT		9
	14045+33	RT		8
	14045+34	LT		7
TOTAL				71

CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT, 11" SO YD				
LOCATION	STATION	TO	STATION	QUANTITY
MANHATTAN-				
MONEE ROAD				
	14035+08	LT	14036+08	422
	14035+08	RT	14036+08	275
	14038+80	LT	14039+80	289
	14038+80	RT	14039+80	415
TOTAL				1401

PORTLAND CEMENT CONCRETE PAVEMENT 11" (JOINTED) SO YD				
LOCATION	STATION	TO	STATION	QUANTITY
MANHATTAN-				
MONEE ROAD				
	14024+23.67	LT	14029+50	LT 1055
	14024+23.67	RT	14029+50	RT 863
	14029+50		14035+08	3692
	14039+80		14044+50	3242
	14044+50		14046+65	1613
RAMP A				
	100+51		102+42	553
RAMP B				
	233+60		237+27	1386
RAMP C				
	301+50		302+50	669
RAMP D				
	415+60		418+90	1268
TOTAL				14340

PORTLAND CEMENT CONCRETE SHOULDERS 11" SO YD				
LOCATION	STATION	TO	STATION	QUANTITY
MANHATTAN-				
MONEE ROAD				
RAMP A				
	100+87	RT	102+42	RT 129
	101+29	LT	102+42	LT 50
RAMP B				
	223+60	LT	236+92	LT 142
	223+60	RT	236+87	RT 303
RAMP C				
	300+85	RT	303+06	RT 187
	301+29	LT	303+06	LT 79
RAMP D				
	415+60	LT	418+54	LT 127
	415+60	RT	418+54	RT 258
TOTAL				1,275

BRIDGE APPROACH PAVEMENT (SPECIAL) SO YD				
LOCATION	STATION	TO	STATION	QUANTITY
MANHATTAN-				
MONEE ROAD				
	14036+08		14036+38	230
	14038+50		14038+80	240
TOTAL				470

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-57 AT MANHATTAN - MONEE ROAD
SCHEDULE OF QUANTITIES
2 OF 3

SCALE: VERT. NTS
HORIZ. NTS
DATE 9/19/2008

DRAWN BY BDC
CHECKED BY TMW

Clark Dietz
ENGINEERS

DESIGN FIRM REGISTRATION
No. 184-000450
118 SOUTH CLINTON STREET
SUITE 600
CHICAGO, IL 60661
PHONE : 312.648.9900
FAX : 312.648.0204

B:\02251\plans\shere\02251\02251.dgn
9/14/2008