



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

September 9, 2008

SUBJECT: FAU 2552 & FAP 369 (Washington St. & 75th St.)
Project M-BRM-7003(985)
Section 00-00114-00-PV
Dupage County
Contract No. 63024
Item 60
September 19, 2008 Letting
Addendum (A)

TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

Plans – Revised sheets 5, 12, 13, 16, 17, 18, 22A, 44 thru 48C, 140, 141, 167 thru 177, 221 thru 241 and added sheets 142B & 228A.

Proposal – Revised the Schedule of Prices, Index of Special Provisions, page 47 of the Special Provisions and added page 392 to the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Eric Harm
Interim Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger DE".

By: Ted B. Walschleger
Engineer of Project Development
and Implementation

FAU 25552
 00-00114-00-PV (NAPERVILLE)
 DUPAGE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63024

ECMS002 DTGECM03 ECRM003 PAGE 3
 RUN DATE - 09/08/08
 RUN TIME - 204310

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
C2012772	S-VIBURN PRUN 6'	EACH	5.000 X	=			
C2015302	S-J CHIN KLLY CMPT 5G	EACH	* 33.000 X	=			
D2C00718	E-JUNI CH S V 1-1/2'C	EACH	172.000 X	=			
D2001572	E-JUNIP VIRG 6'	EACH	20.000 X	=			
D2002188	E-PICEA PUNGENS 8'	EACH	5.000 X	=			
D2002784	E-PINUS NIGRA 7'	EACH	28.000 X	=			
K0030470	PEREN PL ORN GRASS TY	UNIT	* 20.000 X	=			
XX000372	TEMP AGGREGATE	TON	90.000 X	=			
XX000504	RESTORATION WORK	L SUM	1.000 X	=			
XX001051	WATER SERV LINE RECON	EACH	2.000 X	=			
XX001429	FORM LINER TEX SURF	SQ YD	2,259.000 X	=			
XX002007	AGG BICYCLE PATH	SQ YD	424.000 X	=			
XX002112	TEMP LUM SV HR MT 400	EACH	* 6.000 X	=			
XX003216	UD 3#6 #6G XLPUSE1.25	FOOT	* 10,522.000 X	=			
XX003308	TRENCH DRAIN	FOOT	14.000 X	=			

* Revised 9-9-08

FAU 2552
 00-00114-00-PV (NAPERVILLE)
 DUPAGE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63024

ECMS002 DTGECM03 ECMR003 PAGE 4
 RUN DATE - 09/08/08
 RUN TIME - 204310

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE DOLLARS	CENTS	TOTAL PRICE DOLLARS	CTS
XX003402	WATER MAIN INSULATION	FOOT	* 1,000.000	=			
XX003435	PCC DRIVE REM & REPL	SQ YD	340.000	=			
XX004238	BIT DR REM & PLACE	SQ YD	90.000	=			
XX004809	UNDR BRIDGE COND SYS	L SUM	1.000	=			
XX005049	POWER PEDESTALS	EACH	3.000	=			
XX005307	T-QUERCUS BICOL 3 B&B	EACH	6.000	=			
XX005480	D I WM 16 R U	FOOT	132.000	=			
XX005581	VIDEO TAPE	UNIT	1.000	=			
XX005592	N PHASE 1 TRNSFRMR VA	EACH	7.000	=			
XX005593	N SWITCHGEAR VAULT	EACH	5.000	=			
XX005594	FA-2 ENCASEMENT	CU YD	725.000	=			
XX005595	TRENCH BACKFILL CA-6	CU YD	1,250.000	=			
XX005597	ROD AND MANDREL	FOOT	32,000.000	=			
XX005598	ADD GROUND ROD INSTL	EACH	20.000	=			
XX005600	COUNTERPOISE, UNPAVED	FOOT	1,100.000	=			

* Revised 9-9-08

FAU 2552
 00-00114-00-PV (NAPERVILLE)
 DUPAGE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63024

ECMS002 DTGECM03 ECMR003 PAGE 5
 RUN DATE - 09/08/08
 RUN TIME - 204310

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	CTS
				DOLLARS	CENTS		
XX005601	COUNTERPOISE, PAVED	FOOT	200.000	=			
XX005602	HAND DIG 0'-5' PAV'T	CU YD	40.000	=			
XX005603	HAND DIG 5'-20' PAV'T	CU YD	30.000	=			
XX005604	HAND DIG 0'-5' UNPAVD	CU YD	40.000	=			
XX005605	HAND DIG 5'-20' UNPAVD	CU YD	30.000	=			
XX005606	MACH AID DIG 0-5 PAVE	CU YD	60.000	=			
XX005608	MAC AID DIG 0-5 UNPAV	CU YD	60.000	=			
XX005937	LED INT IL STNAME SGN	EACH	7.000	=			
XX005963	ANTI-GRAFFITI COATING	SQ FT	25,488.000	=			
XX005987	MACH AID DIG 5-20 PVT	CU YD	30.000	=			
XX005989	MACH AID DIG 5-20 UPA	CU YD	60.000	=			
XX006223	PERIMTR EROS BARR MOD	FT	2,620.000	=			
XX006257	REC REF PVT MARKER	EACH	875.000	=			
XX006444	MULCH SPL	ACRE	* 0.750	=			
XX006602	S-ARONIA MLAN IB 2.5'	EACH	84.000	=			

* Revised 9-9-08

FAU 2552
 00-00114-00-PV (NAPERVILLE)
 DUPAGE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63024

ECMS002 DTGECM03 ECMR003 PAGE 6
 RUN DATE - 09/08/08
 RUN TIME - 204310

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	CTS
				DOLLARS	CENTS		
XX006629	S-RHUS TYPHINA CG 5G	EACH	* 94.000		=		
XX007053	CONDUIT RISER ASSEM 6	EACH	1.000		=		
XX007054	HANDHOLE, DEH5	EACH	2.000		=		
XX007055	HANDHOLE, DEH6	EACH	1.000		=		
XX007138	2W 3 PVCDB 1 X 2	FOOT	970.000		=		
XX007140	2W 5 PVCDB 1 X 2	FOOT	20.000		=		
XX007141	2W 6 PVCDB 1 X 2	FOOT	90.000		=		
XX007343	MULCH SHRD HARDWOOD 4	SQ YD	2,420.000		=		
XX007593	MAN INSTALL TYPE A	EACH	8.000		=		
XX007594	MAN INSTALL TYPE G	EACH	8.000		=		
XX007595	MAN INSTALL TYPE E	EACH	1.000		=		
XX007596	CON T TRANS & TRANSP	EACH	4.000		=		
XX007597	1W 1-3 PVC DB 1X1	FOOT	80.000		=		
XX007598	10W 6-6 4-3 PVCDB 4X3	FOOT	60.000		=		
XX007599	10W 10-6 PVC DB 4X3	FOOT	340.000		=		

* Revised 9-9-08

FAU 2552
 00-00114-00-PV (NAPERVILLE)
 DUPAGE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63024

ECMS002 DTGECM03 ECMR003 PAGE 7
 RUN DATE - 09/08/08
 RUN TIME - 204310

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE
				DOLLARS	CENTS	
XX007600	12W 12-6 PVC DB 4X3	FOOT	175.000	X	=	
XX007601	14W 14-6 PVC DB 5X3	FOOT	220.000	X	=	
XX007602	3W 3-6 PVC DB 1X3	FOOT	40.000	X	=	
XX007603	3W 3-3 PVC DB 1X3	FOOT	120.000	X	=	
XX007604	4W 4-3 PVC DB 2X2	FOOT	65.000	X	=	
XX007623	4W 4-6 PVC DB 2X2	FOOT	1,660.000	X	=	
XX007624	5W 5-6 PVC DB 2X3	FOOT	35.000	X	=	
XX007625	6W 6-6 PVC DB 2X3	FOOT	3,435.000	X	=	
XX007626	7W 7-6 PVC DB 3X3	FOOT	75.000	X	=	
XX007627	8W 6-6 2-3 PVCDB 3X3	FOOT	760.000	X	=	
XX007628	8W 8-6 PVC DB 3X3	FOOT	200.000	X	=	
XX007629	9W 9-6 PVC DB 3X3	FOOT	95.000	X	=	
XX007630	CON B&P CN 3 SPL	FOOT	115.000	X	=	
XX007631	CON B&P CN 2W 3 2X2SP	FOOT	100.000	X	=	
XX007632	CON B&P CN 4W 3 2X2SP	FOOT	280.000	X	=	

* Revised 9-9-08

FAU 2552
 00-00114-00-PV (NAPERVILLE)
 DUPAGE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63024

ECMS002 DTGECM03 ECMR003 PAGE 8
 RUN DATE - 09/08/08
 RUN TIME - 204310

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE DOLLARS	CENTS	TOTAL PRICE DOLLARS	CTS
XX007633	CON B&P CN 3W 6 2X3SP	FOOT	70.000 X	=			
XX007634	CON B&P CN 4W 6 2X2SP	FOOT	70.000 X	=			
XX007635	CON B&P CN 6W 6 2X3SP	FOOT	255.000 X	=			
XX007636	CON B&P CN 8W 6 3X3SP	FOOT	80.000 X	=			
XX007637	CON B&P CN 8W 6 3 3X3	FOOT	70.000 X	=			
XX007638	CONN EX HANDHOLE VALT	EACH	1.000 X	=			
XX007639	CONN EX SWITCHGEAR VAL	EACH	4.000 X	=			
XX007640	CONN EX TRANSFRMER VAL	EACH	9.000 X	=			
XX007641	E-JUNI CH FAR PJ 6'	EACH	8.000 X	=			
XX007642	GROUND ROD 3/4 X 10	EACH	3.000 X	=			
XX007643	LUM PED TUN 50W HPS	EACH	14.000 X	=			
XX007644	MAN DT 9 DIA T1F CL	EACH	1.000 X	=			
XX007645	SAN SEW DI 10 AUGERED	FOOT	260.000 X	=			
XX007646	SEED MES WET NAT GRAS	ACRE	1.000 X	=			
XX007647	S-HYDRA PAN TAR 2.5'	EACH	11.000 X	=			

* Revised 9-9-08

FAU 2552
 00-00114-00-pv (NAPERVILLE)
 DUPAGE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63024

ECMS002 DTGECM03 ECMR003 PAGE 9
 RUN DATE - 09/08/08
 RUN TIME - 204310

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
XX007648	S-ITEA VIRG LH VS 2'	EACH	46.000		=		
XX007649	S-RHUS COP PF SS 2'	EACH	102.000		=		
XX007650	S-RHUS TYPHINA TES 3'	EACH	94.000		=		
XX007651	S-SORBARIA UFS 2'	EACH	50.000		=		
XX007652	S-SYMPHO X CH H 1.5'	EACH	82.000		=		
XX007653	S-VIBURN OPUL ROSE 3'	EACH	44.000		=		
XX007654	STONE PILRS DIS STORE	EACH	7.000		=		
XX007655	STORM SEW BACK PREV	EACH	1.000		=		
XX007656	3-SIDED PCC STR 14X11	FOOT	153.000		=		
XX007657	TRAIL TREE ROOT BARR	FOOT	1,000.000		=		
XX007658	T-QUERCUS MACR 3	EACH	8.000		=		
XX007659	T-CELTIS OC CHILAND 3	EACH	6.000		=		
XX007660	T-ROBINIA PSEUD 2-1/2	EACH	11.000		=		
XX007661	T-TAXODI DIS SB 3	EACH	20.000		=		
XX007662	T-MALUS PF TF 3	EACH	34.000		=		

*Revised 9-9-08

FAU 25552
 00-00114-00-PV (NAPERVILLE)
 DUPAGE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63024

ECMS002 DTGECM03 ECMR003 PAGE 10
 RUN DATE - 09/08/08
 RUN TIME - 204310

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	CTS
				DOLLARS	CENTS		
XX007663	T-SYRG PEK M TF 3	EACH	3.000				
XX007664	UD 3#2 #2G XLP USE 2	FOOT	155.000				
XX007723	TEMP WP 60 CL4 15MA	EACH	* 6.000				
XX172700	MAN TA 8 DIA T1F CL	EACH	10.000				
X0301407	PERENNIAL PLT-GAL POT	UNIT	25.000				
X0301576	COAXIAL CABLE IN CON	FOOT	155.000				
X0301892	MAN TA 8D T1FCL R-PLT	EACH	2.000				
X0320873	VIDEO VEH DETECTOR	EACH	1.000				
X0321598	MH TA 6D W/2 T1FCL RP	EACH	5.000				
X0322102	TEMP SIDEWALK RAMP	EACH	17.000				
X0322256	TEMP INFO SIGNING	SQ FT	2,344.000				
X0322671	STAB CONSTR ENTRANCE	SQ YD	240.000				
X0322923	SEGMENT CONC BLK WALL	SQ FT	617.000				
X0322925	ELCBL C TRACER 14 1C	FOOT	7,864.000				
X0323080	DRAINAGE SCUPPR DS-12	EACH	10.000				

* Revised 9-9-08

FAU 2552
 00-00114-00-PV (NAPERVILLE)
 DUPAGE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63024

ECMS002 DTGECM03 ECMR003 PAGE 11
 RUN DATE - 09/08/08
 RUN TIME - 204310

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
X0323199	SAN SEW, DUCT IRN, 10	FOOT	560.000	=			
X0323330	PCC SUBSTRUCTURE	L SUM	1.000	=			
X0323426	SED CONT DR ST INL CL	EACH	2,422.000	=			
X0323574	MAINTAIN LIGHTING SYS	CAL MO	8.000	=			
X0323830	DRAINAGE SCUPPR DS-11	EACH	4.000	=			
X0323973	SED CONT SILT FENCE	FOOT	12,116.000	=			
X0323988	TEMP SOIL RETEN SYSTEM	SQ FT	2,230.000	=			
X0324007	OPTIM TRAF SIGNAL SYS	EACH	1.000	=			
X0324440	CONN TO EX W MAIN 8	EACH	2.000	=			
X0324455	DRILL/SET SOLD P SOIL	CU FT	13,379.000	=			
X0324456	DRILL/SET SOLD P ROCK	CU FT	6,629.000	=			
X0324788	GRANITE PAVERS	SQ FT	5,910.000	=			
X0324973	REM & REPL BIT SURF S	SQ FT	3,750.000	=			
X0324993	SEP JT W/SLEEP SLAB	FOOT	681.000	=			
X0325342	CONN TO EX W MAIN 16	EACH	2.000	=			

* Revised 9-9-08

FAU 25552
 00-00114-00-PV (NAPERVILLE)
 DUPAGE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63024

ECMS002 DTGECM03 ECMR003 PAGE 12
 RUN DATE - 09/08/08
 RUN TIME - 204310

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
X0325737	TEMP TR SIGNAL TIMING	EACH	2.000				
X0329891	SILT CURTAIN	SQ YD	275.000				
X0712400	TEMP PAVEMENT	SQ YD	3,562.000				
X4021000	TEMP ACCESS- PRIV ENT	EACH	3.000				
X4022000	TEMP ACCESS- COM ENT	EACH	4.000				
X4023000	TEMP ACCESS- ROAD	EACH	3.000				
X5020501	UNWAT STR EX PROT L1	EACH	1.000				
X5020502	UNWAT STR EX PROT L2	EACH	1.000				
X5020503	UNWAT STR EX PROT L3	EACH	1.000				
X5020504	UNWAT STR EX PROT L4	EACH	1.000				
X6022120	MAN DT 7 DIA T1F CL	EACH	1.000				
X6022130	MAN DT 8 DIA T1F CL	EACH	1.000				
X6060015	COMB CC&G TM4.24 VMGF	FOOT	131.000				
X6700410	ENGR FLD OFF A SPL	CAL MO	34.000				
X8050010	SERV INSTALL GRND MT	EACH	2.000				

* Revised 9-9-08

FAU 2552
 00-00114-00-pv (NAPERVILLE)
 DUPAGE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63024

ECMS002 DTGECM03 ECMR003 PAGE 13
 RUN DATE - 09/08/08
 RUN TIME - 204310

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
X8120305	CON EMB STR 2 PVC S40	FOOT	1,931.000				
X8620020	UNINTER POWER SUPPLY	EACH	2.000				
X8710020	F0CC62.5/125 MM12SM12	FOOT	7,864.000				
X8730027	ELCBL C GROUND 6 1C	FOOT	1,540.000				
X8730250	ELCBL C 20 3C TW SH	FOOT	2,182.000				
X8770100	S C MA&P DMA 24 & 55	EACH	2.000				
Z0001050	AGG SUBGRADE 12	SQ YD	60,712.000				
Z0001900	ASB BEARING PAD REMOV	EACH	138.000				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
Z0030240	IMP ATTN TEMP NRD TL2	EACH	8.000				
Z0030340	IMP ATTN REL NRD TL2	EACH	3.000				
Z0053700	RESET SURVEY MONUMENT	EACH	1.000				
Z0076600	TRAINEES	HOUR	4,000.000	0.	80	3,200.	00
20100110	TREE REMOV 6-15	UNIT	1,473.000				
20100210	TREE REMOV OVER 15	UNIT	1,295.000				

* Revised 9-9-08

FAU 2552
 00-00114-00-pv (NAPERVILLE)
 DUPAGE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63024

ECMS002 DTGECM03 ECMR003 PAGE 14
 RUN DATE - 09/08/08
 RUN TIME - 204310

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
20101000	TEMPORARY FENCE	FOOT	7,235.000	X	=		
20101200	TREE ROOT PRUNING	EACH	40.000	X	=		
20200100	EARTH EXCAVATION	CU YD	40,045.000	X	=		
20200200	ROCK EXCAVATION	CU YD	596.000	X	=		
20200410	EARTH EXCAVATION SPL	CU YD	1,220.000	X	=		
20201200	REM & DISP UNS MATL	CU YD	5,909.000	X	=		
20700400	POROUS GRAN EMB SPEC	CU YD	890.000	X	=		
20700420	POROUS GRAN EMB SUBGR	CU YD	3,903.000	X	=		
20800150	TRENCH BACKFILL	CU YD	7,026.000	X	=		
21001000	GEOTECH FAB F/GR STAB	SQ YD	11,709.000	X	=		
21101625	TOPSOIL F & P 6	SQ YD	26,120.000	X	=		
21101645	TOPSOIL F & P 12	SQ YD	15,703.000	X	=		
21101685	TOPSOIL F & P 24	SQ YD	10,200.000	X	=		
21101815	COMPOST F & P 4	SQ YD	550.000	X	=		
21300010	EXPLOR TRENCH SPL	FOOT	20.000	X	=		

* Revised 9-9-08

FAU 2552
 00-00114-00-pv (NAPERVILLE)
 DUPAGE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63024

ECMS002 DTGECM03 ECMR003 PAGE 15
 RUN DATE - 09/08/08
 RUN TIME - 204310

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE DOLLARS	CENTS	TOTAL PRICE DOLLARS	CTS
25000210	SEEDING CL 2A	ACRE	7.000 X		=		
25000310	SEEDING CL 4	ACRE	* 1.500 X		=		
25000400	NITROGEN FERT NUTR	POUND	447.000 X		=		
25000500	PHOSPHORUS FERT NUTR	POUND	447.000 X		=		
25000600	POTASSIUM FERT NUTR	POUND	447.000 X		=		
25000920	SEEDING CL 1A SPL	ACRE	* 1.250 X		=		
25100630	EROSION CONTR BLANKET	SQ YD	92,646.000 X		=		
25200100	SODDING	SQ YD	190.000 X		=		
25200200	SUPPLE WATERING	UNIT	2,112.000 X		=		
25200700	SODDING SPL	SQ YD	2,150.000 X		=		
28000250	TEMP ERDS CONTR SEED	POUND	1,025.000 X		=		
28000300	TEMP DITCH CHECKS	EACH	65.000 X		=		
28000500	INLET & PIPE PROTECT	EACH	37.000 X		=		
28000510	INLET FILTERS	EACH	205.000 X		=		
28100105	STONE RIPRAP CL A3	SQ YD	1,914.000 X		=		

* Revised 9-9-08

FAU 2552
 00-00114-00-PV (NAPERVILLE)
 DUPAGE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63024

ECMS002 DTGECM03 ECMR003 PAGE 16
 RUN DATE - 09/08/08
 RUN TIME - 204310

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE
				DOLLARS	CENTS	
28100107	STONE RIPRAP CL A4	SQ YD	534.000	=		
28100109	STONE RIPRAP CL A5	SQ YD	1,137.000	=		
28101500	RIPRAP SPL	SQ YD	100.000	=		
28200200	FILTER FABRIC	SQ YD	1,219.000	=		
31101700	SUB GRAN MAT B 9	SQ YD	2,397.000	=		
35300310	PCC BSE CSE 8 1/2	SQ YD	46,099.000	=		
35300500	PCC BSE CSE 10	SQ YD	2,883.000	=		
40600200	BIT MATLS PR CT	TON	48.000	=		
40600300	AGG PR CT	TON	242.000	=		
40600625	LEV BIND MM N50	TON	202.000	=		
40600895	CONSTRUC TEST STRIP	EACH	2.000	=		
40600982	HMA SURF REM BUTT JT	SQ YD	118.000	=		
40601005	HMA REPL OVER PATCH	TON	131.000	=		
40603085	HMA BC IL-19.0 N70	TON	207.000	=		
40603240	P HMA BC IL19.0 N90	TON	7,623.000	=		

* Revisal 9-9-08

FAU 2552
 00-00114-00-PV (NAPERVILLE)
 DUPAGE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63024

ECMS002 DTGECM03 ECMR003 PAGE 17
 RUN DATE - 09/08/08
 RUN TIME - 204310

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE DOLLARS	CENTS	TOTAL PRICE DOLLARS	CTS
40603310	HMA SC "C" N50	TON	202.000		=		
40603595	P HMA SC "F" N90	TON	5,929.000		=		
42001300	PROTECTIVE COAT	SQ YD	14,199.000		=		
42001400	BR APPRACH PAVT SPL	SQ YD	955.000		=		
42300200	PCC DRIVEWAY PAVT 6	SQ YD	348.000		=		
42300400	PCC DRIVEWAY PAVT 8	SQ YD	296.000		=		
42400200	PC CONC SIDEWALK 5	SQ FT	39,583.000		=		
42400800	DETECTABLE WARNINGS	SQ FT	364.000		=		
44000100	PAVEMENT REM	SQ YD	34,784.000		=		
44000157	HMA SURF REM 2	SQ YD	10,809.000		=		
44000200	DRIVE PAVEMENT REM	SQ YD	2,117.000		=		
44000500	COMB CURB GUTTER REM	FOOT	16,710.000		=		
44000600	SIDEWALK REM	SQ FT	17,679.000		=		
44001700	COMB C C&G REM & REPL	FOOT	240.000		=		
44004250	PAVED SHLD REMOVAL	SQ YD	5,724.000		=		

* Revised 9-9-08

FAU 2552
 00-00114-00-PV (NAPERVILLE)
 DUPAGE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63024

ECMS002 DTGECM03 ECMR003 PAGE 18
 RUN DATE - 09/08/08
 RUN TIME - 204310

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
44004610	SIDEWLK REM & REPL SP	SQ FT	1,920.000	=			
44201000	CL B PATCH T4 12	SQ YD	120.000	=			
44201359	CL C PATCH T4 10	SQ YD	606.000	=			
44201796	CL D PATCH T4 12	SQ YD	80.000	=			
44300200	STRIP REF CR CON TR	FOOT	4,626.000	=			
48203021	HMA SHOULDERS 6	SQ YD	377.000	=			
50100200	REM EXIST STRUCT	L SUM	1.000	=			
50102400	CONC REM	CU YD	49.000	=			
50200100	STRUCTURE EXCAVATION	CU YD	5,700.000	=			
50200400	ROCK EXC STRUCT	CU YD	746.000	=			
50300225	CONC STRUCT	CU YD	2,501.000	=			
50300255	CONC SUP-STR	CU YD	710.000	=			
50300260	BR DECK GROOVING	SQ YD	1,919.000	=			
50300280	CONCRETE ENCASEMENT	CU YD	563.000	=			
50300300	PROTECTIVE COAT	SQ YD	4,439.000	=			

* Revised 9-9-08

FAU 2552
 00-00114-00-PV (NAPERVILLE)
 DUPAGE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63024

ECMS002 DTGECM03 ECMR003 PAGE 19
 RUN DATE - 09/08/08
 RUN TIME - 204310

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	CTS
				DOLLARS	CENTS		
50500105	F & E STRUCT STEEL	L SUM	1.000	X	=		
50500505	STUD SHEAR CONNECTORS	EACH	16,912.000	X	=		
50700209	UNTREATED TIMBER LAG	SQ FT	12,418.000	X	=		
50800105	REINFORCEMENT BARS	POUND	48,170.000	X	=		
50800205	REINF BARS, EPOXY CTD	POUND	443,020.000	X	=		
50800515	BAR SPLICERS	EACH	502.000	X	=		
50901725	BICYCLE RAILING SPL	FOOT	263.000	X	=		
50901755	PARAPET RAILING SPL	FOOT	2,965.000	X	=		
51202210	FUR SOLDIER PILES HP	FOOT	1,383.000	X	=		
51202230	FUR SOLDIER PILES WS	FOOT	2,567.000	X	=		
51500100	NAME PLATES	EACH	1.000	X	=		
51603000	DRILLED SHAFT IN SOIL	CU YD	90.000	X	=		
51604000	DRILLED SHAFT IN ROCK	CU YD	101.000	X	=		
52000110	PREF JT STRIP SEAL	FOOT	295.000	X	=		
52100010	ELAST BEARING ASSY T1	EACH	43.000	X	=		

* Revised 9.9.08

FAU 2552
 00-00114-00-PV (NAPERVILLE)
 DUPAGE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63024

ECMS002 DTGECM03 ECMR003 PAGE 20
 RUN DATE - 09/08/08
 RUN TIME - 204310

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
52100020	ELAST BEARING ASSY T2	EACH	21.000 X		=		
52100520	ANCHOR BOLTS 1	EACH	128.000 X		=		
52100530	ANCHOR BOLTS 1 1/4	EACH	42.000 X		=		
54010603	PCBC 6X3	FOOT	380.000 X		=		
542A0223	P CUL CL A 1 18	FOOT	113.000 X		=		
54207171	P CUL 1 RC-E EQRS 36	FOOT	88.000 X		=		
54207183	P CUL 1 RC-E EQRS 48	FOOT	330.000 X		=		
54213657	PRC FLAR END SEC 12	EACH	4.000 X		=		
54213663	PRC FLAR END SEC 18	EACH	10.000 X		=		
54213669	PRC FLAR END SEC 24	EACH	3.000 X		=		
54213681	PRC FLAR END SEC 36	EACH	2.000 X		=		
54213705	PRC FLAR END SEC 60	EACH	1.000 X		=		
54214521	PRC FL END S EQ RS 36	EACH	2.000 X		=		
54214533	PRC FL END S EQ RS 48	EACH	2.000 X		=		
54215424	CIP RC END SEC 24	EACH	1.000 X		=		

* Revised 9-9-08

FAU 2552
 00-00114-00-pv (NAPERVILLE)
 DUPAGE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63024

ECMS002 DTGECM03 ECRM003 PAGE 21
 RUN DATE - 09/08/08
 RUN TIME - 204310

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE
				DOLLARS	CENTS	
54215430	CIP RC END SEC	EACH	1.000			
54215448	CIP RC END SEC	EACH	1.000			
54244405	FL INLT BX MED 542546	EACH	18.000			
550A0160	STORM SEW CL A 1	FOOT	177.000			
550A0180	STORM SEW CL A 1	FOOT	267.000			
550A0190	STORM SEW CL A 1	FOOT	32.000			
550A0340	STORM SEW CL A 2	FOOT	6,922.000			
550A0360	STORM SEW CL A 2	FOOT	680.000			
550A0380	STORM SEW CL A 2	FOOT	1,567.000			
550A0410	STORM SEW CL A 2	FOOT	1,850.000			
550A0430	STORM SEW CL A 2	FOOT	1,243.000			
550A0450	STORM SEW CL A 2	FOOT	1,150.000			
550A0470	STORM SEW CL A 2	FOOT	455.000			
550A0480	STORM SEW CL A 2	FOOT	293.000			
550A0500	STORM SEW CL A 2	FOOT	592.000			

* Revised 9.9.08

FAU 2552
 00-00114-00-PV (NAPERVILLE)
 DUPAGE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63024

ECMS002 DTGECM03 ECWR003 PAGE 22
 RUN DATE - 09/08/08
 RUN TIME - 204310

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE
				DOLLARS	CENTS	
550A0640	STORM SEW CL A 3 12	FOOT	36.000	X	=	
550A0660	STORM SEW CL A 3 15	FOOT	311.000	X	=	
550A0710	STORM SEW CL A 3 24	FOOT	141.000	X	=	
550A0750	STORM SEW CL A 3 36	FOOT	741.000	X	=	
550A0800	STORM SEW CL A 3 60	FOOT	20.000	X	=	
55035900	SS 2 RCEP S60 R38	FOOT	333.000	X	=	
55037000	SS 3 RCEP S60 R38	FOOT	103.000	X	=	
55100400	STORM SEWER REM 10	FOOT	335.000	X	=	
55100500	STORM SEWER REM 12	FOOT	1,352.000	X	=	
55100700	STORM SEWER REM 15	FOOT	1,420.000	X	=	
55100900	STORM SEWER REM 18	FOOT	132.000	X	=	
55101200	STORM SEWER REM 24	FOOT	322.000	X	=	
55101900	STORM SEWER REM 48	FOOT	42.000	X	=	
56103100	D I WATER MAIN 8	FOOT	660.000	X	=	
56105000	WATER VALVES 8	EACH	1.000	X	=	

* Revised 9-9-08

FAU 2552
 00-00114-00-PV (NAPERVILLE)
 DUPAGE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63024

ECMS002 DTGECM03 ECMR003 PAGE 23
 RUN DATE - 09/08/08
 RUN TIME - 204310

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE
				DOLLARS	CENTS	
56400500	FIRE HYDNITS TO BE REM	EACH	1.000	=		
56400600	FIRE HYDRANTS	EACH	1.000	=		
58000110	MEMBRANE WATERPRF SPL	SQ FT	5,715.000	=		
58700200	BRIDGE SEAT SEALER	SQ FT	590.000	=		
58700300	CONCRETE SEALER	SQ FT	2,798.000	=		
59100100	GEOCOMPOSITE WALL DR	SQ YD	2,049.000	=		
59300100	CONTR LOW-STRENG MATL	CU YD	601.000	=		
60107700	PIPE UNDERDRAINS 6	FOOT	2,638.000	=		
60108200	PIPE UNDERDRAIN 6 SP	FOOT	132.000	=		
60109580	P UNDR FOR STRUCT 4	FOOT	1,890.000	=		
60201310	CB TA 4 DIA T20F&G	EACH	162.000	=		
60207005	CB TC T1F CL	EACH	1.000	=		
60207605	CB TC T8G	EACH	1.000	=		
60208210	CB TC T20F&G	EACH	2.000	=		
60218400	MAN TA 4 DIA T1F CL	EACH	14.000	=		

* Revised 9.9.08

FAU 2552
 00-00114-00-PV (NAPERVILLE)
 DUPAGE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63024

ECMS002 DTGECM03 ECMR003 PAGE 24
 RUN DATE - 09/08/08
 RUN TIME - 204310

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE
				DOLLARS	CENTS	
60221100	MAN TA 5 DIA T1F CL	EACH	35.000	X	=	
60223800	MAN TA 6 DIA T1F CL	EACH	8.000	X	=	
60224446	MAN TA 7 DIA T1F CL	EACH	6.000	X	=	
60228110	MAN SAN 4 DIA T1F CL	EACH	4.000	X	=	
60228300	DROP SAN MAN T1F CL	EACH	1.000	X	=	
60236200	INLETS TA T8G	EACH	5.000	X	=	
60248700	VV TA 4 DIA T1F CL	EACH	2.000	X	=	
60250200	CB ADJUST	EACH	4.000	X	=	
60255500	MAN ADJUST	EACH	4.000	X	=	
60260100	INLETS ADJUST	EACH	4.000	X	=	
60406100	FR & LIDS T1 CL	EACH	5.000	X	=	
60500040	REMOV MANHOLES	EACH	26.000	X	=	
60500050	REMOV CATCH BAS	EACH	23.000	X	=	
60500060	REMOV INLETS	EACH	19.000	X	=	
60600605	CONC CURB TB	FOOT	335.000	X	=	

* Revised 9.9.08

FAU 2552
 00-00114-00-PV (NAPERVILLE)
 DUPAGE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63024

ECMS002 DTGECM03 ECMR003 PAGE 25
 RUN DATE - 09/08/08
 RUN TIME - 204310

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	CTS
				DOLLARS	CENTS		
60603800	COMB CC&G TB6.12	FOOT	3,023.000	=			
60604200	COMB CC&G TB6.12 SPL	FOOT	25.000	=			
60605000	COMB CC&G TB6.24	FOOT	18,519.000	=			
60605400	COMB CC&G TB6.24 SPL	FOOT	2,446.000	=			
60608521	COMB CC&G TM2.24	FOOT	1,712.000	=			
60608600	COMB CC&G TM6.06	FOOT	52.000	=			
60618300	CONC MEDIAN SURF 4	SQ FT	5,919.000	=			
60623711	CONC MEDIAN	SQ FT	2,074.000	=			
63000000	SPBGR TY A	FOOT	125.000	=			
63000005	SPBGR TY B	FOOT	75.000	=			
63100045	TRAF BAR TERM T2	EACH	2.000	=			
63100085	TRAF BAR TERM T6	EACH	3.000	=			
63100167	TR BAR TRM T1 SPL TAN	EACH	5.000	=			
63200310	GUARDRAIL REMOV	FOOT	1,028.000	=			
63300705	RUB RAIL	FOOT	145.000	=			

* Revised 9.9.08

FAU 2552
 00-00114-00-PV (NAPERVILLE)
 DUPAGE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63024

ECMS002 DTGECM03 ECRM003 PAGE 26
 RUN DATE - 09/08/08
 RUN TIME - 204310

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
67100100	MOBILIZATION	L SUM	1.000	=			
70101800	TRAF CONT & PROT SPL	L SUM	1.000	=			
70106800	CHANGEABLE MESSAGE SN	CAL MO	62.000	=			
70300100	SHORT-TERM PAVT MKING	FOOT	13,464.000	=			
70300240	TEMP PVT MK LINE 6	FOOT	3,640.000	=			
70300520	PAVT MARK TAPE T3 4	FOOT	5,744.000	=			
70301000	WORK ZONE PAVT MK REM	SQ FT	63,856.000	=			
70400100	TEMP CONC BARRIER	FOOT	2,540.000	=			
70400200	REL TEMP CONC BARRIER	FOOT	1,100.000	=			
72000100	SIGN PANEL T1	SQ FT	469.000	=			
72000200	SIGN PANEL T2	SQ FT	124.000	=			
72400310	REMOV SIGN PANEL T1	SQ FT	651.000	=			
72400320	REMOV SIGN PANEL T2	SQ FT	44.000	=			
72400720	RELOC SIGN PANEL T2	SQ FT	30.000	=			
72800100	TELES STL SIN SUPPORT	FOOT	720.000	=			

* Revised 9.9.08

FAU 2552
 00-00114-00-PV (NAPERVILLE)
 DUPAGE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63024

ECMS002 DTGECM03 ECRM003 PAGE 27
 RUN DATE - 09/08/08
 RUN TIME - 204310

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
73000100	WOOD SIN SUPPORT	FOOT	76.000	X	=		
73100100	BASE TEL STL SIN SUPP	EACH	7.000	X	=		
78000100	THPL PVT MK LTR & SYM	SQ FT	5,131.000	X	=		
78000200	THPL PVT MK LINE 4	FOOT	155,215.000	X	=		
78000400	THPL PVT MK LINE 6	FOOT	16,794.000	X	=		
78000500	THPL PVT MK LINE 8	FOOT	5,221.000	X	=		
78000600	THPL PVT MK LINE 12	FOOT	6,641.000	X	=		
78000650	THPL PVT MK LINE 24	FOOT	1,807.000	X	=		
78003100	PREF PL PM TB LTR-SYM	SQ FT	199.000	X	=		
78003110	PREF PL PM TB LINE 4	FOOT	1,024.000	X	=		
78003130	PREF PL PM TB LINE 6	FOOT	775.000	X	=		
78100105	RAISED REF PVT MKR BR	EACH	69.000	X	=		
78200100	MONODIR PRIS BAR REFL	EACH	278.000	X	=		
78200410	GUARDRAIL MKR TYPE A	EACH	16.000	X	=		
78200420	GUARDRAIL MKR TYPE B	EACH	15.000	X	=		

* Revised 9.9.08

FAU 2552
 00-00114-00-PV (NAPERVILLE)
 DUPAGE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63024

ECMS002 DTGECM03 ECMR003 PAGE 28
 RUN DATE - 09/08/08
 RUN TIME - 204310

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	CTS.
				DOLLARS	CENTS		
78201000	TERMINAL MARKER - DA	EACH	5.000				
78300100	PAVT MARKING REMOVAL	SQ FT	14,448.000				
80400100	ELECT SERV INSTALL	EACH	3.000				
80400200	ELECT UTIL SERV CONN	L SUM	1.000	6,000	00	6,000	00
81000300	CON T 1 GALVS	FOOT	350.000				
81000600	CON T 2 GALVS	FOOT	3,805.000				
81000700	CON T 2 1/2 GALVS	FOOT	149.000				
81000800	CON T 3 GALVS	FOOT	16.000				
81000900	CON T 3 1/2 GALVS	FOOT	13.000				
81001000	CON T 4 GALVS	FOOT	790.000				
81001100	CON T 5 GALVS	FOOT	112.000				
81001200	CON T 6 GALVS	FOOT	10.000				
81018200	CON P 1 GALVS	FOOT	560.000				
81018500	CON P 2 GALVS	FOOT	500.000				
81018900	CON P 4 GALVS	FOOT	1,554.000				

* Revised 9.9.08

FAU 25552
 00-00114-00-PV (NAPERVILLE)
 DUPAGE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63024

ECMS002 DTGECM03 ECMR003 PAGE 29
 RUN DATE - 09/08/08
 RUN TIME - 204310

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE
				DOLLARS	CENTS	
81019000	CON P 5 GALVS	FOOT	155.000	=		
81019100	CON P 6 GALVS	FOOT	197.000	=		
81100100	CON AT ST 1/2 GALVS	FOOT	290.000	=		
81100300	CON AT ST 1 GALVS	FOOT	450.000	=		
81100600	CON AT ST 2 GALVS	FOOT	280.000	=	*	
81300220	JUN BX SS AS 6X6X4	EACH	2.000	=		
81300550	JUN BX SS AS 12X12X6	EACH	5.000	=		
81302000	JUN BX CI AS 4X4X3	EACH	3.000	=		
81400100	HANDHOLE	EACH	34.000	=		
81400200	HD HANDHOLE	EACH	2.000	=		
81400300	DBL HANDHOLE	EACH	6.000	=		
81700315	EC C EPR RHW 3-1C 10	FOOT	745.000	=		
81800300	A CBL 3-1C2 MESS WIRE	FOOT	1,000.000	=	*	
81900200	TR & BKFIL F ELECT WK	FOOT	15,482.000	=		
82102400	LUM SV HOR MT 400W	EACH	30.000	=	*	

* Revised 9.9.08

FAU 2552
 00-00114-00-pv (NAPERVILLE)
 DUPAGE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63024

ECMS002 DTGECM03 ECMR003 PAGE 30
 RUN DATE - 09/08/08
 RUN TIME - 204310

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
82500505	LIGHT CONTROLLER SPL	EACH	3.000 X	=			
82500605	LT CONTROL PC RELAY	EACH	3.000 X	=			
83007400	LT P A 35MH 10MA	EACH	5.000 X	=			
83008400	LT P A 40MH 10MA	EACH	21.000 X	=			
83600200	LIGHT POLE FDN 24D	FOOT	1,065.000 X	=			
83600215	LIGHT POLE FDN 24D OS	FOOT	45.000 X	=			
83800105	BKWY DEV TR B 11.5BC	EACH	32.000 X	=			
84200500	REM EX LT UNIT SALV	EACH	2.000 X	=			
84200700	LIGHTING FDN REMOV	EACH	2.000 X	=			
84400105	RELOC EX LT UNIT	EACH	28.000 X	=			
85700205	FAC T4 CAB SPL	EACH	1.000 X	=			
85700305	FAC T5 CAB SPL	EACH	1.000 X	=			
86000100	MASTER CONTROLLER	EACH	1.000 X	=			
86400100	TRANSCIEVER - FIB OPT	EACH	2.000 X	=			
87301215	ELCBL C SIGNAL 14 2C	FOOT	4,652.000 X	=			

* Revised 9.9.08

FAU 2552
 00-00114-00-PV (NAPERVILLE)
 DUPAGE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63024

ECMS002 DTGECM03 ECMR003 PAGE 31
 RUN DATE - 09/08/08
 RUN TIME - 204310

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE
				DOLLARS	CENTS	
87301225	ELCBL C SIGNAL 14 3C	FOOT	7,421.000		=	
87301245	ELCBL C SIGNAL 14 5C	FOOT	2,948.000		=	
87301255	ELCBL C SIGNAL 14 7C	FOOT	3,546.000		=	
87301305	ELCBL C LEAD 14 1PR	FOOT	11,415.000		=	
87301805	ELCBL C SERV 6 2C	FOOT	124.000		=	
87502440	TS POST GALVS 10	EACH	1.000		=	
87502480	TS POST GALVS 14	EACH	1.000		=	
87502500	TS POST GALVS 16	EACH	3.000		=	
87700160	S MAA & P 24	EACH	1.000		=	
87700170	S MAA & P 26	EACH	1.000		=	
87700270	S MAA & P 46	EACH	1.000		=	
87700320	S MAA & P 55	EACH	1.000		=	
87702850	STL COMB MAA&P 24	EACH	1.000		=	
87702860	STL COMB MAA&P 26	EACH	1.000		=	
87702920	STL COMB MAA&P 38	EACH	1.000		=	

* Revised 9.9.08

FAU 2552
 00-00114-00-pv (NAPERVILLE)
 DUPAGE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63024

ECMS002 DTGECM03 ECMR003 PAGE 32
 RUN DATE - 09/08/08
 RUN TIME - 204310

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
87703000	STL COMB MAA&P 55	EACH	1.000	X	=		
87800100	CONC FDN TY A	FOOT	20.000	X	=		
87800150	CONC FDN TY C	FOOT	8.000	X	=		
87800400	CONC FDN TY E 30D	FOOT	60.000	X	=		
87800415	CONC FDN TY E 36D	FOOT	90.000	X	=		
87900100	DRILL EX FOUNDATION	EACH	1.000	X	=		
87900200	DRILL EX HANDHOLE	EACH	2.000	X	=		
88040070	SH P LED 1F 3S BM	EACH	1.000	X	=		
88040090	SH P LED 1F 3S MAM	EACH	24.000	X	=		
88040150	SH P LED 1F 5S BM	EACH	6.000	X	=		
88040160	SH P LED 1F 5S MAM	EACH	9.000	X	=		
88040260	SH P LED 2F 1-3 1-5BM	EACH	1.000	X	=		
88102810	PED SH P LED 1F BM	EACH	12.000	X	=		
88102850	PED SH P LED 3F BM	EACH	2.000	X	=		
88200100	TS BACKPLATE	EACH	26.000	X	=		

* Revised 9-9-08

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
88500100	INDUCTIVE LOOP DETECT	EACH	30.000	X	=		
88600100	DET LOOP T1	FOOT	1,640.000	X	=		
88700200	LIGHT DETECTOR	EACH	7.000	X	=		
88700300	LIGHT DETECTOR AMP	EACH	2.000	X	=		
88800100	PED PUSH-BUTTON	EACH	18.000	X	=		
89000100	TEMP TR SIG INSTALL	EACH	1.000	X	=		
89502375	REMOV EX TS EQUIP	EACH	2.000	X	=		
89502380	REMOV EX HANDHOLE	EACH	13.000	X	=		
89502385	REMOV EX CONC FDN	EACH	12.000	X	=		
TOTAL				\$			

** Revised 9.9.08*

- NOTE:
1. EACH PAY ITEM SHOULD HAVE A UNIT PRICE AND A TOTAL PRICE.
 2. THE UNIT PRICE SHALL GOVERN IF NO TOTAL PRICE IS SHOWN OR IF THERE IS A DISCREPANCY BETWEEN THE PRODUCT OF THE UNIT PRICE MULTIPLIED BY THE QUANTITY.
 3. IF A UNIT PRICE IS OMITTED, THE TOTAL PRICE WILL BE DIVIDED BY THE QUANTITY IN ORDER TO ESTABLISH A UNIT PRICE.
 4. A BID MAY BE DECLARED UNACCEPTABLE IF NEITHER A UNIT PRICE NOR A TOTAL PRICE IS SHOWN.

Traffic Signal Specifications For Detector Replacement And/Or Installation On Roadway Grinding, Resurfacing, & Patching Operations	263
Relocate Existing Emergency Vehicle Priority System, Detector Unit	266
Relocate Existing Emergency Vehicle Priority System, Phasing Unit	267
Rebuild Existing Handhole Rebuild Existing Handhole, Special	267
Remove And Reinstall Fiber Optic Cable In Conduit	268
Modify Temporary Traffic Signal Installation	268
Remove Existing Handholes	269
Coaxial Cable in Conduit	269
Video Vehicle Detector	270
Steel Combination Mast Arm Assembly And Pole With Dual Mast Arms, 24 Ft. And 54 Ft.	270
Corps of Engineers Permit	271
Kane-DuPage Soil & Water Conservation District	273
Storm Water Pollution Prevention Plan	274
IDNR Application	286
<i>TEMPORARY WOOD POLE WITH MAST ARM</i>	<i>392</i>

** Revised 9-9-08*

Stone Pillar Dismantle and Store

Description: This work shall consist of dismantling stone pillars by hand, and stacking the stone on palettes. Palettes with the stacked stone shall be left adjacent to the original stone pillar for removal by others.

The stone pillars are located along the frontage of Pioneer Park on the east side of Washington Street. Their condition varies from completely intact to a collapsed pile of stone.

The total height of any loaded palette shall not exceed 24 inches. The palettes shall be placed along the edge of the existing gravel parking lot in Pioneer Park for removal by the Forest Preserve District of DuPage County. Palettes shall be securely wrapped with plastic shrink wrap to prevent movement of stones during future transportation operations. The Forest Preserve District of DuPage County shall be given at least 48 hours advance notice prior to completion of the work and provided with an estimated number of pallets available for transport. The Forest Preserve contact is Kevin Horsfall who can be reached at 630-933-7243.

Method of Measurement: This work shall be measured for payment per each existing stone pillar to be dismantled.

Basis of Payment: The work will be paid for at the contract unit price per each for STONE PILLAR DISMANTLE AND STORE, which price shall include all costs for labor, materials, equipment, and incidentals necessary to perform the work.

Temperature Control for Concrete Placement (District One)

Effective: May 1, 2007

Delete the second and third sentences of the second paragraph of Article 1020.14(a) of the Standard Specifications.

Temporary Ditch Checks

Description: This Special Provision shall be in accordance with Section 280 of the Standard Specifications except as herein modified. Temporary ditch checks shall be constructed with the use of aggregate only. The gradation shall be either CA-1, CA-2, CA-3 or CA-4. The aggregate shall be placed in a manner to produce a reasonably homogeneous stable fill that contains no segregated pockets of large or small fragments or large unfilled spaces caused by bridging of the larger rock fragments.

Method of Measurement: This work shall be in accordance with Article 280.07 of the Standard Specifications.

Basis of Payment: This work shall be paid at the contract unit price per each for TEMPORARY DITCH CHECKS.

Temporary Concrete Barrier

Add the following paragraph to article 704.04 of the Standard Specifications: If the base of the temporary concrete barrier wall is 12 inches or less from the travel lane, then the wall shall also have a 6 inch wide temporary pavement marking yellow edgeline.

TEMPORARY WOOD POLE WITH MAST ARM

Description

This item shall consist of furnishing and installing a temporary wood pole with mast arm as specified herein and shown on the contract drawings.

Materials

The wood pole and mast arm shall comply with Article 1069.04, and be of the length and class specified. The mast arm shall be a truss type, manufactured from either aluminum or galvanized steel, with brackets for attaching to the wood pole, and of all-welded construction. Wood poles and mast arms do not have to be new but must be undamaged and otherwise fully conforming to the requirements of the standard specifications.

Installation

Pole and mast arm installation shall comply with articles 830.03 and 830.04 of the Standard Specifications. Earth excavated for pole installation shall be removed to where excess earth is stored for other work on the project or removed from the project site.

Removal

Upon acceptance of the proposed permanent lighting system, the Contractor shall maintain possession of the temporary wood pole and mast arm and remove them from the construction site. The removal of the temporary luminaire mounted on the pole is included in this work and not paid for separately. The hole created by the removal of the pole shall be filled and compacted with clean fill and topsoil and seeded in conformance with the materials and grading specified for that location in the plan drawings or as directed by the Engineer. Promptly upon removal of the pole, the hole shall be filled or covered with steel plate able to safely support personnel and passenger vehicles before the Contractor's workers move more than 20 feet away from the hole.

Basis of Payment

This item will be paid for at the contract unit price each for TEMPORARY WOOD POLE WITH MAST ARM, of the indicated lengths and class, which shall be payment in full for the material and work described herein and as shown on the plans. 70% of the contract unit price shall be paid upon approved installation of the TEMPORARY WOOD POLE WITH MAST ARM. The full amount of the contract unit price shall be payable upon complete removal of the TEMPORARY WOOD POLE WITH MAST ARM.