

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2552	00-00114-00-PV	DuPAGE	563	6
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	CONTRACT NO. 63024	

IDOT CODE NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL	J000-2A	X928-2A	X071-2A	Y007	Y031-1F			Y030-1E	Y060	Y002
				ROADWAY	PEDSTRIAN TUNNEL & WEST WALLS	STRUCTURES		TRAFFIC SIGNALS			LIGHTING	NAPERVILLE UTILITIES	SIGNING
				90% STATE, 10% DUPAGE COUNTY & NAPERVILLE		BRIDGE	NORTHEAST & SOUTHEAST RETAINING WALLS	75TH & WASHINGTON	WASHINGTON & HOBSON	TRAFFIC SIGNAL INTERCONNECT			
FUNDING	STP	STP/TCM	HBRRP	STP	STP	STP	STP	STP	STP	NON-PARTICIPATING	STP		
28000510	INLET FILTERS	EACH	205	205									
28100105	STONE RIPRAP, CLASS A3	SQ YD	1914	1914									
28100107	STONE RIPRAP, CLASS A4	SQ YD	534	82		452							
28100109	STONE RIPRAP, CLASS A5	SQ YD	1137	1137									
28101500	RIP-RAP SPECIAL	SQ YD	100									100 E	
28200200	FILTER FABRIC	SQ YD	1219	1219									
31101700	SUB-BASE GRANULAR MATERIAL, TYPE B 9"	SQ YD	2397	1579	818								
35300310	PORTLAND CEMENT CONCRETE BASE COURSE 8 1/2"	SQ YD	46099	46099									
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	2883	2883									
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	48	48									
40600300	AGGREGATE (PRIME COAT)	TON	242	242									
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	202	133	69								
40600895	CONSTRUCTING TEST STRIP	EACH	2	2									
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	118	118									
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	131	113								18 W	
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	207	207									
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	7623	7623									
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	202	133	69								
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	5929	5929									
42001300	PROTECTIVE COAT	SQ YD	14199	13960	239								
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	955	955									
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	348	348									
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	296	296									
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	39583	37136	2147							300 W	
42400800	DETECTABLE WARNINGS	SQ FT	364	364									
44000100	PAVEMENT REMOVAL	SQ YD	34784	34784									
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	10809	10809									
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	2117	2117									
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	16710	16698								12 W	

LEGEND:


- * SPECIALTY ITEM
- E NAPERVILLE DEPARTMENT OF PUBLIC UTILITIES - ELECTRIC (NON-PARTICIPATING)
- W NAPERVILLE DEPARTMENT OF PUBLIC UTILITIES - WATER (NON-PARTICIPATING)

REVISIONS	
NAME	DATE

INTERSECTION IMPROVEMENT
WASHINGTON STREET - 75th STREET
SUMMARY OF QUANTITIES

SHEET 2 OF 19

CONSULTANT
TYLIN INTERNATIONAL

City of  **Naperville**

DRAWN:	SHEET NO.
CHECKED:	
APPROVED:	
DATE: APRIL 11, 2008	
SCALE: NONE	
JOB NO. P-91-494-00	PROJECT NO. M-CMM-7003 (985)