

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2552	00-00114-00-PV	DuPAGE	563	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 63024				

IDOT CODE NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL	J000-2A	X928-2A	X071-2A	Y007	Y031-1F			Y030-1E	Y060	Y002
				ROADWAY	PEDSTRIAN TUNNEL & WEST WALLS	STRUCTURES		TRAFFIC SIGNALS			LIGHTING	NAPERVILLE UTILITIES	SIGNING
				90% STATE, 10% DUPAGE COUNTY & NAPERVILLE		BRIDGE	NORTHEAST & SOUTHEAST RETAINING WALLS	75TH & WASHINGTON	WASHINGTON & HOBSON	TRAFFIC SIGNAL INTERCONNECT			
FUNDING	STP	STP/TCM	HBRRP	STP	STP	STP	STP	STP	STP	NON-PARTICIPATING	STP		
44000600	SIDEWALK REMOVAL	SQ FT	17679	17379								300 W	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	240									240 E	
44004250	PAVED SHOULDER REMOVAL	SQ YD	5724	5724									
44004610	SIDEWALK REMOVAL AND REPLACEMENT (SPECIAL)	SQ FT	1920									1920 E	
44201000	CLASS B PATCHES TYPE IV 12 INCHES	SQ YD	120									120 E	
44201359	CLASS C PATCHES, TYPE IV 10 INCH	SQ YD	606	518								88 W	
44201796	CLASS D PATCHES TYPE IV 12 INCH	SQ YD	80									80 E	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	4626	4626									
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	377	377									
50100200	REMOVAL OF EXISTING STRUCTURES	L SUM	1			1							
50102400	CONCRETE REMOVAL	CU YD	49	49									
50200100	STRUCTURE EXCAVATION	CU YD	5700	9	710	2752	2229						
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	746	142	329	147	8					120	
50300225	CONCRETE STRUCTURES	CU YD	2501	36	456	970	1039						
50300255	CONCRETE SUPERSTRUCTURE	CU YD	710			710							
50300260	BRIDGE DECK GROOVING	SQ YD	1919			1919							
50300280	CONCRETE ENCASEMENT	CU YD	563									563 E	
50300300	PROTECTIVE COAT	SQ YD	4439		305	3473	661						
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			1							
50500505	STUD SHEAR CONNECTORS	EACH	16912		1030	14646	1236						
50700209	UNTREATED TIMBER LAGGING	SQ FT	12418		6089		6329						
50800105	REINFORCEMENT BARS	POLND	48170		4940	43230							
50800205	REINFORCEMENT BARS, EPOXY COATED	POLND	443020	2980	44580	284850	110610						
50800515	BAR SPLICERS	EACH	502		16	486							
50901725	BICYCLE RAILING, SPECIAL	FOOT	263	81	31		151						
50901755	PARAPET RAILING, SPECIAL	FOOT	2965	73	738	581	1573						
51202210	FURNISHING SOLDIER PILES (HP SECTION)	FOOT	1383		847		536						
51202230	FURNISHING SOLDIER PILES (W SECTION)	FOOT	2567		866		1701						
51500100	NAME PLATES	EACH	1			1							

LEGEND:


- SPECIALTY ITEM
- E NAPERVILLE DEPARTMENT OF PUBLIC UTILITIES - ELECTRIC (NON-PARTICIPATING)
- W NAPERVILLE DEPARTMENT OF PUBLIC UTILITIES - WATER (NON-PARTICIPATING)

REVISIONS	
NAME	DATE

INTERSECTION IMPROVEMENT
WASHINGTON STREET - 75th STREET
SUMMARY OF QUANTITIES

SHEET 3 OF 19

CONSULTANT
TYLIN INTERNATIONAL

City of  **Naperville**

DRAWN	SHEET NO.
CHECKED	
APPROVED	
DATE: APRIL 11, 2008	
SCALE: NONE	
JOB NO.: P-91-494-00	PROJECT NO.: M-CMM-7003 (985)

P:\63024\7\000V\50005103.dwg 5/4/2008 5:46:46 PM