

**SUMMARY OF QUANTITIES**

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2552	00-00114-00-PV	DuPAGE	563	9
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	CONTRACT NO. 63024	

IDOT CODE NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL	J000-2A	X928-2A	X071-2A	Y007	Y031-1F			Y030-1E	Y060	Y002
				ROADWAY	PEDSTRIAN TUNNEL & WEST WALLS	STRUCTURES		TRAFFIC SIGNALS			LIGHTING	NAPERVILLE UTILITIES	SIGNING
				90% STATE, 10% DUPAGE COUNTY & NAPERVILLE		BRIDGE	NORTHEAST & SOUTHEAST RETAINING WALLS	75TH & WASHINGTON	WASHINGTON & HOBSON	TRAFFIC SIGNAL INTERCONNECT			
FUNDING	STP	STP/TCM	HBRRP	STP	STP	STP	STP	STP	STP	NON-PARTICIPATING	STP		
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	1567	1567									
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	1850	1850									
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	1243	1243									
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	1150	1150									
550A0470	STORM SEWERS, CLASS A, TYPE 2 42"	FOOT	455	455									
550A0480	STORM SEWERS, CLASS A, TYPE 2 48"	FOOT	293	293									
550A0500	STORM SEWERS, CLASS A, TYPE 2 60"	FOOT	592	592									
550A0640	STORM SEWERS, CLASS A, TYPE 3 12"	FOOT	36	36									
550A0660	STORM SEWERS, CLASS A, TYPE 3 15"	FOOT	311	311									
550A0710	STORM SEWERS, CLASS A, TYPE 3 24"	FOOT	141	141									
550A0750	STORM SEWERS, CLASS A, TYPE 3 36"	FOOT	741	741									
550A0800	STORM SEWERS, CLASS A, TYPE 3 60"	FOOT	20	20									
55100400	STORM SEWER REMOVAL 10"	FOOT	335	138								197	
55100500	STORM SEWER REMOVAL 12"	FOOT	1352	1352									
55100700	STORM SEWER REMOVAL 15"	FOOT	1420	1420									
55100900	STORM SEWER REMOVAL 18"	FOOT	132	132									
55101200	STORM SEWER REMOVAL 24"	FOOT	322	322									
55101900	STORM SEWER REMOVAL 48"	FOOT	42	42									
56103100	DUCTILE IRON WATER MAIN, 8"	FOOT	660									660	
56105000	WATER VALVE, 8"	EACH	1									1	
56400500	FIRE HYDRANTS TO BE REMOVED	EACH	1									1	
56400600	FIRE HYDRANTS	EACH	1									1	
58000110	MEMBRANE WATERPROOFING (SPECIAL)	SQ FT	5715		5715								
58700200	BRIDGE SEAT SEALER	SQ FT	590			590							
58700300	CONCRETE SEALER	SQ FT	2798			2798							
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	2049		677	339	1033						
59300100	CONTROLLED LOW STRENGTH MATERIAL	CU YD	601	267								334 W	
60107700	PIPE UNDERDRAINS 6"	FOOT	2638	2638									
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	132	132									

**LEGEND:**


- SPECIALTY ITEM
- E NAPERVILLE DEPARTMENT OF PUBLIC UTILITIES - ELECTRIC (NON-PARTICIPATING)
- W NAPERVILLE DEPARTMENT OF PUBLIC UTILITIES - WATER (NON-PARTICIPATING)

REVISIONS	
NAME	DATE

INTERSECTION IMPROVEMENT  
WASHINGTON STREET - 75th STREET  
SUMMARY OF QUANTITIES

SHEET 5 OF 19

CONSULTANT  
**TYLIN INTERNATIONAL**

City of  **Naperville**

DRAWN:	SHEET NO.
CHECKED:	
APPROVED:	
DATE: APRIL 11, 2008	
SCALE: NONE	
JOB NO.: P-91-494-00	PROJECT NO.: M-CMM-7003 (985)

05/16/2008 4:29:55 PM