

**SUMMARY OF QUANTITIES**

IDOT CODE NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL	J000-2A	X928-2A	X071-2A	Y007	Y031-1F			Y030-1E	Y060	Y002
				ROADWAY	PEDSTRIAN TUNNEL & WEST WALLS	STRUCTURES		TRAFFIC SIGNALS			LIGHTING	NAPERVILLE UTILITIES	SIGNING
				90% STATE, 10% DUPAGE COUNTY & NAPERVILLE	STP/TCM	BRIDGE	NORTHEAST & SOUTHEAST RETAINING WALLS	75TH & WASHINGTON	WASHINGTON & HOBSON	TRAFFIC SIGNAL INTERCONNECT	STP	NON-PARTICIPATING	STP
FUNDING	STP	STP	STP	STP	STP	STP	STP	STP	STP	STP	STP	STP	
60109580	PIPE UNDERDRAINS FOR STRUCTURES, 4"	FOOT	1890		707		1183						
60201310	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 20 FRAME AND GRATE	EACH	162	162									
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	1	1									
60208210	CATCH BASINS, TYPE C, TYPE 20 FRAME AND GRATE	EACH	2	2									
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	14	14									
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	35	35									
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	8	8									
60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	6	6									
* 60228110	MANHOLES, SANITARY, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4									4 W	
* 60228300	DROP SANITARY MANHOLES WITH TYPE 1 FRAME, CLOSED LID	EACH	1									1 W	
60236200	INLET, TYPE A, TYPE 8 GRATE	EACH	5	5									
* 60248700	VALVE VAULTS, 4' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2									2	
60250200	CATCH BASINS TO BE ADJUSTED	EACH	4	4									
60255500	MANHOLES TO BE ADJUSTED	EACH	4	4									
60260100	INLETS TO BE ADJUSTED	EACH	4	4									
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	5	5									
60500040	REMOVING MANHOLES	EACH	26	26									
60500050	REMOVING CATCH BASINS	EACH	23	23									
60500060	REMOVING INLETS	EACH	19	19									
60600605	CONCRETE CURB, TYPE B	FOOT	335	335									
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	3023	3023									
60604200	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL)	FOOT	25	13								12 W	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	18519	18519									
60605400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (SPECIAL)	FOOT	2446	2446									
60608521	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.24	FOOT	1712	1712									
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	52	52									
60618300	CONCRETE MEDIAN SURFACE 4 INCH	SQ FT	5919	5919									
60623711	CONCRETE MEDIAN	SQ FT	2074	2074									
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	125	125									

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2552	00-00114-00-PV	DUPAGE	563	10
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	CONTRACT NO. 63024	

**LEGEND:**


- \* SPECIALTY ITEM
- E NAPERVILLE DEPARTMENT OF PUBLIC UTILITIES - ELECTRIC (NON-PARTICIPATING)
- W NAPERVILLE DEPARTMENT OF PUBLIC UTILITIES - WATER (NON-PARTICIPATING)

REVISIONS	
NAME	DATE

INTERSECTION IMPROVEMENT  
WASHINGTON STREET - 75th STREET  
SUMMARY OF QUANTITIES

SHEET 6 OF 19

CONSULTANT  
**TYLIN INTERNATIONAL**

City of  **Naperville**

DRAWN:	SHEET NO.
CHECKED:	
APPROVED:	
DATE: APRIL 11, 2008	
SCALE: NONE	
JOB NO.: P-91-494-00	PROJECT NO.: M-CMM-7003 (985)