

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2552	00-00114-00-PV	DuPAGE	563	14
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 63024				

IDOT CODE NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL	J000-2A	X928-2A	X071-2A	Y007	Y031-1E			Y030-1E	Y000	Y002
				ROADWAY	PEDSTRIAN TUNNEL & WEST WALLS	STRUCTURES		TRAFFIC SIGNALS			LIGHTING	NAPERVILLE UTILITIES	SIGNING
				90% STATE, 10% DUPAGE COUNTY & NAPERVILLE		BRIDGE	NORTHEAST & SOUTHEAST RETAINING WALLS	75TH & WASHINGTON	WASHINGTON & HOBSON	TRAFFIC SIGNAL INTERCONNECT			
FUNDING	STP	STP/TCM	HBRRP	STP	STP	STP	STP	STP	STP	NON-PARTICIPATING	STP		
* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	3						2	1			
* 87700160	STEEL MAST ARM ASSEMBLY AND POLE, 24 FT	EACH	1						1				
* 87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT	EACH	1							1			
* 87700270	STEEL MAST ARM ASSEMBLY AND POLE, 46 FT.	EACH	1							1			
* 87700320	STEEL MAST ARM ASSEMBLY AND POLE, 55 FT	EACH	1						1				
* 87702850	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 24 FT.	EACH	1						1				
* 87702860	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	1							1			
* 87702920	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1							1			
* 87703000	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 55 FT.	EACH	1						1				
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	20						8	12			
* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	8						4	4			
* 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	60						30	30			
* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	90						60	30			
* 87900100	DRILL EXISTING FOUNDATION	EACH	1									1 E	
* 87900200	DRILL EXISTING HANDHOLES	EACH	2							2			
* 88040070	SIGNAL HEAD, POLYCARBONATE, L.E.D., 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1							1			
* 88040090	SIGNAL HEAD, POLYCARBONATE, L.E.D., 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	24						16	8			
* 88040150	SIGNAL HEAD, POLYCARBONATE, L.E.D., 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	6						4	2			
* 88040160	SIGNAL HEAD, POLYCARBONATE, L.E.D., 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	9						8	1			
* 88040260	SIGNAL HEAD, POLYCARBONATE, L.E.D., 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	1							1			
* 88102810	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, L.E.D., 1-FACE, BRACKET MOUNTED	EACH	12						6	6			
* 88102850	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, L.E.D., 3-FACE, BRACKET MOUNTED	EACH	2						2				
* 88200100	TRAFFIC SIGNAL BACKPLATE	EACH	26						16	10			
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	30						20	10			
* 88600100	DETECTOR LOOP, TYPE 1	FOOT	1640						1051	589			
* 88700200	LIGHT DETECTOR	EACH	7						4	3			
* 88700300	LIGHT DETECTOR AMPLIFIER	EACH	2						1	1			
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	18						12	6			
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1						1				

LEGEND:


- * SPECIALTY ITEM
- E NAPERVILLE DEPARTMENT OF PUBLIC UTILITIES - ELECTRIC (NON-PARTICIPATING)
- W NAPERVILLE DEPARTMENT OF PUBLIC UTILITIES - WATER (NON-PARTICIPATING)

REVISIONS	
NAME	DATE

INTERSECTION IMPROVEMENT
WASHINGTON STREET - 75th STREET
SUMMARY OF QUANTITIES

SHEET 10 OF 19

CONSULTANT
TYLIN INTERNATIONAL

City of  **Naperville**

DRAWN:	SHEET NO.
CHECKED:	
APPROVED:	
DATE: APRIL 11, 2008	
SCALE: NONE	
JOB NO.: P-91-494-00	PROJECT NO.: M-CMM-7003 (985)

6/16/2008 5:46:00 PM