

SUMMARY OF QUANTITIES

IDOT CODE NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL	J000-2A	X928-2A	X071-2A	Y007	Y031-1/E			Y030-1/E	Y060	Y002
				ROADWAY	PEDESTRIAN TUNNEL & WEST WALLS	STRUCTURES		TRAFFIC SIGNALS			LIGHTING	NAPERVILLE UTILITIES	SIGNING
				90% STATE, 10% DUPAGE COUNTY & NAPERVILLE	STP/TCM	BRIDGE	NORTHEAST & SOUTHEAST RETAINING WALLS	75TH & WASHINGTON	WASHINGTON & HOBSON	TRAFFIC SIGNAL INTERCONNECT	STP	NON-PARTICIPATING	STP
FUNDING	STP	HBRRP	STP	STP	STP	STP	STP	STP	STP	STP	STP	STP	
XX005963	ANTI-GRAFFITI COATING	SQ FT	25488		12197	1834	11457						
* XX005598	ADDITIONAL GROUND ROD INSTALLATION	EACH	20									20 E	
* XX006602	SHRUB, ARONIA MELANOCARPA 'MORTON' (IROQUOIS BEAUTY BLACK CHOKEBERRY), 2.5' HEIGHT, BALLED AND BURLAPPED	EACH	84	84									
XX006223	PERIMETER EROSION BARRIER, MODIFIED	FOOT	2620	2620									
* XX006257	RECESSED REFLECTIVE PAVEMENT MARKER	EACH	875	875									
* XX006444	MULCH SPECIAL	ACRE	1									1 E	
* X8620020	UNINTERRUPTABLE POWER SUPPLY	EACH	2					1	1				
* XX006629	SHRUB, RHUS TYPHINA BAILTIGER (TIGER EYE SUMAC), CONTAINER GROWN, 5-GALLON	EACH	45	45									
XX004238	BITUMINOUS DRIVE WAY REMOVAL AND REPLACEMENT	SQ YD	90									90 E	
* XX007053	CONDUIT RISER ASSEMBLY 6"	EACH	1									1 E	
* XX007054	HANDHOLE -DEH5	EACH	2									2 E	
* XX007055	HANDHOLE -DEH6	EACH	1									1 E	
* XX007138	2 WAY--2 3"PVC DUCT BANK 1 HIGH BY 2 WIDE	FOOT	970									970 E	
* XX007140	2 WAY--2- 5"PVC DUCT BANK 1 HIGH BY 2 WIDE	FOOT	20									20 E	
* XX007141	2 WAY--2- 6"PVC DUCT BANK 1 HIGH BY 2 WIDE	FOOT	90									90 E	
XX172700	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	10	10									
* X0301407	PERENNIAL PLANTS, GALLON POT	UNIT	25	25									
* X0301576	COAXIAL CABLE IN CONDUIT	FOOT	155					155					
* X0320873	VIDEO VEHICLE DETECTOR	EACH	1					1					
X0321598	MANHOLES, TYPE A, 6'-DIAMETER, 2-TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	5	5									
X0322102	TEMPORARY SIDEWALK RAMPS	EACH	17	14								3 E	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	2344	2344									
X0322671	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	240	240									
* X0322923	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	617	267								350 E	
* X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14-1C	FOOT	7864							7864			
X0323080	DRAINAGE SCUPPERS, DS-12	EACH	10			10							
* X0323199	SANITARY SEWER, DUCTILE IRON 10"	FOOT	560									560 W	
X0323330	PRECAST CONCRETE SUBSTRUCTURE	L SUM	1		1								

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2552	00-00114-00-PV	DUPAGE	563	18
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	CONTRACT NO. 63024	

LEGEND:


- * SPECIALTY ITEM
- E NAPERVILLE DEPARTMENT OF PUBLIC UTILITIES - ELECTRIC (NON-PARTICIPATING)
- W NAPERVILLE DEPARTMENT OF PUBLIC UTILITIES - WATER (NON-PARTICIPATING)

REVISIONS	
NAME	DATE

INTERSECTION IMPROVEMENT
WASHINGTON STREET - 75th STREET
SUMMARY OF QUANTITIES

SHEET 14 OF 19

CONSULTANT
TYLIN INTERNATIONAL

City of  **Naperville**

DRAWN	SHEET NO.
CHECKED	
APPROVED	
DATE: APRIL 11, 2008	
SCALE: NONE	
JOB NO.: P-91-494-00	PROJECT NO.: M-CMM-7003 (985)