

**SUMMARY OF QUANTITIES**

F.A.D. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2552	00-00114-00-PV	DUPAGE	563	20
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	CONTRACT NO. 63024	

IDOT CODE NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL	J000-2A	X928-2A	X071-2A	Y007	Y031-1F			Y030-1E	Y060	Y002
				ROADWAY	PEDSTRIAN TUNNEL & WEST WALLS	STRUCTURES		TRAFFIC SIGNALS			LIGHTING	NAPERVILLE UTILITIES	SIGNING
				90% STATE, 10% DUPAGE COUNTY & NAPERVILLE	STP/TCM	BRIDGE	NORTHEAST & SOUTHEAST RETAINING WALLS	75TH & WASHINGTON	WASHINGTON & HOBSON	TRAFFIC SIGNAL INTERCONNECT	STP	NON-PARTICIPATING	STP
FUNDING	STP	STP	STP	STP	STP	STP	STP	STP	STP	STP	STP	STP	
X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F,SM12F	FOOT	7864										
X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1/C (GREEN)	FOOT	1540					933	607				
X8730250	ELECTRIC CABLE IN CONDUIT, NO. 20 3/C, TWISTED, SHIELDED	FOOT	2182					1466	716				
X8770100	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 24 FT. AND 54 FT.	EACH	2					2					
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	60712	60712									
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	138			138							
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1									
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-DIRECTIVE), TEST LEVEL 2	EACH	8	8									
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-DIRECTIVE), TEST LEVEL 2	EACH	3	3									
Z0053700	RESETTING SURVEY MONUMENTS	EACH	1	1									
Z0076600	TRAINEES	HOUR	4000	4000									
XX007597	1 WAY-- 1-3" PVC DUCT BANK 1 HIGH BY 1 WIDE	FOOT	80									80 E	
XX007598	10 WAY-- 6-6" & 4-3" PVC DUCT BANK 4 HIGH BY 3WIDE	FOOT	60									60 E	
XX007599	10 WAY--10- 6" PVC DUCT BANK 4 HIGH BY 3 WIDE	FOOT	340									340 E	
XX007600	12 WAY--12- 6" PVC DUCT BANK 4 HIGH BY 3 WIDE	FOOT	175									175 E	
XX007601	14 WAY--14- 6" PVC DUCT BANK 5 HIGH BY 3 WIDE	FOOT	220									220 E	
XX007602	3 WAY--3- 6" PVC DUCT BANK 1 HIGH BY 3 WIDE	FOOT	40									40 E	
XX007603	3 WAY--3-3" PVC DUCT BANK 1 HIGH BY 3 WIDE	FOOT	120									120 E	
XX007604	4 WAY--4- 3" PVC DUCT BANK 2 HIGH BY 2 WIDE	FOOT	65									65 E	
XX007623	4 WAY--4- 6" PVC DUCT BANK 2 HIGH BY 2 WIDE	FOOT	1660									1660 E	
XX007624	5 WAY--5- 6" PVC DUCT BANK 2 HIGH BY 3 WIDE	FOOT	35									35 E	
XX007625	6 WAY--6- 6" PVC DUCT BANK 2 HIGH BY 3 WIDE	FOOT	3435									3435 E	
XX007626	7 WAY--7- 6" PVC DUCT BANK 3 HIGH BY 3 WIDE	FOOT	75									75 E	
XX007627	8 WAY-- 6-6" & 2-3" PVC DUCT BANK 3 HIGH BY 3 WIDE	FOOT	760									760 E	
XX007628	8 WAY- 8- 6" PVC DUCT BANK 3 HIGH BY 3 WIDE	FOOT	200									200 E	
XX007629	9 WAY--9-6" PVC DUCT BANK 3 HIGH BY 3 WIDE	FOOT	95									95 E	
XX007630	CONDUIT, BORED AND PULLED, COILABLE NON-METALLIC, 3" SPECIAL	FOOT	115									115 E	
XX007631	CONDUIT, BORED AND PULLED, COILABLE NON-METALLIC, 2 WAY DUCT 3" -	FOOT	100									100 E	

**LEGEND:**


- \* SPECIALTY ITEM
- E NAPERVILLE DEPARTMENT OF PUBLIC UTILITIES - ELECTRIC (NON-PARTICIPATING)
- W NAPERVILLE DEPARTMENT OF PUBLIC UTILITIES - WATER (NON-PARTICIPATING)
- Δ Y680

REVISIONS	
NAME	DATE

INTERSECTION IMPROVEMENT  
WASHINGTON STREET - 75th STREET  
SUMMARY OF QUANTITIES

SHEET 16 OF 19

CONSULTANT  
**TYLIN INTERNATIONAL**

City of  **Naperville**

DRAWN: \_\_\_\_\_ SHEET NO. \_\_\_\_\_

CHECKED: \_\_\_\_\_

APPROVED: \_\_\_\_\_

DATE: APRIL 11, 2008

SCALE: NONE

JOB NO.: P-91-494-00 PROJECT NO.: M-CMM-7003 (985)