

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2552	00-00114-00-PV	DuPAGE	563	40
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 63024				


EARTHWORK QUANTITIES

LOCATION		EARTH EXCAVATION (20200100)	TOPSOIL (UNSUITABLE) REMOVAL (20201200)	EXCAVATION TO BE USED IN EMBANKMENT (ADJ FOR SHRINKAGE - 15%) (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
STA	TO STA	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
WASHINGTON						
427+95	467+53	26990.0	3300.0	22941.5	2940.0	+ 20001.5
75TH						
128+00	163+50	11327.5	2079.4	9628.4	9079.9	+ 548.5
HOBSON						
700+73	702+24	170.0	55.0	144.5	100.0	+ 44.5
TOTALS		38487.5	5434.4	32714.4	12119.9	+ 20594.5
TUNNEL						
143+50	147+50	1447.5	165.6	1230.4	0.1	+ 1230.2
GRAND TOTAL		39935	5600	33945	12120	+ 21824.8

REVISIONS	
NAME	DATE

INTERSECTION IMPROVEMENT
 WASHINGTON STREET - 75th STREET
 SCHEDULE OF QUANTITIES
 PROPOSED EARTHWORK QUANTITIES
 SHEET 7 OF 7

CONSULTANT
TYLIN INTERNATIONAL

City of  **Naperville**

DRAWN:	SHEET NO.
CHECKED:	
APPROVED:	
DATE: APRIL 11, 2008	
SCALE:	
JOB NO.: P-91-494-00	PROJECT NO.: M-CMM-7003 (985)

P:\60247\road\N\Sched7.dgn
 4/11/2008 10:41 PM