

PROPOSED SIGNING SCHEDULE


F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2552	00-00114-00-PV	DuPAGE	563	187
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 63024				

SIGN NO.	ALIGNMENT	SIGN INFORMATION						SUPPORT INFORMATION			SIGN DESCRIPTION	
		PROP. STATION	OFFSET	TYPE	WIDTH (FT)	HEIGHT (FT)	AREA (FT)	TYPE	POST QUANTITY	POST LENGTH (FT)		BASE FOR TELES. STEEL (EACH)
55	75TH ST CENTERLINE	134+71.43	115.4' LT	1	3.0	3.0	9.0	TELESCOPING STEEL	1	18.0		R1-1
56	75TH ST CENTERLINE	134+74.43	115.4' LT	1	3.0	3.0	9.0	MOUNTED WITH ABOVE				R3-2
57	75TH ST CENTERLINE	134+89.81	11.4' RT	1	3.0	1.0	3.0	TELESCOPING STEEL	1	13.0		R6-1R
58	75TH ST CENTERLINE	134+90.27	12.0' LT	1	3.0	1.0	3.0	TELESCOPING STEEL	1	13.0		R6-1R
59	75TH ST CENTERLINE	135+09.99	81.5' RT	1	3.0	3.0	9.0	TELESCOPING STEEL	1	18.0		R1-1
60	75TH ST CENTERLINE	135+09.99	81.5' RT	1	3.0	3.0	9.0	MOUNTED WITH ABOVE				R3-2
61	75TH ST CENTERLINE	136+98.86	56.0' LT	1	3.0	3.0	9.0	TELESCOPING STEEL	1	16.3		W9-1R
62	75TH ST CENTERLINE	141+98.86	56.0' LT	1	3.0	3.0	9.0	TELESCOPING STEEL	1	16.3		W9-1R
63	75TH ST CENTERLINE	143+03.35	56.4' RT	2	2.5	4.0	10.0	TELESCOPING STEEL	1	16.0		RELOCATED EXISTING SIGN PANEL - "DOWNTOWN NAPERVILLE WITH UP ARROW"
64	75TH ST CENTERLINE	144+54.00	50.9' RT	2	3.0	4.0	12.0	TELESCOPING STEEL	1	11.0	1	R2-1 -"SPEED LIMIT 45"
65	75TH ST CENTERLINE	147+91.28	83.4' LT	1	2.0	2.5	5.0	SIGNAL POST MOUNT				R10-11a
66	75TH ST CENTERLINE	148+04.05	11.5' LT	1	2.5	2.5	6.25	TELESCOPING STEEL	1	17.0		R3-8 (MODIFIED)
67	75TH ST CENTERLINE	148+04.05	11.5' LT	1	2.0	2.5	5.0	MOUNTED WITH ABOVE				R4-7
68	75TH ST CENTERLINE	148+35.71	74.9' RT	1	2.0	2.5	5.0	SIGNAL POST MOUNT				R10-11a
69	75TH ST CENTERLINE	148+41.34	67.4' LT	1	2.5	2.5	6.25	SIGNAL POST MOUNT				M1-6 - "DU PAGE COUNTY 33"
70	75TH ST CENTERLINE	150+14.70	67.3' RT	1	2.5	2.5	6.25	SIGNAL POST MOUNT				M1-6 - "DU PAGE COUNTY 33"
71	75TH ST CENTERLINE	150+15.44	74.3' LT	1	2.0	2.5	5.0	SIGNAL POST MOUNT				R10-11a
72	75TH ST CENTERLINE	150+62.32	11.9' RT	1	2.5	2.5	6.25	TELESCOPING STEEL	1	17.0		R3-8 (MODIFIED)
73	75TH ST CENTERLINE	150+62.32	11.9' RT	1	2.0	2.5	5.0	MOUNTED WITH ABOVE				R4-7
74	75TH ST CENTERLINE	150+64.30	83.4' LT	1	2.0	2.5	5.0	SIGNAL POST MOUNT				R10-11a
75	75TH ST CENTERLINE	150+84.86	58.4' RT	1	3.0	3.0	9.0	TELESCOPING STEEL	1	11.3	1	W9-1R
76	75TH ST CENTERLINE	154+92.49	4.7' LT	1	3.0	1.0	3.0	TELESCOPING STEEL	1	13.0		R6-1R
77	75TH ST CENTERLINE	155+58.23	12.0' RT	1	3.0	1.0	3.0	TELESCOPING STEEL	1	13.0		R6-1R
78	75TH ST CENTERLINE	155+78.17	72.7' RT	1	3.0	3.0	9.0	TELESCOPING STEEL	1	18.0		R1-1
79	75TH ST CENTERLINE	155+78.17	72.7' RT	1	3.0	3.0	9.0	MOUNTED WITH ABOVE				R3-2
80	75TH ST CENTERLINE	156+26.44	56.0' LT	2	2.5	4.0	10.0	TELESCOPING STEEL	1	16.0		RELOCATED EXISTING SIGN PANEL - "DOWNTOWN NAPERVILLE WITH UP ARROW"
81	75TH ST CENTERLINE	156+85.21	54.0' RT	1	3.0	3.0	9.0	TELESCOPING STEEL	1	16.3		W9-2L
82	75TH ST CENTERLINE	160+05.41	12.0' LT	1	3.0	1.0	3.0	TELESCOPING STEEL	1	13.0		R6-1R
83	75TH ST CENTERLINE	160+90.71	67.8' LT	1	3.0	3.0	9.0	TELESCOPING STEEL	1	18.0		R1-1
84	75TH ST CENTERLINE	160+90.71	67.8' LT	1	3.0	3.0	9.0	MOUNTED WITH ABOVE				R3-2
85	75TH ST CENTERLINE	162+50.00	44.0' LT	2	3.0	4.0	12.0	TELESCOPING STEEL	1	16.0		R2-1
86	75TH ST CENTERLINE	163+00.00	44.0' RT	2	3.0	4.0	12.0	TELESCOPING STEEL	1	16.0		R2-1

REVISIONS	
NAME	DATE

INTERSECTION IMPROVEMENT
 WASHINGTON STREET - 75th STREET
 PROPOSED SIGNING SCHEDULE
 75TH AND WASHINGTON
 SHEET 2 OF 2

CONSULTANT
TYLIN INTERNATIONAL

City of  **Naperville**

DRAWN: _____ SHEET NO. _____
 CHECKED: _____
 APPROVED: _____
 DATE: APRIL 11, 2008
 SCALE: _____
 JOB NO.: P-91-494-00 PROJECT NO.: M-CMM-7003 (985)

4/11/2008 2:04:12 PM p:\60247\road\signing\signing2.dgn