



DnB90SA: STANDOFF BEND

Item Code	Description 1	Description 2	DnB90SA		
			Qty	Qty	Qty
285 101 00140	ELBOW, 30"R STL 90 DEG 3"	GALVANIZED	2		
285 101 00180	ELBOW, 36"R STL 90 DEG 5"	GALVANIZED		2	
285 101 00210	ELBOW, 48"R STL 90 DEG 6"	GALVANIZED			2
285 102 00040	COUPLING, PVC 3"	LONG LINE SCH 40	2		
285 102 00110	COUPLING, PVC 5"	LONG LINE SCH 40		2	
285 102 00140	COUPLING, PVC 6"	LONG LINE SCH 40			2
285 199 00005	BRACKET, POLE, 3"	STANDOFF	1	1	1
285 199 00030	STRAP, 3" CONDUIT	WITH 2 BOLT, NUT & WASHERS	2		
285 199 00040	STRAP, 5" CONDUIT	WITH 2 BOLT, NUT & WASHERS		2	
285 199 00050	STRAP, 6" CONDUIT	WITH 2 BOLT, NUT & WASHERS			2
285 199 00070	CHANNEL, 12"	4-WAY T-SLOT	1	1	
285 199 00080	CHANNEL, 24"	4-WAY T-SLOT			1

ASSEMBLY CODES		
CODE	QTY	DESCRIPTION
DnB90SA	1	Standoff Bend Assembly
n is dependent on size		

NAPERVILLE PUBLIC UTILITIES DEPARTMENT ELECTRIC STANDARDS	STEEL BEND STUBS AT RISER POLE	DATE: 06-29-04 Page 1 of 2 C30-0320
--	---------------------------------------	---

NAPERVILLE PUBLIC UTILITIES DEPARTMENT ELECTRIC STANDARDS	STEEL BEND STUBS AT RISER POLE	DATE: 06-29-04 Page 2 of 2 C30-0320
--	---------------------------------------	---

WF# INFORMATION		CITY OF NAPERVILLE/DEPARTMENT OF PUBLIC UTILITIES - ELECTRIC			
WF# 59481 WASHINGTON ST. 75TH TO OLYMPUS DR. EAST SIDE	JOB 1 EU-73	CALL J.U.L.I.E. 48 HRS. PRIOR TO CONSTRUCTION			
WF# 59482 75TH WASHINGTON ST. TO OLYMPUS DR. NORTH SIDE	JOB 2 EU-73	PROJECT TITLE 75TH ST. AND WASHINGTON ST. ROAD IMPROVEMENTS	MAP NO.: -	CAD FILE: 0056270001D67.DWG	
WF# 59484 75TH WASHINGTON ST. TO CLYDE DR. SOUTH SIDE	JOB 3 EU-73	PROJECT DESCRIPTION TRENCH SECTION DETAILS	DRAWN BY: JK, PM	PROJECT NO.: EU12-06-03	EU73
WF# 59485 WASHINGTON ST. 75TH TO BAILEY RD. EAST SIDE	JOB 4 EU-73	DATE 4-01-08	ISSUED	WORK REQUEST NO. 56270	CHKD:
	ENGINEER RPS			APRV:	SBC:
	REVISION	1	2	3	COMPLETED BY:
				SCALE: NTS	SHEET 67 OF 73