

SUMMARY OF QUANTITIES

FA RITE	SECTION	COUNTY
---	05-P4096-00-PK	COOK
FED. ROAD DIST. NO.	ILLINOIS	CONTRACT NO. 63080

ITEM NO.	IDOT CODE NO.	PAY ITEM	UNIT	CODE TYPE Y024 QUANTITY
1	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	62
2	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	16
3	20200100	EARTH EXCAVATION	CU YD	545
4	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	500
6	21101825	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	7575
6	25000210	SEEDING, CLASS 2A	ACRE	2
* 7	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	140
* 8	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	140
* 9	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	140
* 10	25100800	EROSION CONTROL MAT	SQ YD	385
11	26000400	PERIMETER EROSION BARRIER	FOOT	4250
12	28000500	INLET AND PIPE PROTECTION	EACH	3
13	28100105	STONE RIPRAP, CLASS A3	SQ YD	25
14	28102630	STONE RIPRAP DITCH CHECKS	EACH	2
15	35100300	AGGREGATE BASE COURSE, TYPE A 4"	SQ YD	5
16	35100400	AGGREGATE BASE COURSE, TYPE A 5"	SQ YD	1633
17	35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	736
18	35100900	AGGREGATE BASE COURSE, TYPE A 10"	SQ YD	6690
19	40300100	BITUMINOUS MATERIALS PRIME COAT	GAL	701
20	40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0 N50	TON	883
21	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX 'C', N50	TON	767
22	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	116
23	42400800	DETECTABLE WARNING	SQ FT	10
24	44000100	PAVEMENT REMOVAL	SQ YD	1633
25	44000600	SIDEWALK REMOVAL	SQ FT	605
26	44002000	CONCRETE CURB REMOVAL	FOOT	150
27	44004400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	375
28	44004402	PAVEMENT REMOVAL (SPECIAL)	CU YD	2239
29	44213200	SAW CUTS	FOOT	220
30	50105200	REMOVE EXISTING CULVERTS	EACH	1
31	54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	4
32	54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	4
33	550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	939
34	55101200	STORM SEWER REMOVAL 24"	FOOT	155
35	55101600	STORM SEWER REMOVAL 36"	FOOT	48
36	60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	147
37	60204505	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	2
38	60221100	MANHOLE, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1
39	60221700	MANHOLE, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	1
40	60500040	REMOVING MANHOLES	EACH	2
41	60603800	COMBINATION CONCRETE CURB AND GUTTER TYPE B-6.12	FOOT	150
42	66410300	CHAIN LINK FENCE REMOVAL	FOOT	780
43	66400205	CHAIN LINK FENCE, 5'	FOOT	780
44	66410410	CHAIN LINK FENCE TO BE RELOCATED	FOOT	20
45	67100100	MOBILIZATION	L. SUM	1
46	70102835	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L. SUM	1
47	72000100	SIGN PANEL TYPE 1	SQ FT	5
* 48	78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ. FT.	220
* 49	78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	4525
* 50	78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	60
* 51	80400100	ELECTRIC SERVICE INSTALLATION	EACH	1
* 52	80400200	ELECTRIC UTILITY SERVICE CONNECTION	L. SUM	1
* 53	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1662
* 54	82102150	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 150 WATT	EACH	1
* 55	82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	14
* 56	82200700	AVIATION OBSTRUCTION WARNING LUMINAIRE	EACH	1
* 57	82500605	LIGHTING CONTROLLER PHOTOCELL RELAY	EACH	1
* 58	84200600	REMOVAL OF EXISTING LIGHT UNIT, NO SALVAGE	EACH	2
* 59	86300300	CONTROLLER CABINET TYPE III	EACH	1
* 60	A2003024	TREE, CELTIS OCCIDENTALIS PRAIRIE PRIDE (PRAIRIE PRIDE HACKBERRY), 3" CALIPER, BALLED AND BURLAPPED	EACH	9
* 61	A2006520	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	3
* 62	A2007120	TREE, QUERCUS RUBRA (RED OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	7
* 63	A2007624	TREE, TAXODIUM DISTICHUM (COMMON BALD CYRESS), 3" CALIPER, BALLED AND BURLAPPED	EACH	6
* 64	A2007824	TREE, TILIA AMERICANA (AMERICAN LINDEN/BASSWOOD), 3" CALIPER, BALLED AND BURLAPPED	EACH	2
65	X0322871	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	150
* 66	X0325713	GROUND ROD	EACH	4
67	X7240500	RELOCATE EXISTING SIGNS	EACH	3
68	XX003575	SITE DEMOLITION	L. SUM	1
69	XX003818	FURNISHING AND INSTALLING CONCRETE WHEEL STOPS	EACH	45
70	Z0007900	BUTT JOINTS	EACH	2
71	Z0018700	DRAINAGE STRUCTURE TO BE REMOVED	EACH	1
72	Z0019600	DUST CONTROL WATERING	UNIT	1
* 73	Z0036200	PAINT CURB	FOOT	50
74	Z0064800	SELECTIVE CLEARING	UNIT	1
75	XX007605	LIMESTONE SCREENING SURFACE 3" (NEW PATHS)	SQ YD	736
76	XX007606	LIMESTONE SCREENING SURFACE 2" (EXISTING PATHS)	SQ YD	3000
77	XX007607	GRAVEL PATH REPLACEMENT (FOR STORM SEWER INSTALLATION)	SQ YD	40
78	XX007608	GRAVEL PATH REPLACEMENT (FOR GRADING)	SQ YD	435
* 79	XX007609	GRASS PAVERS	SQ YD	100
* 80	XX007610	BASIN W/8" ROUND GRATE	EACH	1
* 81	XX007611	BASEBALL BACKSTOP	FOOT	120
* 82	XX007612	UNIT DUCT, 600 V, 2-1C NO. 8, 1/4" NO. 8 GROUND, 1" DIA. POLYETHYLENE	FOOT	219
* 83	XX007613	UNIT DUCT, 600 V, 4-1C NO. 8, 1/4" NO. 8 GROUND, 1" DIA. POLYETHYLENE	FOOT	67
* 84	XX007614	UNIT DUCT, 600 V, 3-1C NO. 8, 1/4" NO. 8 GROUND, 1" DIA. POLYETHYLENE	FOOT	120
* 85	XX007615	UNIT DUCT, 600 V, 2-1C NO. 3, 2-1C NO. 6, 1/4" NO. 3 GROUND, 1 1/2" DIA. POLYETHYLENE	FOOT	745
* 86	XX007616	UNIT DUCT, 600 V, 3-1C NO. 6, 1/4" NO. 8 GROUND, 1" DIA. POLYETHYLENE	FOOT	123
* 87	XX007617	UNIT DUCT, 600 V, 1-1C NO. 3, 1/4" NO. 3 GROUND, 1" DIA. POLYETHYLENE	FOOT	388
* 88	XX007618	LIGHT POLE, STEEL, 16'	EACH	7
* 89	XX007619	LIGHT POLE, STEEL, 10'	EACH	3
* 90	XX007620	UPLIGHT, VANDAL PROOF	EACH	1
* 91	XX007621	TIME CLOCK, ELECTRIC	EACH	1
* 92	XX007622	ELECTRIC METER	EACH	1

* DENOTES SPECIALTY ITEMS

DATE	BY	REVISIONS	DATE
05/23/08	JFG	PER IDOT COMMENTS	6-18-08
	JFG	PER IDOT COMMENTS	6-24-08
	JFG	PER IDOT COMMENTS	7-16-08
	JFG	PER IDOT COMMENTS	7-25-08
	JFG	PER IDOT COMMENTS	8-4-08

W-T CIVIL ENGINEERING, LLC.
CIVIL AND STRUCTURAL ENGINEERS

W-T

SPRING ROCK PARK
CENTRAL AVE & 47TH ST
WESTERN SPRINGS, IL

SUMMARY OF QUANTITIES

DATE: 05/23/08
SCALE: 1" = 50'
DRAWN: JFG
CHECK: TOA
JOB: CE06316
SHEET: 3 OF 26

FIELD ENGINEER: MARLIN SOLOMON 847-705-4407