

SCHEDULE OF QUANTITIES

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	*	VAR	66	4
FED. ROAD DIST. NO. 4		ILLINOIS	FED. AID PROJECT	

*** D4 SCOUR MITIGATION 2006**

SCHEDULE OF QUANTITIES			STRUCTURE NUMBER					
ITEM	UNIT		029-0002	029-0027	029-0053	062-0014	072-0037	078-0005
TREE REMOVAL (6-15 UNITS)	UNIT		0	22	0	0	0	0
EARTH EXCAVATION FOR STILLING BASIN	CU YD		418	0	0	0	0	0
CHANNEL EXCAVATION	CU YD		145	1056	1657	89	1403	20
SEEDING CLASS 3	ACRE		0.1	0.02	0.07	0.02	.17	0.02
EROSION CONTROL BLANKET	SQ YD		370	200	440	28	820	108
PERIMETER EROSION BARRIER	FOOT		39	25	0	0	422	0
STONE RIPRAP, CLASS A3	TON		0	0	0	0	341	0
STONE RIPRAP, CLASS A5	TON		155	159	718	550	2850	867
FILTER FABRIC	SQ YD		671	1242	2902	324	3717	700
GABIONS	CU YD		415	337	450	0	0	0
SLOPE MATTRESS 12"	SQ YD		356	624	2175	0	0	0
SUBBASE GRANULAR MATERIAL, TYPE C	TON		708	590	869	0	0	0
REMOVAL OF EXISTING STRUCTURES	EACH		0	0	2	0	0	0
REMOVAL AND REINSTALLATION OF EXISTING STEEL PLATE BEAM GUARD RAIL, TYPE A	EACH		0	0	0	50	0	0
DEWATERING STRUCTURE NO. 1	EACH		1	0	0	0	0	0
DEWATERING STRUCTURE NO. 2	EACH		0	1	0	0	0	0
DEWATERING STRUCTURE NO. 3	EACH		0	0	1	0	0	0
DEWATERING STRUCTURE NO. 4	EACH		0	0	0	1	0	0
DEWATERING STRUCTURE NO. 5	EACH		0	0	0	0	1	0
DEWATERING STRUCTURE NO. 6	EACH		0	0	0	0	0	1
GABION ANCHOR STAKE	EACH		239	102	148	0	0	0

QUANTITIES NOT OTHERWISE SHOWN

ITEM	UNIT	TOTAL	DESCRIPTION
TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	EACH	3	SEE GENERAL NOTE #8

ITEM	UNIT	TOTAL	LOCATION
SEEDING, CLASS 3	ACRE	1.0	JOBSITE
NITROGEN FERTILIZER NUTRIENT	POUND	90	JOBSITE
PHOSPHORUS FERTILIZER NUTRIENT	POUND	90	JOBSITE
POTASSIUM FERTILIZER NUTRIENT	POUND	90	JOBSITE
EROSION CONTROL BLANKET	SQ YD	1956	JOBSITE
TEMP. EROSION CONTROL SEEDING	POUND	100	JOBSITE
MOBILIZATION	L SUM	1	JOBSITE