

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	STRUCTURE 80% FEDERAL 20% STATE X081-2A															
20200100	EARTH EXCAVATION	CU YD	100	100															
25000210	SEEDING, CLASS 2A	ACRE	0.25	0.25															
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	23	23															
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	23	23															
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	23	23															
25100115	MULCH, METHOD 2	ACRE	0.25	0.25															
25100630	EROSION CONTROL BLANKET	SQ YD	466	466															
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	25	25															
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	28	28															
40600300	AGGREGATE (PRIME COAT)	TON	0.8	0.8															
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	15	15															
40600990	TEMPORARY RAMP	SQ YD	108	108															
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	30	30															
42001300	PROTECTIVE COAT	SQ YD	35	35															
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	356	356															
44000400	GUTTER REMOVAL	FOOT	93	93															
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	1															
50102400	CONCRETE REMOVAL	CU YD	2.0	2.0															
50300225	CONCRETE STRUCTURES	CU YD	2.0	2.0															
50300260	BRIDGE DECK GROOVING	SQ YD	497	497															
50300300	PROTECTIVE COAT	SQ YD	531	531															
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	4,770	4,770															
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	6,790	6,790															
50800515	BAR SPLICERS	EACH	153	153															
51500100	NAME PLATES	EACH	1	1															
52000110	PREFORMED JOINT STRIP SEAL	FOOT	64	64															
59000200	EPOXY CRACK INJECTION	FOOT	40	40															
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	5.8	5.8															
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	537.5	537.5															
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2															
63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	3	3															

LEGEND:
* SPECIALTY ITEMS

SHEET NO. 1 OF 2

FILE NAME =	USER NAME = SJS	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
...N10149\Quantities\SUMMOTY.DGN		DRAWN -	REVISED -			721	(115BR-1)BR	PIATT	32	3
Johnson, Depp & Gulesberry CONSULTING ENGINEERS Springfield, Illinois	PLOT SCALE = 20.0000' / IN.	CHECKED -	REVISED -							CONTRACT NO. 70433
	PLOT DATE = 06/17/2008 16:11:48	DATE -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.
						FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		