

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	60-(16B, 16-1B)	MADISON	62	2
STA. 155+50.00		TO STA. 168+61.00		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 76567				

GENERAL NOTES

1. TEMPORARY SEEDING AND MULCH SHALL BE COMPLETED ON A WEEKLY BASIS ON EXPOSED GROUND AND SHALL BE IN ACCORDANCE WITH SECTION 280 OF THE STANDARD SPECIFICATIONS EXCEPT THAT MULCH AND TEMPORARY SEEDING SHALL BE PAID FOR AS TEMPORARY EROSION CONTROL SEEDING AND NO OTHER PAYMENT WILL BE PERMITTED.
2. CLASS 4A SEEDING IS TO BE PLACED AS SOON AS EARTHWORK IS COMPLETED.
3. MULCH USED SHALL BE AS WEED SEED FREE AS POSSIBLE. NO EMULSIFIED ASPHALT WILL BE ALLOWED TO BE USED ON THE MULCH.
4. SEEDING SHALL BE PLACED ON ALL AREAS THAT ARE DISTURBED BY CONSTRUCTION OPERATIONS. NUTRIENTS AND MULCH, IF REQUIRED, SHALL BE APPLIED TO ALL SEEDED AREAS. THE SEEDING SHALL BE DONE ACCORDING TO ARTICLES 250 AND 251 OF THE STANDARD SPECIFICATION OR AS DIRECTED BY THE ENGINEER.
5. WHERE SECTION OR SUB-SECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL MONUMENTS OR OTHERWISE REFERENCE THEIR LOCATION. THE CONTRACTOR WILL BE RESPONSIBLE FOR HAVING AN AUTHORIZED SURVEYOR RE-ESTABLISH ANY SECTION OR SUB-SECTION MONUMENTS DESTROYED BY HIS OPERATIONS.
6. PROTECTIVE COAT SHALL BE APPLIED TO THE SURFACES OF NEW CONCRETE ACCORDING TO ARTICLES 420.21 AND/OR 503.19 OF THE STANDARD SPECIFICATIONS.
7. ONLY THOSE TREES DESIGNATED BY THE ENGINEER SHALL BE REMOVED. THE CONTRACTOR SHALL PROTECT ALL REMAINING TREES FROM DAMAGE DUE TO HIS OPERATIONS.
8. EROSION CONTROL MEASURES SHALL BE IN ACCORDANCE WITH IDOT SPECIFICATIONS. PLACEMENT SHALL BE ACCORDING TO THE SWPPP OR AS DIRECTED BY THE ENGINEER.
9. EXISTING ROAD SIGNS WHICH INTERFERE WITH CONSTRUCTION SHALL BE REMOVED OR RELOCATED AS SHOWN IN THE PLANS AND AS DIRECTED BY THE ENGINEER AFTER THE CONSTRUCTION IS COMPLETE, THE CONTRACTOR SHALL REPLACE THE SIGNS AS DIRECTED BY THE ENGINEER.
10. ALL ELEVATIONS REFER TO U.S.G.S. MEAN SEA LEVEL DATUM.
11. ABANDONED UNDERGROUND UTILITIES THAT CONFLICT WITH CONSTRUCTION SHALL BE DISPOSED OF OUTSIDE THE LIMITS OF THE RIGHT OF WAY ACCORDING TO ARTICLE 202.03 OF THE STANDARD SPECIFICATIONS AND AS DIRECTED BY THE ENGINEER.
12. ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUB-NUMBER LISTED IN THE INDEX OF SHEETS.
13. CONTRACTOR WILL NOT BE ALLOWED TO USE STRAW BALES FOR TEMPORARY EROSION CONTROL SYSTEMS (STD. 280001)
14. EXCEPT WHERE DESIGNATED OTHERWISE, THE DEPTHS AND OFFSETS OF ALL UTILITIES SHOWN ON PLAN SHEETS HAVE BEEN TAKEN FROM INFORMATION FURNISHED BY THE UTILITY OWNERS. THESE LOCATIONS MUST BE CONSIDERED APPROXIMATE.
15. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE TO BE GIVEN TO UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
 - AMEREN - UE (GAS & ELECTRIC)
 - AMERITECH (TELEPHONE)
 - ILLINOIS AMERICAN WATER CO. (JERSEY COUNTY RURAL WATER COMPANY INC.)
 - CHARTER COMMUNICATIONS (CABLE TV)
 - VILLAGE OF GODFREY (SAN. SEWER)

(MEMBERS OF J.U.L.I.E. (800) 892-0123 ARE INDICATED BY *. NON-J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.)
16. "SLIPPERY WHEN WET", "MUD ON PAVEMENT" AND "TRUCKS ENTERING AND LEAVING ROADWAY" SIGNS SHALL BE MADE AVAILABLE FOR USE AT THE DISCRETION OF THE ENGINEER FOR THE PROJECT. COST TO BE INCLUDED IN GRADING AND STRUCTURES AND WILL NOT BE PAID FOR SEPARATELY.
17. ALL WARNING SIGNS SHALL BE 48" FLUORESCENT ORANGE.

COMMITMENTS

1. TREE FELLING IS RESTRICTED BETWEEN SEPTEMBER 30 AND APRIL 1 DUE TO HABITAT FOR THE ENDANGERED INDIANA BAT.
2. IF ARCHAEOLOGICAL CLEARANCE HAS NOT BEEN OBTAINED FOR THE ENTIRE PROJECT, THE RESIDENT ENGINEER SHALL PROVIDE THE CONTRACTOR THOSE AREAS OF THE PROJECT WHICH HAVE BEEN CLEARED, AND IN WHICH THE CONTRACTOR MAY WORK. THE RESIDENT ENGINEER SHALL ALSO NOTIFY THE CONTRACTOR WHEN ADDITIONAL SITES BECOME AVAILABLE.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

GENERAL NOTES

SCALE: NO SCALE
DATE: 06-11-08

DRAWN BY: U.J.
CHECKED BY: M.A.R.