

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	60-(16B,16-16-1B)	MADISON	62	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	C000	X071-2A
20100500	TREE REMOVAL, ACRES	ACRE	1.9	1.9	
20200100	EARTH EXCAVATION	CU YD	6360	6360	
20300100	CHANNEL EXCAVATION	CU YD	1351	1351	
20400800	FURNISHED EXCAVATION	CU YD	11603	11603	
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	508		508
25000312	SEEDING, CLASS 4A	ACRE	3.4	3.4	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	6.8	6.8	
25100115	MULCH, METHOD 2	ACRE	3.4	3.4	
25100630	EROSION CONTROL BLANKET	SQ YD	853	853	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1020	1020	
28000300	TEMPORARY DITCH CHECKS	EACH	5	5	
28000400	PERIMETER EROSION BARRIER	FOOT	450	450	
28100107	STONE RIPRAP, CLASS A4	SQ YD	2480	1123	1357
28200200	FILTER FABRIC	SQ YD	2480	1123	1357
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	279	279	
42001300	PROTECTIVE COAT	SQ YD	713	713	
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	434	434	
50105220	PIPE CULVERT REMOVAL	FOOT	1		1
50200100	STRUCTURE EXCAVATION	CU YD	107.5		107.5
50300100	FLOOR DRAINS	EACH	10		10
50300225	CONCRETE STRUCTURES	CU YD	119.4		119.4
50300255	CONCRETE SUPERSTRUCTURE	CU YD	286.7		286.7
50300260	BRIDGE DECK GROOVING	SQ YD	748		748
50300300	PROTECTIVE COAT	SQ YD	888		888
50500505	STUD SHEAR CONNECTORS	EACH	3786		3786
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	77160		77160
50800515	BAR SPLICERS	EACH	214		214
51201600	FURNISHING STEEL PILES HP12X53	FOOT	498		498
51201610	FURNISHING STEEL PILES HP12X63	FOOT	681		681
51202395	DRIVING PILES	FOOT	1179		1179
51203600	TEST PILE STEEL HP12X53	EACH	1		1
51203610	TEST PILE STEEL HP12X63	EACH	1		1
51204650	PILE SHOES	EACH	19		19
51500100	NAME PLATES	EACH	2		2
54200229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	25	25	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	222		222
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	330		330
67100100	MOBILIZATION	L SUM	1	0.5	0.5

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	C000	X071-2A
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
X0795800	COARSE AGGREGATE	TON	58	58	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1

PLOT DATE = 6/18/2008
 FILE NAME = c:\projects\adit1365\consult\summary of quantities.dgn
 PLOT BY = adit / jn
 REFERENCE = REF#