CONTRACT NO. 94533

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	1YRS, 2ZRS-1	CRAWFORD	378	29
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

PIPE CULVERT SCHEDULE - CONTINUED

LOCATION		TYPE	TRENCH BACKFILL	PIPE CULVERTS															PRECAST REINFORCED CONCRETE FLARED END SECTIONS						END SECTIONS									PIPE TEES			INLETS
				RCCP						CLASS D																								375 PIPE WITH 300 RISER	600 PIPE WITH 375 RISER	750 PIPE WITH 375 RISER	TYPE A, TY 8 GRATE
STATION	RT/LT /AR		CUBIC METER	TYPE 1 375 METER	TYPE 1 450 METER	TYPE 1 600 METER	TYPE 1 750 METER	TYPE 1 900 METER	TYPE 1 1500 METER	TYPE 1 300 METER	TYPE 1 375 METER	TYPE 1 450 METER	TYPE 1 525 METER	TYPE 1 600 METER	TYPE 1 675 METER	TYPE 1 750 METER	TYPE 1 900 METER	TYPE 1 1050 METER	375 EACH	450 EACH	600 EACH	750 EACH	900 EACH	1500 EACH	300 EACH	375 EACH	450 EACH	525 EACH	600 EACH	675 EACH	750 EACH	900 EACH	1050 EACH	EACH	EACH	EACH	EACH
STA 12+138.500	AR	PIPE CULVERTS	17.69					19.51															2														
STA 12+353.000	LT	PIPE CULVERTS										16.15															2										
STA 12+353.000	RT	PIPE CULVERTS										16.15															2										
STA 12+991.000	LT	PIPE CULVERTS										13.72															2										
STA 13+058.500	LT	PIPE CULVERTS									14.94															2											
STA 13+084.000	RT	PIPE CULVERTS									17.98															2											
STA 13+097.000	LT	PIPE CULVERTS	3.87	14.94															2																		
STA 13+127.500	LT	PIPE CULVERTS									29.26															2											
STA 13+163.500	LT	PIPE CULVERTS									15.24															2											
STA 13+205.500	LT	PIPE CULVERTS									14.94															2											
STA 13+246.000	LT	PIPE CULVERTS									16.46																										
STA 13+328.500	LT	PIPE CULVERTS									13.72															2											
STA 13+480.000	LT	PIPE CULVERTS										13.11															2										
STA 13+490.500	RT	PIPE CULVERTS									12.19															2											
STA 13+527.500	RT	PIPE CULVERTS									13.11															2											
STA 13+602.700	RT	PIPE CULVERTS										12.50															1										
STA 13+615.000	RT	PIPE CULVERTS										12.50															1										
STA 13+672.000	RT	PIPE CULVERTS												21.64															2								
STA 13+750.400	RT	PIPE CULVERTS												18.90															2								
STA 13+802.800	RT	PIPE CULVERTS												16.76															2								
STA 13+803.800	LT	PIPE CULVERTS														14.33															2						
STA 13+981.300	LT	PIPE CULVERTS												17.37															2								
STA 14+077.100	RT	PIPE CULVERTS												17.37															2								
STA 14+217.800	RT	PIPE CULVERTS									12.19															2											
STA 14+221.800	LT	PIPE CULVERTS									16.15															2											
STA 14+234.800	RT	PIPE CULVERTS									10.36															2											
STA 14+242.400	LT	PIPE CULVERTS									17.68															2											
STA 14+447.300	LT	PIPE CULVERTS									18.59																										
STA 14+447.300	RT	PIPE CULVERTS	8.40	21.95															2																		
STA 14+454.300	LT	PIPE CULVERTS									2.44					28.28										1					2					1	
STA 14+461.300	LT	PIPE CULVERTS									19.81																										
STA 14+553.800	LT	PIPE CULVERTS														15.24															2						
STA 14+600.800	LT	PIPE CULVERTS															13.72															2					
STA 14+629.900	RT	PIPE CULVERTS	5.93		17.37															2																	
STA 14+630.300	LT	PIPE CULVERTS															14.63															2					
STA 14+659.300	LT	PIPE CULVERTS															10.36															2					
STA 14+664.800	RT	PIPE CULVERTS	6.27		17.68															2																	
STA 14+696.800	RT	PIPE CULVERTS											16.15															2									
STA 14+711.600	LT	PIPE CULVERTS	7.34					12.80															2														
STA 14+725.800	RT	PIPE CULVERTS												12.80															2								
STA 14+756.800	LT	PIPE CULVERTS																11.58															2				
STA 14+763.300	RT	PIPE CULVERTS												15.85															2								
STA 14+770.800	LT	PIPE CULVERTS																12.50															2				
STA 14+861.800	RT	PIPE CULVERTS										19.51															2										
STA 14+886.300	RT	PIPE CULVERTS									15.24															2											
STA 14+926.300	LT	PIPE CULVERTS										12.80															2										
STA 14+926.300	RT	PIPE CULVERTS									12.50															2											
STA 14+981.900	LT	PIPE CULVERTS									12.80															2											
STA 15+232.300	LT	PIPE CULVERTS													17.07															2							
STA 15+321.000	LT	PIPE CULVERTS	6.72			16.46															2																
STA 15+353.800	LT	PIPE CULVERTS												9.45															2								
STA 15+450.800	RT	PIPE CULVERTS												13.41															2								
STA 15+454.800	LT	PIPE CULVERTS	7.01			16.76															2																
STA 15+509.800	LT	PIPE CULVERTS	8.20			17.98															2																
STA 15+511.800	RT	PIPE CULVERTS												10.67															2								
URBAN																																					
STA 15+595.800	LT	PIPE CULVERTS										17.07															2										

CONTINUED

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

PIPE CULVERT SCHEDULE

SCALE

DRAWN BY KOJ

DATE APRIL 18, 2008

CHECKED BY RGH

H. M. & G. NO. 4420

PLOT DATE = 4/18/2008
FILE NAME = H:\4420\70027_sch_pipe culverts.dgn