PIPE CULVERT SCHEDULE - CONTINUED

LOCATION		TYPE	TRENCH BACKFILL	PIPE CULVERTS															PRECAST REINFORCED CONCRETE FLARED END SECTIONS						END SECTIONS									PIPE TEES			INLETS
				RCCP						CLASS D																								375 PIPE WITH 300 RISER	600 PIPE WITH 375 RISER	750 PIPE WITH 375 RISER	TYPE A, TY 8 GRATE
				TYPE 1	TYPE 1	TYPE 1	TYPE 1	TYPE 1	TYPE 1	TYPE 1	TYPE 1	TYPE 1	TYPE 1	TYPE 1	TYPE 1	TYPE 1	TYPE 1	TYPE 1																			
STATION	RT/LT /AR		CUBIC METER	375 METER	450 METER	600 METER	750 METER	900 METER	1500 METER	300 METER	375 METER	450 METER	525 METER	600 METER	675 METER	750 METER	900 METER	1050 METER	375 EACH	450 EACH	600 EACH	750 EACH	900 EACH	1500 EACH	300 EACH	375 EACH	450 EACH	525 EACH	600 EACH	675 EACH	750 EACH	900 EACH	1050 EACH	EACH	EACH	EACH	EACH
STA 15+660.800	LT	PIPE CULVERTS										16.76															2										
STA 15+661.300	RT	PIPE CULVERTS	3.06	16.14															2																		
STA 15+723.100	RT	PIPE CULVERTS									16.15															2											
STA 15+870.300	RT	PIPE CULVERTS										9.75															2										
STA 15+871.400	LT	PIPE CULVERTS	1.39		12.19															2																	
STA 15+890.000	LT	PIPE CULVERTS										8.84															2										
STA 15+931.300	RT	PIPE CULVERTS										11.28															2										
STA 15+960.300	LT	PIPE CULVERTS										17.37															2										
TOTALS			169.99	126.18	65.53	118.42	32.30	55.47	17.37	2.44	924.5	592.54	93.26	371.89	36.58	89.85	75.60	24.08	12	8	14	4	6	2	1	104	82	14	48	6	12	14	4	1	1	1	2
TOTALS ROUNDED FOR SUMMARY SHEET			170	126.5	66.0	118.5	32.5	55.5	17.5	2.5	924.5	593.0	93.5	372.0	37.0	90.0	76.0	24.5	12	8	14	4	6	2	1	104	82	14	48	6	12	14	4	1	1	1	2

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

PIPE CULVERT SCHEDULE

SCALE

DRAWN BY KOJ

DATE APRIL 18, 2008

CHECKED BY RGH

H. M. & G. NO. 4420

PLOT DATE = 4/18/2008
FILE NAME = H:\4420\70027_sch_pipe culverts.dgn