

F&P NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
793 9392	08-00025-00-RL 07-00025-01-WR	MADISON	127	7
STA.		TO STA.		

CONTRACT NO. 97352

CURB, GUTTER, & SIDEWALK SCHEDULE											
STATION	TO	STATION	GUTTER REMOVAL	COMB. CONC. CURB & GUTTER REMOVAL	SIDEWALK REMOVAL	CONCRETE GUTTER, TYPE A	CONCRETE GUTTER, TYPE B	COMB. CONC. CURB & GUTTER TYPE B6.24	COMB. CONC. CURB & GUTTER TYPE B6.18	PORTLAND CEMENT CONCRETE SIDEWALK, 4"	DETECTABLE WARNINGS
			FEET	FEET	SQ FT	FEET	FEET	FEET	FEET	FEET	SQ FT
US 40											
240+96.98	TO	244+37.71 RT						340.81			
TROY-O'FALLON ROAD											
100+41.12	TO	104+05.54 LT						456.04			
100+48.01	TO	101+47.26 LT		153.09							
100+52.65	TO	101+65.81 RT		152.90							
100+57.01	TO	107+56.45 RT						714.03			
101+47.26	TO	107+53.93 L	603.07								
101+65.81	TO	105+41.63 R	378.44								
103+43.40 RT			11.66								
103+48.01 LT			13.39								
104+05.54	TO	104+75.93 LT					69.78				
105+05.90	TO	105+42.75 LT					36.43				
105+73.42	TO	106+16.57 LT					42.77				
106+47.61	TO	106+16.57 LT					77.03				
115+52.68	TO	116+03.37 LT				49.39					
116+28.70	TO	116+60.12 LT				30.62					
TURTLE CREEK											
9+17.29	TO	9+83.71 LT		63.46				74.80			
9+17.29	TO	9+82.73 RT		75.88	242.11			82.17	278.69	8.00	
9+28.21	TO	9+71.44 LT			67.69				197.49	8.00	
MEADOWBROOKE DRIVE											
9+42.12	TO	9+80.00 LT		44.46	105.33			50.01	147.90	8.00	
9+42.12	TO	9+77.00 RT		46.88	87.97			42.47	148.25	8.00	
FAIR OAKS DRIVE											
10+20.11	TO	10+62.05 LT		40.98				46.67			
10+20.11	TO	10+62.05 RT		40.52	68.91			54.18	147.51	8.00	
10+30.78	TO	10+59.66 LT			65.36				161.05	8.00	
TOTAL			1,006.56	618.17	637.37	80.01	226.01	1,510.88	350.30	1,080.89	48.00

EARTHWORK SCHEDULE						
STATION	TO	STATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE(+), SHORTAGE (-)
			CU YD	CU YD	CU YD	CU YD
US 40						
236+99.46	TO	254+82.64	830	622.5	72	550.5
TROY-O'FALLON ROAD						
100+26.33	TO	131+47.11	1,609	1,206.75	6,417	-5,210.25
TOTAL			2,439	1,829.25	6,489	-4,659.75

PERIMETER EROSION BARRIER			
STATION	TO	STATION	PERIMETER EROSION BARRIER
			FEET
TROY-O'FALLON ROAD			
108+16.26	TO	108+83.20 LT	64.51
108+86.44	TO	110+50.00 RT	176.20
109+00.00	TO	109+28.13 LT	32.49
111+00.00	TO	111+53.58 LT	56.92
111+18.88	TO	111+60.35 RT	47.03
111+74.48	TO	114+99.97 LT	310.90
111+79.45	TO	115+27.10 RT	374.82
117+00.00	TO	119+40.05 RT	248.06
117+50.00	TO	119+44.16 LT	191.36
119+54.53	TO	121+26.04 LT	172.52
128+68.44	TO	131+00.00 LT	242.51
TOTAL			1,917.32

INLET & PIPE PROTECTION			
STATION	OFFSET		NUMBER OF APPLICATIONS
			EACH
US 40			
241+06.51	38.53'	RT	1
242+53.38	39.40'	RT	1
242+53.38	32.50'	RT	1
244+44.10	33.57'	RT	1
252+36.39	28.10'	RT	1
252+77.39	27.65'	RT	1
TROY-O'FALLON ROAD			
102+51.29	25.00'	RT	1
102+74.70	25.00'	LT	1
103+43.20	25.42'	RT	1
103+46.78	23.08'	LT	1
104+66.02	21.33'	LT	1
106+67.78	35.09'	RT	1
107+02.64	34.64'	RT	1
107+59.32	35.52'	RT	1
107+83.29	33.53'	RT	1
108+32.29	52.68'	RT	1
108+36.86	36.63'	RT	1
108+84.68	52.23'	RT	1
108+93.30	68.87'	RT	1
109+14.44	58.81'	RT	1
115+18.56	53.56'	RT	1
115+62.38	49.84'	RT	1
119+49.36	58.79'	LT	1
121+15.24	44.41'	LT	1
121+45.85	37.71'	LT	1
125+09.25	35.00'	RT	1
125+15.05	32.13'	LT	1
125+28.56	41.23'	RT	1
125+39.12	49.59'	LT	1
125+76.95	50.80'	LT	1
125+87.81	39.43'	RT	1
126+03.09	36.66'	LT	1
128+24.70	37.67'	LT	1
TOTAL			33

EROSION CONTROL BLANKET			
STATION	TO	STATION	EROSION CONTROL BLANKET
			SQ. YD.
US 40			
239+50.20	TO	241+16.46 RT	245.22
252+68.70	TO	253+71.83 RT	146.90
TROY-O'FALLON ROAD			
106+94.69	TO	107+66.87 RT	124.33
122+00.00	TO	125+13.26 RT	520.21
TOTAL			1,036.66

CLASS SI CONCRETE						
STATION	TYPE A GUTTER ENTRANCE (CU. YD.)		TYPE B GUTTER ENTRANCE (CU. YD.)		TYPE B GUTTER OUTLET (CU. YD.)	
	INLET (CU. YD.)	OUTLET (CU. YD.)	INLET (CU. YD.)	OUTLET (CU. YD.)	INLET (CU. YD.)	OUTLET (CU. YD.)
TROY-O'FALLON ROAD						
104+91.01 LT				2.09		
105+58.05 LT				2.20		
106+32.00 LT				2.24		
107+41.07 LT				2.22		
107+57.44 TO 107+82.10 LT					1.90	
115+15.79 TO 115+52.68 LT			4.57			
116+15.12 LT	3.72					
116+60.12 TO 116+72.42 LT		0.92				
TOTAL			3.72	0.92	4.57	1.90

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	
STATION	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT SQ. YD.
US 40	
236+99.46 TO 237+29.46	73.32
241+34.31 LT	37.65
243+15.54 LT	43.46
248+63.33 LT	43.46
254+52.64 TO 254+82.64	69.66
SOUTH MAIN ST.	
99+79.71 TO 100+09.71	382.61
TROY-O'FALLON RD.	
131+17.11 TO 131+47.11	79.87
TOTAL	

PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	
STATION	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT SQ. YD.
US 40	
237+23.11 RT	64.49
247+93.02 RT	36.01
TURTLE CREEK	
9+17.29 TO 9+27.29	62.03
MEADOWBROOKE DR.	
9+42.12 TO 9+62.12	94.17
FAIR OAKS DR.	
10+42.05 TO 10+62.05	63.28
TOTAL	

REVISIONS	
NAME	DATE

SCHEDULES

U.S. 40 TROY-O'FALLON ROAD IMPROVEMENTS
CITY OF TROY
MADISON COUNTY, ILLINOIS

P:\050162D\dwg\050162SCH.DWG 4/16/2008 9:05:04 AM CDT