

FWP NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
793 9392	05-00025-00-IL 07-00025-01-MR	MADISON	127	8
STA.		TO STA.		

CONTRACT NO. 97352

SIGNAGE SCHEDULE						
STATION	OFFSET (FEET)	SIGN TYPE	SIZE	SIGN PANEL - TYPE 1	WOOD SIGN SUPPORT	
				SQ. FT.	FOOT	
MAST ARM MOUNTED						
SOUTHBOUND		R10-12	24"X30"	5.00	-	
NORTHBOUND		R10-12	24"X30"	5.00	-	
US 40						
241+91.88	37.33	RT	R3-1100	24"X24"	4.00	15.5
TROY-O'FALLON ROAD						
103+01.78	29.04	LT	R3-1100	24"X24"	4.00	12.0
104+22.69	29.67	RT	R3-9B	24"X36"	6.00	13.0
113+91.54	33.00	LT	R3-9B	24"X36"	6.00	15.0
118+54.25	33.00	RT	R3-9B	24"X36"	6.00	15.0
132+08.74	33.00	LT	R3-9B	24"X36"	6.00	15.0
				TOTAL	42	85.5

RAISED REFLECTIVE PAVEMENT MARKER							
LOCATION	ONE-WAY CRYSTAL	ONE-WAY AMBER	TWO-WAY AMBER				
	EACH	EACH	EACH	EACH			
US 40							
236+99.46 TO 244+34.46		20	8				
241+39.46 TO 244+34.46	15						
245+57.64 TO 250+42.64	13						
245+57.64 TO 254+82.64		20	13				
SOUTH MAIN STREET							
96+37.11 TO 99+74.40		8					
98+54.40 TO 99+74.40	4						
TROY-O'FALLON ROAD							
100+61.83 TO 102+78.81	10						
124+01.66 TO 127+21.11	6						
100+61.83 TO 131+47.11		20	115				
				TOTAL	48	68	136

PAVEMENT MARKING REMOVAL			
STATION TO STATION	DESCRIPTION	PAVEMENT MARKING REMOVAL	
		SQ FT	
SOUTH MAIN STREET			
96+37.11 TO 99+79.71	4" CENTERLINE	226.12	
96+63.54 TO 98+58.55 RT	4" SKIP-DASH	15.84	
98+58.55 TO 99+70.97 RT	4" TURN LANE	37.10	
98+79.88 TO 99+53.36 RT	LETTERS & SYMBOLS	84.60	
99+70.97 TO 99+79.93 RT	8" ENVELOPE	12.70	
99+78.20 TO 99+79.93 RT	12" DIAGONALS	2.46	
		TOTAL	378.82

THERMOPLASTIC PAVEMENT MARKINGS										
STATION	DESCRIPTION	4" YELLOW LINE	4" WHITE LINE	6" WHITE LINE	8" WHITE LINE	12" YELLOW LINE	12" WHITE LINE	24" WHITE LINE	LETTERS AND SYMBOLS	
		FEET	FEET	FEET	FEET	FEET	FEET	FEET	SQ FT	
US 40										
236+99.46 TO 244+34.46	DOUBLE CENTERLINE	2300.07								
236+99.46 TO 244+07.74 LT	EDGE LINE		708.33							
236+99.46 TO 244+37.81 RT	EDGE LINE		738.93							
237+48.83 TO 241+08.71	DIAGONALS					95.31				
239+71.89 TO 241+91.88 RT	2'-6" SKIP DASH		52.00							
241+39.46 TO 244+50.41 RT	LANE LINE		310.96							
241+87.57 TO 244+16.73	TURN ARROWS								93.6	
241+91.88 TO 244+52.49 RT	LANE LINE		260.62							
244+34.46	STOP BAR									
244+50.41 RT	STOP BAR							11.00		
244+52.49 TO 244+77.73	PAINTED MEDIAN				88.07		43.45			
244+65.43 RT	STOP BAR							18.00		
245+44.10 LT	STOP BAR							25.46		
245+44.10 TO 250+42.64 LT	LANE LINE		498.54							
245+52.22 TO 254+82.64 LT	EDGE LINE		933.13							
245+57.64	STOP BAR							11.00		
245+57.64 TO 254+82.64	DOUBLE CENTERLINE	2680.03								
246+03.79 TO 249+94.72	TURN ARROWS								46.8	
246+25.38 TO 254+82.64 RT	EDGE LINE		857.46							
250+88.39 TO 254+21.76	DIAGONALS					94.63				
SOUTH MAIN STREET										
96+37.11 TO 99+74.40	DOUBLE CENTERLINE	1052.20								
96+37.11 TO 99+97.04 LT	EDGE LINE		372.27							
96+37.11 TO 100+11.58 RT	EDGE LINE		419.75							
96+75.39 TO 98+36.10	DIAGONALS					35.84				
97+75.40 TO 98+54.40 RT	2'-6" SKIP DASH		20.00							
98+54.40 TO 99+91.83 RT	LANE LINE		137.43							
98+79.09 TO 99+63.00 RT	TURN ARROWS								84.6	
99+74.40 RT	STOP BAR							10.00		
99+91.83 RT	STOP BAR							26.03		
TROY-O'FALLON ROAD										
100+42.63 TO 100+80.55 LT	PAINTED MEDIAN				133.72		81.81			
100+43.79 TO 131+47.11 LT	EDGE LINE		3073.73							
100+56.36 LT	STOP BAR							18.00		
100+61.83 LT	STOP BAR							12.00		
100+61.83 TO 102+00.63	LANE LINE		138.80							
100+80.55 TO 102+78.81 LT	LANE LINE		198.26							
100+85.63 RT	STOP BAR							12.00		
100+85.63 TO 102+00.63 RT	DOUBLE CENTERLINE	230.00								
101+02.04 TO 126+99.37	TURN ARROWS								405.6	
102+00.63 TO 123+41.66 RT	TWTL	2141.03								
102+00.63 TO 123+41.66 RT	10'-30' SKIP DASH	540.00								
102+60.63 TO 123+41.66 LT	TWTL	2081.03								
102+60.63 TO 123+41.66 LT	10'-30' SKIP DASH	520.00								
102+78.81 TO 104+98.81	2'-6" SKIP DASH		54.00							
100+56.69 TO 131+47.11 RT	EDGE LINE		2924.08							
124+01.66 TO 125+16.66 RT	LANE LINE		115.00							
124+01.66 TO 125+16.66 LT	DOUBLE CENTERLINE	230.00								
126+06.11 TO 127+21.11 LT	LANE LINE		115.00							
126+06.11 TO 127+21.11 RT	DOUBLE CENTERLINE	230.00								
127+21.11 TO 131+47.11	DOUBLE CENTERLINE	1655.25								
127+21.11 TO 131+47.11	DIAGONALS					96.03				
TURTLE CREEK										
9+65.28 RT	STOP BAR							25.39		
9+69.28	CROSS WALK			60.93						
9+75.28	CROSS WALK			75.32						
MEADOWBROOKE DRIVE										
9+62.00 RT	STOP BAR							26.28		
9+66.00	CROSS WALK			57.83						
9+72.00	CROSS WALK			68.92						
FAIR OAKS DRIVE										
10+28.00	CROSS WALK			55.09						
10+34.00	CROSS WALK			44.00						
10+38.00 LT	STOP BAR							19.36		
		TOTAL	13,659.61	11,928.29	362.09	221.79	321.81	196.29	154.49	630.6

REVISIONS	
NAME	DATE

SCHEDULES

U.S. 40 TROY-O'FALLON ROAD IMPROVEMENTS  
CITY OF TROY  
MADISON COUNTY, ILLINOIS