CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE											
				90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE
				ROADWAY	S.N. 016-1000 S.N. 016-1001	S.N. 016-1005	S.N. 016-2455	S.N. 016-2457	S.N. 016-0483	S.N. 016-1026	S.N. 016-0486	S.N. 016-0488	SAFETY	SIGN STRUCTURES	DRAINAGE
				0004	0014	0014	0014	0014	0014	0014	0014	0014	0021	0040	0044
				URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
* 72000100	SIGN PANEL - TYPE 1	SQ FT	260										260		
* 72000200	SIGN PANEL - TYPE 2	SQ FT	440										440		
* 72000300	SIGN PANEL - TYPE 3	SQ FT	987										987		
* 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	5										5		
* 72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	21										21		
* 72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	119										119		
* 72400320	REMOVE SIGN PANEL - TYPE 2	SQ FT	203										203		
* 72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	364										364		
* 72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	6157										6157		
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	225										225		
* 73000100	WOOD SIGN SUPPORT	FOOT	304										304		
* 73300100	OVERHEAD SIGN STRUCTURE - SPAN, TYPE 1-A (4'-0" X 4'-6")	FOOT	152											152	
* 73400100	CONCRETE FOUNDATIONS	CU YD	12.6											12.6	
* 73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	17.9											17.9	

14

* SPECIALTY ITEM

Rev.

FILE NAME =	DESIGNED - AAA	REVISED -	
...\General\D160J16-sht-SQ0-11.dgn	DRAWN - TMB	REVISED -	
USER NAME = tblank	CHECKED - JMM	REVISED -	
PLOT DATE = 6/23/2014	DATE - 6/23/2014	REVISED -	

benesch engineers · scientists · planners

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 11 OF 21 SHEETS STA. TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
372/373	2013-0388-R	COOK	821	14

CONTRACT NO. 60J16

ILLINOIS FED. AID PROJECT