	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE											
					90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE
					ROADWAY	S.N. 016-1000 S.N. 016-1001	S.N. 016-1005	S.N. 016-2455	S.N. 016-2457	S.N. 016-0483	S.N. 016-1026	S.N. 016-0486	S.N. 016-0488	SAFETY	SIGN STRUCTURES	DRAINAGE
					0004	0014	0014	0014	0014	0014	0014	0014	0014	0021	0040	0044
					URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
•	81702190	ELECTRIC CABLE IN COUNDUIT, 600V(XLP-TYPE USE) 1/C NO. 4/C	FOOT	525										525		
•	81800300	AERIAL CABLE, 3-1/C NO.2 WITH MESSENGER WIRE	FOOT	589										589		
•	82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	101										101		
•	82107200	UNDERPASS LUMINAIRE, 100 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	8										8		
•	83050715	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 6 FT. DAVIT ARM	EACH	16										16		
•	83050825	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. DAVIT ARM	EACH	83										83		
•	83057475	LIGHT POLE, WOOD, 90 FOOT, CLASS 3, WITH 15FT MAST ARM	EACH	2										2		
•	83600365	LIGHT POLE FOUNDATION, METAL, 15" BOLT CIRCLE, 10"X8'	EACH	83										83		
•	83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	83										83		
•	84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	1										1		
•	84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	100										100		
•	84200804	REMOVAL OF POLE FOUNDATION	EACH	78										78		
•	84301200	REMOVAL OF NAVIGATION OBSTRUCTION WARNING LIGHTING SYSTEM	L SUM	1										1		
•	84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	2										2		

• SPECIALTY ITEM

FILE NAME = ...\General\D16BJ16-sht-SCD-15.dgn	DESIGNED - AAA	REVISED -
	DRAWN - TMB	REVISED -
USER NAME = tblank	CHECKED - JMM	REVISED -
PLOT DATE = 6/23/2014	DATE - 6/23/2014	REVISED -

benesch engineers · scientists · planners

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET 15 OF 21 SHEETS | STA. | TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
372/373	2013-038B-R	COOK	821	18
		CONTRACT NO. 60J16		
	ILLINOIS FED. AID PROJECT			