



- NOTES:**
- CONTRACTOR SHALL REMOVE THE EXISTING "LB" FITTING, CONDUIT NIPPLE, AND CONDUIT RUNNING DOWN TO THE GROUND. THE COSTS FOR THIS REMOVAL WORK SHALL BE INCLUDED IN THE COST OF THE PROPOSED JUNCTION BOX. CONTRACTOR SHALL THEN INSTALL THE PROPOSED STAINLESS STEEL JUNCTION BOX WITH NEW 2" DIA. PVCC RGC NIPPLE AND 2 1/2" DIA. PVCC RGC DOWN TO THE GROUND.
 - CONTRACTOR SHALL REMOVE THE EXISTING CABLES FROM THE CONDUIT PRIOR TO INSTALLATION OF THE PROPOSED CABLES. REMOVAL OF THE EXISTING CABLES SHALL BE PAID FOR UNDER PAY ITEM "REMOVE ELECTRIC CABLE FROM CONDUIT" FOR EACH CABLE REMOVED.

FILE NAME =	DESIGNED - GRR	REVISED -
...\\D160J16-sht-IL171-prlight-SB-06.dgn	DRAWN - JLW	REVISED -
USER NAME = tblank	CHECKED - GHT	REVISED -
PLOT DATE = 8/7/2014	DATE - 6/23/2014	REVISED -



**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

PROPOSED LIGHTING PLAN	
IL 171	
SCALE:	SHEET 19 OF 49 SHEETS STA. 68+00.00 TO STA. 82+00.00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
372/373	2013-038B-R	COOK	821	218
CONTRACT NO. 60J16			ILLINOIS FED. AID PROJECT	